TRANSMITTAL NO. 81
WESTMINSTER COMPANY

SECTION 15400 - PARAGRAPH 2.4.1

UNACCOMPANIED ENLISTED PERSONNEL HOUSING MARINE CORPS BASE, CAMP LEJEUNE, NC

CONTRACT No. N62470-82-C-2244

TRANSMITTAL NO. 81 WESTMINSTER COMPANY

SECTION 15400 - PARAGRAPH 2.4.1

ITEM #1

DISAPP

DEVIATION FOR WATER CLOSETS

AMYDIV REVIEWER

"It is hereby certified that the (material) (equipment) shown and marked in this submittal, shop drawings, catalog cut(s), etc., and approved/proposed to be incorporated into Contract Number N62470-82-C-2244, is in compliance with the contract drawings and specifications, and can be installed in the allocated space, and is ___ approved for use ___ submitted for Government * approval. While Date 6/2/84

Authorized Reviewer

Signature CQC Rep

DEVIATION: APPROVED

DISAPPROVED

LANTDIV REVIEWER

DATE

PAB 456

MAYAL	ATLANTIC DIVISION
	MALL IN SEMGINE FROM
	NORFOLK, VIRGINIA 23511

APPROVED AS MODES
DISAPPROVED

SUBJECT TO THE REQUIREMENTS OF


APPROVAL OF A SUPERITAL DOLS NOT INCLUDE APPROVAL OF A SUPERITAL DOLS NOT INCLUDE APPROVAL OF ANY DE MATION FROM THE CONTRACT REQUIREMENTS UNLESS THE CONTRACTOR CALLS ATTENDED TO AND SUPPORTS THE DEVIATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING PROPER PHYSICAL DIMENSION. A MEIGHTS, COORDINATION OF TRADES, ETC., AS REQUIRED.

EMENER 1783 406 DATE OF 17-85

FOR OFFICER IN CHARGE OF CONSTRUCTION



825 S 17th Street Wilmington, NC 28401 Phone: (919) 343-1510 Reply to P O Box 3037 Wilmington, NC 28406



May 16, 1985

Mr. Roger McLendon Westminister Co. P.O. Box 1167 Jacksonville, NC 28540

RE: Water Closet, P-1 2.4.1

UEPH Project

Contract: N62470-82-C-224

Dear Roger,

Per your request, please find enclosed notorized letters of compliance covering the above mentioned water closet.

As I had mentioned in my letter of March 8, 1985, I am unaware of any plumbing fixture manufacturer who offers a floor mounted, rear outlet flush valve type closet which will cleanse on less water than this particular unit.

Your prompt attention in submitting this for approval will be greatly appreciated.


Sincerely,

Chip Duvis

President/General Manager


Enclosures

CD: mw





825 S 17th Street Wilmington, NC 28401 Phone (919) 343-1510 Reply to P O Box 3037 Wilmington, NC 28406



March 8, 1985

Mr. Roger Mclendon Westminister Co. P.O. Box 1167 Jacksonville, NC 28540

RE: Water Closet, P-1, 2.4.1

UEPH Project

Contract: N62470-82-C-224

Dear Roger,

In reference to the above mentioned water-closet as submitted for this project, it has come to my attention that this closet, K-4486-ET, requires between 4½ and 5 gallons per flushing cycle to properly cleanse.

Neither myself or Kohler company are aware of any fixture manufacturer who offers a floor mounted, back outlet flush valve type closet bowl which operates on 4 gallons as requested.

I am enclosing another submittal sheet for your review and asking for a second approval. Certainly, transmittal #052 approved the items, yet I do not want us to be in a situation of having to request a deviation on this after the items are on the job.

Please feel free to contact me if I may be of any assistance.


Sincerely,

Chip Davis


President/General Manager

Enclosures


CD/mw



- · Wall outlet, angle-back toilet.
- Siphon jet flushing action.
- Large 2 %" passageway.



ANGLESEY K-4486-ET / K-4498-ER



K-4486-ET Anglesey vitreous china siphon jet elongated angle back toilet with 2%" (67 mm) passageway, wall outlet, 1½" top spud and 2 floor screws. 4½" (115 mm) floor to center of wall outlet roughing-in.

(Specify K-4488-ET for Anglesey with integral seat and 11/2" top spud.)


Recommended Seat

K-4670-C Lustra solid plastic white seat with check hinge (K-4671-C black).

Suggested flush valves — Delany 402-AVB/Sloan 110-FYV.

K-4498-ER Anglesey vitreous china siphon jet elongated angle back toilet with integral seat, 2%" (67 mm) passageway, 1½" rear spud and 2 floor screws. 4½" (11.5 mm) floor to center of wall outlet roughing-in. Suggested flush valve — Delany 534-VB/Sloan 152YV.





KOHLER

May 10, 1985

Dear Mr. Davis:

PURCHASE ORDER M48-1514; UNACCOMPANIED ENLISTED PERSONNEL HOUSING CAMP JOHNSON, CAMP LEJEUNE, NC

In accordance with a request from our Charlotte office, we are enclosing certification that the K-4486-ET bowl complies with ANSI Specification All2.19.2M.

Please let us know if we can be of further assistance to you.

Sincerely,

R. T. Daniels
Manager - Pricing
Plumbing Products

Mr. Chip Davis
Ferguson Enterprises, Inc.
P.O. Box 3037
Wilmington, NC 28406

RTD mj

Encl.

cc: Kohler Co., Charlotte



KOHLER

May 10, 1985

State of Wisconsin)
) ss.
County of Sheboygan)

Eugene P. Seifert, being duly sworn on oath deposes and says:

The K-4486-ET bowl for use on the Unaccompanied Enlisted Personnel Housing Project, Camp Johnson, Camp Lejeune, NC, complies with ANSI Specification All2.19.2M.

KOHLER CO.

By Engene Politers
Treasurer

Subscribed and sworn to before me this 10th day of May, 1985.

Notary Public, Sheboygan County, Wis.

My commission expires 3/31/87



