



DEPARTMENT OF THE NAVY

ATLANTIC DIVISION
NAVAL FACILITIES ENGINEERING COMMAND
NORFOLK, VIRGINIA 23511-6287

TELEPHONE NO.

(804) 445-2930

IN REPLY REFER TO:

6280

1141JJH

6 APR 1987

From: Commander, Atlantic Division, Naval Facilities Engineering Command
To: Commanding General, Marine Corps Base, Camp Lejeune

Subj: ENGINEERING SERVICE REQUEST TO STUDY THE WATER SYSTEMS AT THE
MCAS NEW RIVER AND CAMP GEIGER

Encl: (1) ESR Study of the Potable Water Systems at the MCAS New River and
Camp Geiger

1. Enclosure (1), the ESR, is forwarded as a preliminary study report.
Please review the contents carefully, particularly Attachment B, and address
comments and questions to Mr. J. J. Harwood, AUTOVON 565-2930.

J. R. Bailey
J. R. BAILEY
By direction





RECEIVED
MURKIN BOND

THE FOLLOWING IS A SUMMARY OF THE INFORMATION RECEIVED FROM THE SOURCE ON APRIL TEN LAST:

1. SOURCE ADVISED THAT THE SUBJECT IS CURRENTLY EMPLOYED AS A [REDACTED] AT [REDACTED].

2. SOURCE STATED THAT THE SUBJECT HAS BEEN IN CONTACT WITH [REDACTED] SINCE [REDACTED].


3. SOURCE REPORTED THAT THE SUBJECT HAS BEEN OBSERVED AT [REDACTED] ON [REDACTED].

ENGINEERING SERVICE REQUEST
TO STUDY THE POTABLE WATER SYSTEMS
AT THE MCAS NEW RIVER AND
CAMP GEIGER, CAMP LEJEUNE, NORTH CAROLINA

MARCH 1987

ENVIRONMENTAL QUALITY BRANCH
UTILITIES, ENERGY, AND ENVIRONMENTAL DIVISION
ATLANTIC DIVISION, NAVAL FACILITIES ENGINEERING COMMAND
NORFOLK, VIRGINIA 23511-6287

Prepared by:



J. J. HARWOOD, P.E.
Environmental Engineer

Encl (1)

ENGINEERING & WATER REQUEST
TO STUDY THE POTENTIAL WATER SYSTEMS
AT THE NEW RIVER AND
CASE OFFICE, CAMP LEONARD, NORTH CAROLINA

BRANCH 108

ENVIRONMENTAL FACILITY BRANCH
UTILITIES, ENERGY, AND FACILITIES DIVISION
ATLANTIC DIVISION, NAVAL FACILITIES ENGINEERING COMMAND
NORFOLK, VIRGINIA 23511-2000

Printed by

J. J. JAMESON, P. O. BOX 108

LIST OF ATTACHMENTS

- A. Water Rehabilitation Guide
- B. Contract Outline
 - Scope of Work - Valve and Leakage Survey
 - Cost Estimate

LIST OF ENCLOSURES

- (1) C Factor Tests
- (2) Water Budget
- (3) Skeletonized Water System
- (4) Existing MCAS Small Pumps
- (5) Existing MCAS and Camp Geiger Plant Pipes
- (6a) Improved System - New Line to Camp Geiger Reservoir (Model)
- (6b) New Line Connection to Camp Geiger Reservoir - Scheme I
- (6c) New Line Connection to Camp Geiger Reservoir (Map) - Scheme I
- (7a) New Line Connection to Camp Geiger (Model) - Scheme II
- (7b) New Line Connection to Camp Geiger (Map) - Scheme II
- (8) Modified MCAS Pump Station
- (9) New Pumps
- (10) Tower Storage Sketches
- (11a) 1983 Fire Protection Survey MCAS
- (11b) 1985 Fire Protection Survey Camp Geiger
- (12a) MOQ Pump House (AS2003)
- (12b) MOQ Pump House Typical Fire Pump Curves
- (13) NCO Club
- (14) MOQ
- (15) WHSE AS 3525
- (16) Hangar AS 840
- (17) Trailer Park
- (18) EM Club with C=120
- (19) Contaminated Fuel Tanks
- (20) O'Club (MCAS)

LIST OF ATTACHMENTS

- A. Water Rehabilitation Guide
- B. Contract Outline
- C. Scope of Work - Valve and Leakage Survey
- D. Cost Estimate

LIST OF ENGINEERS

- (1) Factory Tests
- (2) Water Budget
- (3) Scaled Water System
- (4) Existing MWS Small Pumps
- (5) Existing MWS and Camp Geiger Plant Pipes
- (6) Improved System - New Line to Camp Geiger Reservoir (Model)
- (7) New Line Connection to Camp Geiger Reservoir - Scheme I
- (8) New Line Connection to Camp Geiger Reservoir (Map) - Scheme I
- (9) New Line Connection to Camp Geiger (Model) - Scheme II
- (10) New Line Connection to Camp Geiger (Map) - Scheme II
- (11) Modified MWS Pump Station
- (12) New Pumps
- (13) Lower Storage Reservoir
- (14) 1983 Fire Protection Survey MWS
- (15) 1983 Fire Protection Survey Camp Geiger
- (16) 100 Map House (AS103)
- (17) 100 Map House Typical Fire Log Survey
- (18) 100 Map House
- (19) MWS
- (20) MWS AS 325
- (21) MWS AS 340
- (22) Trailer Park
- (23) BM Grid with 0-120
- (24) Connected Fuel Tanks
- (25) 0' Grid (MWS)

1. Introduction

The Marine Corps Base, Camp Lejeune, North Carolina, submitted an Engineering Service Request for a study of the potable water systems of the MCAS, New River and Camp Geiger. Originally, each activity had its own water supply wells, treatment, pumping and storage facilities. An emergency 8-inch line connected both systems. A new water treatment and pumping plant was built at the Air Station which now supplies water to both the Air Station and Camp Geiger via the 8-inch emergency line.

2. Because of concerns about the reliability of the system, parts of which are quite old (1940 era), equipment and operational problems, and the need for a reliable system that will support present needs and future expansion plans, a complete system study in accordance with the Navy water pipe rehabilitation guide is needed (Attachment A). The five steps of the study are:

- a. Site visit to collect data and make preliminary tests.
- b. Hydraulic Analysis to identify improvements that are needed assuming the existing system is in usable condition.
- c. Contracted field examinations to identify parts of the system which are not in usable condition.
- d. Design of system improvements from b and c.
- e. Two part construction contract to install the designed improvements.
 - (1) To replace valves and inspect pipe
 - (2) Replace pipe (if needed), and construct recommended system improvements.

3. Step a - Site Visit by Mr. J. Harwood, Code 114 was in April 1986.

This is a report of Steps a and b and it makes recommendations and provides cost estimates and scopes of work for Steps c and d which are to be accomplished by contract. Plans and specifications for Step e will be done by Step d.

The report covers operational and hydraulic equipment problems and makes specific improvement recommendations for adequate water flow, pressure and storage for present and future, normal and fire protection needs. It also addresses problems common to aging water systems.

1. Introduction

The Marine Corps Base, Camp Lejeune, North Carolina, submitted an Engineering Service Request for a study of the potable water systems of the MCB. New River and Camp Geiger. Originally, each activity had its own water supply wells, treatment, pumping and storage facilities. An emergency 8-inch line connected both systems. A new water treatment and pumping plant was built at the Air Station which now supplies water to both the Air Station and Camp Geiger via the 8-inch emergency line.

1. Because of concerns about the reliability of the system parts of which are quite old (1940 era), equipment and operational problems, and the need for a reliable system that will support present needs and future expansion plans, a complete system study in accordance with the Navy water pipe rehabilitation guide is needed (Attachment A). The five steps of the study are:

- a. Site visit to collect data and make preliminary tests.
- b. Hydraulic analysis to identify improvements that are needed assuming the existing system is in as-bid condition.
- c. Contracted field examinations to identify parts of the system which are not in as-bid condition.
- d. Design of system improvements from b and c.
- e. Two part construction contract to install the required improvements.

- (1) To replace valves and inspect pipe.
- (2) Replace pipe (if needed), and construct recommended system improvements.

2. Step 1 - Site visit by Mr. J. J. Barwood, CWS III was in April 1984.

This is a report of steps a and b and it makes recommendations and a cost estimate for steps c and d which are to be accomplished by contract. Plans and specifications for step e will be done by Step 2.

The report covers operational and maintenance equipment problems and makes specific improvement recommendations for adequate water flow, pressure and storage for present and future, normal and fire protection needs. It also addresses problems common to aging water systems.

4. Details

Operational and hydraulic equipment problems

a. Each system, Camp Geiger and the Air Station, have two elevated water storage towers. The new Air Station treatment and pumping plant is located at the Air Station near Camp Geiger. Treated water is pumped into lines going to Camp Geiger in one direction and the Air Station in another. Apparently, there is insufficient pumping capacity to fill the Air Station and Camp Geiger tower at the same time during periods of high water usage. The lines to the Air Station must be closed to fill the furthest Camp Geiger tower (STC 606). Water is still stored in a Camp Geiger reservoir and pumped into the system when needed to augment the Air Station pumps, and for emergencies.

b. Other reported problems were insufficient fire protection in the MOQ area; keeping the chlorine residual at the MOQ reservoir; insufficient fire protection for Hangar 840; the pumps at Camp Geiger lose their prime if the water level in the Camp Geiger ground storage reservoir gets too low; Camp Geiger elevated tower STC 1070 overflows before tower STC 606 fills unless the STC 1070 valve in the tower feed line is throttled; and much of the system is old and felt not to be reliable.

c. Recommendations to provide deluge sprinkler water supplies for Hangar 840 were also requested.

This report will provide specific recommendation that address these problems and improve the system to support present needs and future planned expansions.

5.

a. Information about population, water consumption, future plans and operation and facility problems were gathered during the site visit in April 1986. Preliminary tests to determine the condition of the pipe interiors were made and the following "C" factors were measured (enclosure (1)):

MCAS MCAVOY Road - between Campbell and Curtis; C = 119 (Good)

(This line was reported to have been previously cleaned by "pigging").

MCAS - MOQ Longstaff St; C = 111 (Good)

Camp Geiger D Street; C = 74 (Fair)

b. The results hold no surprises. The older Camp Geiger pipes are fair and the newer, probably cement lined, and cleaned pipes are in good condition.

Operational and hydraulic equipment problems

a. Each system, Camp Geiger and the Air Station, have two elevated water storage towers. The new Air Station treatment and pumping plant is located at the Air Station near Camp Geiger. Treated water is pumped into lines going to Camp Geiger in one direction and the Air Station in another. Apparently, there is insufficient pumping capacity to fill the Air Station and Camp Geiger tower at the same time during periods of high water usage. The lines to the Air Station must be closed to fill the furthest Camp Geiger tower (STC 305). Water is still stored in a Camp Geiger reservoir and pumped into the system when needed to augment the Air Station pumps, and for emergencies.

b. Other reported problems were insufficient fire protection in the 300 area; keeping the chlorine residual at the 300 reservoir; insufficient fire protection for Hangar 840; the pumps at Camp Geiger loose their prime if the water level in the Camp Geiger ground storage reservoir gets too low; Camp Geiger elevated tower STC 1070 overflows before tower STC 305 fills unless the STC 1070 valve in the lower feed line is throttled; and much of the system is old and felt not to be reliable.

c. Recommendations to provide damage resistant water supplies for Hangar 840 were also requested.

This report will provide specific recommendations that address these problems and improve the system to support present needs and future planned expansion.

3. Information about population, water consumption, future plans and operational and facility problems were gathered during the site visit in April 1986. Preliminary tests to determine the condition of the pipe interiors were made and the following "C" factors were assured (enclosure (i)):

MCAS MAGWAY Road - between Campbell and Curtis; C = 112 (Good)

(This line was reported to have been previously cleared by "pigging".)

WAG - 1000 Margaret; St; C = 111 (Good)

Camp Geiger D Street; C = 104 (Fair)

d. The results hold no surprises. The older Camp Geiger pipes are fair and the newer, probably cement lined, and cleared pipes are in good condition.

c. A Water budget (enclosure (2)) indicates:

Average demand = 896 KGPD
Expected usage = 630 KGPD
Unaccounted for water = 266 KGPD

$100 \times \frac{266}{890} = 30$ percent A good part of the 30 percent is probably leakage. This would also be expected from old parts of a water system.

6. a. A skeletonized computer model of the water system was made (enclosure (3)). The two smaller pumps (enclosure (4)) at the existing MCAS and Camp Geiger pumping stations were used, enclosure (5). A 48-hour extended period simulation was made for a maximum day (2.5 x average water usage). The results are graphically presented in Figure 1a for Tower STC 606. Note how the Tower STC 606 empties. This agrees with the operating experience if the Air Station is not valved off during Camp Geiger filling periods. A tower emptying is unacceptable. Notice that it empties about 0700 hours and does not recover during a maximum day of water usage.

b. A second simulation was made for the existing system using the large MCAS pumps (enclosure (4)). The results, shown in Figure 1b, also show Tower STC 606 emptying.

7. Two schemes were analyzed by computer model to resolve the hydraulic problems. Scheme I uses both MCAS and Camp Geiger pump stations and Scheme II uses only the MCAS pump station.

a. Scheme I - The computer model was improved by adding another 8-inch PVC line from the MCAS pump station to Camp Geiger, connecting at the Camp Geiger ground level reservoir, (enclosures (6a) and (7)). The flow rate to the reservoir is controlled by orifice plate (enclosure (6b)). The MCAS pump station was modified as shown in enclosure (8), and three new 6x8x18A Aurora pumps with 15 1/4-inch impellers were installed at the MCAS pump station, and two at the Camp Geiger pump station, (enclosure (9)).

b. Altitude values were installed at the towers and the high water levels set at elevations of 168 feet for all the towers. The pumps were set to turn on and off at the following tower water levels:

	<u>Tower</u>	<u>HWL</u>	<u>LWL</u>
MCAS Pump	STC 310	168	162
Camp Geiger Pump	STC 606	168	158

c. The two MCAS tank low water levels (LWL) were set at 162 feet to provide adequate fire reserve stored in the tower. The LWLs were set at 158 feet on the two Camp Geiger tanks because there is not enough storage capacity in the Camp Geiger elevated tanks for normal fluctuating operating demands and fire reserve. The fire reserve for Camp Geiger will have to come from the ground storage tanks. (Please see enclosure (10)).

c. A Water Budget (enclosure (2)) indicates:

Unaccounted for water = 266 KGPB
 Average demand = 826 KGPB
 Expected usage = 530 KGPB

A good part of the 30 percent is probably leakage. This would also be expected from old parts of a water system.

A. A digitalized computer model of the water system was made (enclosure (3)). The two smaller pumps (enclosure (4)) at the existing MOAB and Camp Geiger pumping stations were used, enclosure (5). A 24-hour extended period simulation was made for a maximum day (2.5 x average water usage). The results are graphically presented in Figure 1 for Tower STC 800. Note how the tower STC 800 empties. This agrees with the operating experience if the Air Station is not valved off during Camp Geiger filling periods. A tower emptying is unacceptable. Notice that it takes about 1700 hours and does not recover during a maximum day of water usage.

B. A second simulation was made for the existing system using the large MOAB pump (enclosure (4)). The results, shown in Figure 1b, also show Tower STC 800 emptying.

7. Two schemes were analyzed by computer model to resolve the hydraulic problems. Scheme I uses both MOAB and Camp Geiger pump stations and Scheme II uses only the MOAB pump station.

a. Scheme I - The computer model was improved by adding another 8-inch PVC line from the MOAB pump station to Camp Geiger, connecting at the Camp Geiger ground level reservoir, (enclosure (6a) and (7)). The flow rate to the reservoir is controlled by orifice plate (enclosure (6b)). The MOAB pump station was modified as shown in enclosure (6), and three new 6x8x18 Aurora pumps with 12 1/2-inch impellers were installed at the MOAB pump station, and one at the Camp Geiger pump station, (enclosure (8)).

b. All three valves were installed at the towers and the high water levels set at elevations of 162 feet for all the towers. The pumps were set to turn on and off at the following tower water levels:

	Lower	High	Low
MOAB Pump	170 310	168	162
Camp Geiger Pump	170 300	168	158

c. The two MOAB tank low water levels (LWL) were set at 162 feet to provide storage. The reservoirs in the towers. The tanks were set at 162 feet on the two Camp Geiger tanks because there is not enough storage capacity in the Camp Geiger elevated tanks for normal fluctuating operating demands and five reservoirs. The five reservoirs for Camp Geiger will have to come from the ground storage tanks. (Please see enclosure (10)).

d. A 48-hour maximum day simulation was made for the improved system and the results show that the tanks do not empty (figure (1-c and d)). The MCAS pump operated for a total of 28 hours out of the 48, and the Camp Geiger pump operated 15 hours.

e. Enclosures (11a) and (11b) are excerpts from the 1983 and 1985 LANTNAVFACENCOM fire protection surveys for the MCAS and Camp Geiger respectively. They show that fire protection capacity overall is good except for three locations at the MCAS. They are the MOQ area, Warehouse 3525 and the O'Club. The improved system model was used to simulate fire flows at those and other locations of Camp Geiger and the MCAS. The results are summarized as follows:

(FIRE FLOWS) SCHEME 1

<u>Location</u>	<u>JCT</u>	<u>Flow GPM</u>	<u>Resid PSIG</u>	<u>Subtract PSIG</u>	<u>Final PSIG</u>	<u>Comments</u>
1. Hangar AS 4106	24	7000	61	-	61	g.t. 20 OK
2. CG Bldg 10	5	1500	60	-	60	g.t. 20 OK
3. CG BEQ	1	1500	59	-	59	g.t. 20 OK
4. TRL PK	7	1500	55	47	8	l.t. 20 (1)
5. MCAS EM Club	33	1000	61	42	19	a.e. 20 (2)
6. MCAS O'Club	16	1000	49	24	25	g.t. 20 OK
7. Cont. Fuel Tks	24	3000	61	170	-109	l.t. 20 (3)
8. NCO Club		1000	(see encl (13))		40	g.t. 20 OK
9. Officers Housing		1000	(see encl (14))		54	g.t. 20 OK
10. Hangar AS 840		New pump REQ, see encl (16)				
11. Warehouse 3525		New pump and RES REQ, see encl (15)				

g.t. = greater than

l.t. = less than

a.e. = about equal

f. The NCO Club and MOQ are presently supplied fire flows and pressures from reservoir AS 2002 and pump station AS 2003. These locations were done by hand computations shown in enclosures (12), (13), and (14). The MCAS O'Club hand computations are shown in enclosure (20). Warehouse 3525 and Hangar AS 840 are remote and require flow and pressures above the capacities of present equipment. They will require separate storage tanks and booster pumps (please see enclosures (15) and (16)).

Scheme II. For this scheme, in addition to improving the MCAS pump station as shown in enclosure (8), the MCAS to Camp Geiger connection is a 10-inch PVC line from the pump station connecting Camp Geiger near Tower STC 1070 and south of Tower STC 600 (enclosures (7a) and (7b)). Altitude valves were set the same as for Scheme I, and two Aurora 6x8x18a pumps were used in the MCAS pump station. Towers STC 606 and AS 301 did not empty during a 48-hour maximum day simulation (Figure 1e and 1f). The two MCAS pumps operated 17 and 13 hours respectively.

h. A 48-hour maximum day simulation was made for the improved system and the results show that the tanks do not empty (Figure 11e and 11f). The MGA pump operated for a total of 12 hours out of the 48, and the Camp Garger pump operated 15 hours.

e. Enclosures (11a) and (11b) are excerpts from the 1983 and 1985 LANTIVAVATCOMOM fire protection surveys for the MGA and Camp Garger respectively. They show that fire protection capacity overall is good except for three locations at the MGA. They are the MGA area, Warehouse 3222 and the O'Club. The improved system model was used to simulate fire flows at those and other locations of Camp Garger and the MGA. The results are summarized as follows:

(11f) FLOW SCHEME 1

Location	Flow GPM	Lead PSIG	Subtotal PSIG	Final PSIG	Comments
1. Hangar A8 4100	7000	61	-	61	2.0 OK
2. CO Line 10	1500	80	-	80	2.0 OK
3. CO TX	1500	50	-	50	2.0 OK
4. TEL TX	1500	55	47	2	2.0 (1)
5. MGA 2nd Fl.	1000	61	42	19	2.0 (2)
6. MGA 1st Fl.	1000	40	24	22	2.0 OK
7. 1st. Fuel Tank	3000	61	170	-109	2.0 (3)
8. MGA Club	1000	(see encl (12))		40	2.0 OK
9. Officers Housing	1000	(see encl (14))		24	2.0 OK
10. Hangar A8 840		see pump REG, see encl (13)			
11. Warehouse 3222		see pump and REG REG, see encl (13)			

g.f. = greater than
 l.f. = less than
 a.e. = about equal

i. The MGA Club and MGA are presently supplied fire flows and pressures from reservoir A8 2700 and pump station A8 2003. Those locations were done by hand computation as shown in enclosure (12), (13), and (14). The MGA O'Club and computations are shown in enclosure (20). Warehouse 3222 and Hangar A 840 are remote and require flow and pressure above the capabilities of present equipment. They will require separate storage tanks and booster pumps (please see enclosure (13) and (14)).

11. For this scheme, in addition to improving the MGA pump station as shown in enclosure (8), the MGA to Camp Garger connection is a 12-inch PVC line from the pump station connecting Camp Garger near Tower 2TC 1010 and south of tower 2TC 600 (enclosures (7a) and (7b)). All valve were set to the same as for scheme 1, and two 4-inch 6x12 pumps were used in the MGA pump station. Towers 2TC 600 and A8 301 did not empty during a 48-hour maximum day simulation (Figure 11e and 11f). The two MGA pumps operated 15 and 18 hours respectively.

(FIRE FLOWS) SCHEME 2

<u>Location</u>	<u>JCT</u>	<u>Flow GPM</u>	<u>Resid PSIG</u>	<u>Subtract PSIG</u>	<u>Final PSIG</u>		<u>Comments</u>	
1. Hangar AS 4106	24	7000	62	-	62	g.t.	20 OK	
2. CG Bldg 10	5	1500	57	-	57	g.t.	20 OK	
3. CG BEQ	1	1500	46	-	46	g.t.	20 OK	
4. TRL PK	7	1500	54	47	7	l.t.	20 (1)	
5. MCAS EM Club	33	1000	62	42	20	e.t.	20 OK	
6. MCAS O'Club	16	1000	51	24	27	g.t.	20 OK	
7. Cont. Fuel Tks	24	3000	63	170	-107	l.t.	20 (3)	
8. NCO Club		1000	(see encl (16))					
9. Officers Housing		1000	(see encl (14))					
10. Hangar AS 840		New pump req., see encl (16)						
11. Warehouse 3525		New pump and res. req., see encl (15)						

g.t. = greater than
l.t. = less than
a.e. = about equal
e.t. = equal to

COST COMPARISON

	<u>Scheme I</u>	<u>Scheme II</u>
Improve Pump Station	Same Cost	Same Cost
New Pump w/controllers	5 Pumps at 30K = 150K	3 pumps = 30K = 90K
New PVC Connections	5120'-8" @ 17.25 = 87K	3500'-10" @ 21 = 73.5K
Totals	<u>237K</u>	<u>163.5K</u>

Scheme I is more costly but it affords extra reserve fire protection storage water.

NOTES:

- (1) Additional lines will be needed at TRL park - see enclosure (17).
- (2) 20 PSIG residual can be obtained by cleaning line - see enclosure (18).
- (3) Storage tank and pump will be needed at site - see enclosure (19).

(FIRE FLOW) SCHEME 2

Location	LCT	Flow GPM	Head PSIG	Supply PSIG	Final PSIG	Comments
1. Hangar A2 4100	24	1000	62	-	62	g.t. 20 OK
2. CC Bldg 10	7	1500	57	-	57	g.t. 20 OK
3. CC W/O	1	1500	48	-	48	g.t. 20 OK
4. TRD PK	4	1500	54	47	7	l.f. 20 (1)
5. MOAS EN O'Pipe	33	1000	62	42	20	e.t. 20 OK
6. MOAS O'Pipe	16	1000	51	34	27	g.t. 20 OK
7. Cont. Fuel Trk	24	2000	63	170	-107	l.f. 20 (3)
8. W/O O'Pipe		1000		(see encl (13))		
9. Officers Housing		1000		(see encl (14))		
10. Hangar A2 840				New pump req., see encl (15)		
11. Warehouse 3525				New pump and res. req., see encl (15)		

g.t. = greater than
 l.f. = less than
 e.t. = about equal
 o.t. = equal to

COST DATA

Item	Scheme 1	Scheme 2
Improve Pump Station	Same Cost	Same Cost
New Pump w/Controllers	2 Pumps at 30K = 150K	3 Pumps at 30K = 90K
New PVC Connections	5120' - 8" @ 17.25 = 87K	3560' - 10" @ 21 = 75.2K
Totals	237K	163.2K

Scheme 1 is more costly but it affords extra reserve fire protection storage water.

- Notes:
- (1) Additional lines will be needed at TRD park - see enclosure (17).
 - (2) 20 PSIG residual can be obtained by cleaning line - see enclosure (18).
 - (3) Storage tank and pump will be needed at site - see enclosure (15).

8. Conclusions

a. In addition to adding pipes, pumps, etc., to the system to provide adequate capacity and operation, the condition of the existing system must be inspected, tested and improved to provide reliable service. Appendix B is an outline of steps for contracts to efficiently test the existing system and provide repairs and designs for installing the needed additional equipment identified by the hydraulic analysis. Appendix B pages I through VIII are scopes of work, cost estimates and costing information. The step sequences are based on previous examination of the system to determine what is needed for the next test or examination.

b. Initial flow tests (enclosure (1)) indicate some corrosion/scale build-up inside the pipes, but not enough to seriously affect operation. However, the 8-inch lines along Curtis and Flounder roads are suspect for low "C" factors, and should be tested. If C is less than 90, the pipe should be cleaned by pigging. The Langelier water stabilization index is slightly positive, and therefore pigging is an appropriate method for cleaning and restoring low "C" factors. At this point, it suggested that the Navy Rehabilitation Guide, Attachment A, be read for information about rehabilitating older systems.

c. Scheme I affords more automatic reserve water storage with Camp Geiger's reservoirs and pumps. There is, however, sufficient storage available from the MCAS treatment plant reservoirs for daily operations and fire needs. Camp Geiger's reservoir and pump station can still be retained and used manually for its additional capacity.

d. The trailer park area use is minimal at present, and no improvements are recommended.

In addition to adding pipe, traps, etc., to the system to provide adequate capacity and operation, the condition of the existing system must be inspected, tested and improved to provide reliable service. Appendix B is an outline of steps for contracts to efficiently test the existing system and provide repairs and designs for installing the needed additional equipment. Appendix B pages I through VIII are identified by the hydraulic analysis. The step sequences scopes of work, cost estimates and costing information. The step sequences are based on previous examination of the system to determine what is needed for the next test or examination.

Initial flow tests (enclosure (I)) indicate some corrosion/scale build-up inside the pipes, but not enough to seriously affect operation. However, the branch lines along Quirt and Lumber roads are suspect for low "C" factors, and should be tested. If C is less than 90, the pipe should be cleaned by pigging. The handler water stabilization index is slightly positive, and therefore pigging is an appropriate method for cleaning and restoring low "C" factors. At this point, it is suggested that the Water Rehabilitation Unit, Attachment A, be read for information about rehabilitating other systems.

Scheme I affords more storage reserve water storage with Camp Quirt's reservoir and pumps. There is, however, little on storage available from the MOA's treatment plant reservoirs for daily operations and fire needs. Camp Quirt's reservoir and pump station can still be retained and used manually for its additional capacity.

The trailer park area use is minimal at present, and no improvements are recommended.

Recommendations for system improvements excluding the trailer park area:

1. Award a contract to:
 - a. Manipulate and test about 215 hydrants and hydrant valves and 560 isolation and maintenance valves 6 inches and larger (1). The test will be for condition, proper operation and valve leakage.
 - b. Perform a sonic leakage survey on all the exterior station pipes. There are about 25 miles of pipe.
 - c. Perform a soil resistivity/copper sulfate reference (Cathodic Protection) survey of the pipelines.
 - d. Perform "C" factor flow tests for pipes on Flounder and Curtis Roads by method shown in "Water Rehabilitation Guide", Attachment A.
 - e. Excavate and inspect the pipes for external condition at locations identified as corrosive from 1c (see Attachment B page VIII).
 - f. Prepare plans and specifications to replace leaking or inoperative valves hydrants and pipes from paragraphs 1a, 1b and 1c; and the following list of improvements:

C. IS DONE
- we have
a copy,
also
pub wks
has it

LIST OF PROJECTS FOR DESIGN AND CONSTRUCTION

- A. Install 10-inch PVC line from MCAS treatment plant to Camp Geiger - Scheme II, see enclosures (7a and 7b).
- B. Modify the MCAS pump house piping and install new pumps in MCAS and Camp Geiger pump houses as shown in enclosures (8) and (9). The pumps will be controlled by pressures at Towers STC 606 and AS 310 as shown in the enclosures and in paragraph 6b of this report.

NOTES:

- (1) Exclusive of trailer park, valves = about 511 plus 10 percent for counting errors = 560.

Recommendations for system improvements excluding the trailer park area:

1. Award a contract for:

- a. Manipulate and test about 215 hydrants and hydrant valves and 500 isolation and maintenance valves 6 inches and larger (1). The test will be for condition, proper operation, and valve leakage.
- b. Perform a sonic leakage survey on all the exterior station pipes. There are about 77 miles of pipe.
- c. Perform a soil resistivity/copper sulfate reference (Cathodic Protection) survey of the pipelines.
- d. Perform "Q" factor flow tests for pipes on Flounder and Curtis roads by method shown in "Water Rehabilitation Guide", Attachment A.
- e. Excavate and inspect the pipes for external condition at locations identified as corrosive from 1c (see Attachment B page VIII).
- f. Prepare plans and specifications to replace leaking or impervious valves hydrants and pipes from paragraphs 1a, 1b and 1c; and the following list of improvements:

LIST OF PROJECTS FOR DESIGN AND CONSTRUCTION

- A. Install 10-inch PVC line from MOAS treatment plant to Camp Geiger - Scheme II, see enclosure (7a and 7b).
- a. Modify the MOAS pump house piping and install new pumps in MOAS and Camp Geiger pump houses as shown in enclosure (8) and (9). The pumps will be controlled by pressure at towers 270 000 and 25 310 as shown in the enclosure and in paragraph 1b of this report.

NOTES:

(1) Exclusive of trailer park, valves = about 211 plus 10 percent for counting errors = 230.

Recommendations for system improvements excluding the trailer park area:

1. Award a contract to:

a. Manipulate and test about 215 hydrants and hydrant valves and 560 isolation and maintenance valves 6 inches and larger (1). The test will be for condition, proper operation and valve leakage.

b. Perform a sonic leakage survey on all the exterior station pipes. There are about 25 miles of pipe.

c. Perform a soil resistivity/copper sulfate reference (Cathodic Protection) survey of the pipelines.

d. Perform "C" factor flow tests for pipes on Flounder and Curtis Roads by method shown in "Water Rehabilitation Guide", Attachment A.

e. Excavate and inspect the pipes for external condition at locations identified as corrosive from 1c (see Attachment B page VIII).

f. Prepare plans and specifications to replace leaking or inoperative valves hydrants and pipes from paragraphs 1a, 1b and 1c; and the following list of improvements:

LIST OF PROJECTS FOR DESIGN AND CONSTRUCTION

A. Install 10-inch PVC line from MCAS treatment plant to Camp Geiger - Scheme II, see enclosures (7a and 7b).

B. Modify the MCAS pump house piping and install new pumps in MCAS and Camp Geiger pump houses as shown in enclosures (8) and (9). The pumps will be controlled by pressures at Towers STC 606 and AS 310 as shown in the enclosures and in paragraph 6b of this report.

NOTES:

(1) Exclusive of trailer park, valves = about 511 plus 10 percent for counting errors = 560.

Recommendations for system improvements excluding the trailer park area:

4. Award a contract to:

- a. Manipulate and test about 215 hydrants and hydrant valves and 50 isolation and maintenance valves 6 inches and larger (1). The test will be for condition, proper operation, and valve leakage.
- b. Perform a sonic leakage survey on all the exterior station pipes. There are about 12 miles of pipe.
- c. Perform a soil resistivity/copper sulfate reference (Cathodic Protection) survey of the pipelines.
- d. Perform "Q" factor flow tests for pipes on Elmhurst and Curtis roads by method shown in "Water Rehabilitation Guide", Attachment A.
- e. Excavate and inspect the pipes for external condition at locations identified as corrosive from 1c (see Attachment B page VIII).
- f. Prepare plans and specifications to replace leaking or inadequate valves hydrants and pipes from paragraphs 1a, 1b and 1c; and the following list of improvements:

LIST OF PROJECTS FOR DESIGN AND CONSTRUCTION

- A. Install 10-inch PVC line from MOAS treatment plant to Camp Gelger - Scheme II, see enclosures (7A and 7B).
- B. Modify the MOAS pump house piping and install new pumps in MOAS and Camp Gelger pump houses as shown in enclosures (8) and (9). The pumps will be controlled by pressure at towers 2TC 000 and AS 310 as shown in the enclosures and in paragraph 1b of this report.

NOTES:

(1) Excludes trailer park valves - about 211 plus 10 percent for counting errors = 230.

C. Provide for an inspection of the AS 2003 pump house and make any needed repairs to place it in proper operation. The pump house has piping to recirculate water through Reservoir AS 2002. Install a chlorinator in the pump house and recirculate chlorinated water through the reservoir in order to keep the chlorine residual.

D. Design and construct a new fire pump house which will take water from Reservoir AS 2002 and service a deluge sprinkler system in Hangar AS 408, (see enclosure (16)).

E. Provide a ground level reservoir and fire pump for fire protection at Warehouse AS 3525, and the contaminated fuel tanks, enclosures (15) and (19).

F. Provide Towers STC 606 and STC 1070 with two-way altitude valves. Repair the altitude valves at Towers AS 310 and 4130 if needed. All valves should close at elevation 168 feet.

Attachments C and D are a scope of work and cost estimate for the valve testing and pipe leakage survey.

2. Purchase and stock replacement valves, pipe and pipe repair parts for those valves and pipes identified in recommendations 1a, 1b and 1e. Using plans and specifications from 1e above, award a second contract to excavate and replace the leaking valves and repair the worst pipe leaks identified in 1a and 1b. Attachment B - pages VIII and VII are special specifications for valve repair work, pipe examination and unit costs. When the number of valves that need replacement is known from 1a, the unit costs of Attachment D can be used to develop a cost estimate for this second contract.

3. The excavations and pipe inspections should start at those locations where the soil is most corrosive and the pipe exteriors would be expected to be the worst. These locations will be identified by the cathodic protection survey of 1c. The information from this survey is to be used with the result of 1a and 1b to plan the sequence of valve and pipe excavation replacements/repairs. The pipes, especially the exteriors of the older pipes, should be examined at corrosive soil locations. Leaking valves and attached pipes at these corrosive areas should be the first to be excavated, inspected and the valves replaced. If a pipe or valve, in a corrosive location, is excavated and the exterior of the pipe is in good condition, it can be assumed that other pipes of the same age in a less corrosive location will also be in good condition.

4. Clean by "pigging" those lines found to have internal buildup from inspections of paragraph 3 and "C" factor tests of 1d.

5. Change Order the design contract 1e to provide plans and specs to replace pipes found to be deteriorated from paragraph 3.

6. Award a construction contract to replace pipes of paragraph 5 and make improvements recommended in this report and designed by paragraph 1f.

6. Provide for an inspection of the AS 2003 pump house and make any needed repairs to place it in proper operation. The pump house has piping to discharge water through Reservoir AS 2002. Install a siphon in the pump house and reservoirs chlorinated water through the reservoir in order to keep the chlorine residual.

7. Design and construct a new five pump house which will take water from Reservoir AS 2002 and service a deluge sprinkler system in Hangar AS 404. (see enclosure (1)).

8. Provide a ground level reservoir and five pumps for fire protection at Warehouse AS 2005, and the contaminated fuel tanks, enclosures (12) and (13).

9. Provide towers 8TC 800 and 8TC 1070 with reflow altitude valves. Repair the altitude valves at towers AS 310 and 410 if needed. All valves should close at elevation 100 feet.

Attachments G and H are a copy of work and cost estimate for the valve testing and pipe leakage survey.

10. Purchase and stock replacement valves, pipe and pipe repair parts for those valves and pipes identified in recommendations 1a, 7 and 12. Using pipe and specifications from 1a above, award a second contract to excavate and replace the leaking valves and repair the worst pipe leaks identified in 1a and 1b. Attachment A - pages VII and VIII and special specifications for valve repair work, pipe examination and unit costs. When the number of valves that need replacement is known from 1a, the unit costs of Attachment B can be used to develop a cost estimate for this second contract.

11. The excavation and pipe inspections should start at those locations where the soil is most corrosive and the pipe extent would be expected to be the worst. These locations will be identified by the cathodic protection survey of 1c. The information from this survey is to be used with the result of 1a and 1b to plan the location of valve and pipe excavation/replacement/repairs. The pipes, especially the extensions of the other pipes, should be examined at corrosive soil locations. Leaking valves and attached pipes at these corrosive areas should be the first to be excavated, inspected and the valves replaced. If a pipe or valve, in a corrosive location, is excavated and the exterior of the pipe is in good condition, it can be assumed that other pipes of the same age in a less corrosive location will also be in good condition.

12. Classify "piping" lines found to have internal bulging from inspections of paragraph 3 and "Factor Tests of 1c."

13. Change order the design contract to provide plans and specs to replace pipes found to be deteriorated from paragraph 3.


14. A bid construction contract to replace pipes of paragraph 3 and make improvements recommended in this report and designed by paragraph 13.

Project

Construct steam pit at FC202 and provide necessary valves, pumps, and piping to tie in the following buildings: FC100, FC200, FC241, and FC251 to the 8" steam main along Main Service Road.

Justification: The boilers and auxiliary equipment at FC202 Steam Plant are of the age that extensive repairs are having to be made. Also, this plant burns No. 2 fuel oil which is expensive, compared to burning coal, where steam is furnished for the 8" steam main requested for tie in.

Estimated Cost: \$20,000



WATER PIPE REHABILITATION GUIDE

ATTACHMENTS

- A. Condensed Guide
- B. Hydraulic Analysis
- C. Hazen Williams "C" Factor Flow Test
- D. Laboratory Analysis Form
- E. Pipe Costs, Water Treatment Information, and Economic Analysis
- F. Copper Sulfate Reference Electrode Measurements

INTRODUCTION

1. Rehabilitation of Navy water pipe lines is expensive and is becoming more of a problem because of the age of the systems. Many were installed in the 40's and 50's and have deteriorated to the point where they are no longer adequate to meet current or future demands, and pipe rehabilitation may be needed. The guide assists in determining where and what type of rehabilitation is appropriate. Much of the updated information for this guide was obtained from comments and publications by the Army Corps of Engineers, Waterways Experimental Station, Vicksburg, Mississippi and from numerous Navy and Municipal Water Works Departments.

2. Prior to the beginning of a pipe rehabilitation project, the scope of the rehabilitation should be developed through a study of the system needs and tests made to determine existing conditions. Typically, a complete study should include:

- a. if needed, updating the system maps showing piping, sizes, elevations, hydrants, service connections, valve locations, pumps, and storage.
- b. estimation of current and future water usage and fire flow rates in each section of the system.
- c. hydraulic analysis to determine required pumping, storage, and pipe flow capacities (sizes and friction factors).
- d. Valve and pipe flow testing to determine valve conditions and actual pipe friction flow factors.
- e. leakage survey.
- f. pressure and leakage testing.
- g. interior and exterior corrosion inspection.
- h. recommendations regarding cleaning, relining, repairs, or replacement.

~~Encl (1)~~

ATTACHMENT A

3. Some of the above items may not be applicable or can be quickly assessed for a particular system or problem. The information contained in this guide should help to determine if a separate study is needed, or to select which items to include as part of the design effort. A system study can be done in-house by Public Works Engineering, by the EFD, or by a separate contract.

4. The Guide also provides information for conducting the study. Attachment A is a condensed reference guide; Attachment B contains information for conducting the hydraulic analysis; Attachment C contains ~~two~~ ^{three} methods for performing flow tests to compute the friction flow factor and evaluate the interior condition of a pipe; Attachment D is a laboratory analysis form showing the parameters to be determined from water samples to compute the water's tendency to scale or corrode (Langelier Index), and indicate its removability (silica content); Attachment E contains water treatment information, pipe cleaning and replacement costs and an economic analysis guide. LANTNAVFACENCOM Code 114 can provide assistance for in-house studies or for obtaining a contract. Point of contact is Mr. J. Harwood at this Command, commercial (804) 445-2930 or AUTOVCN 565-2930 or FTS 955-2930.

DISCUSSION

5. The most common problems which lead to water pipe rehabilitation are:

- a. insufficient pipe flow capacity (low pressures);
- b. excessive pipe breaks and leaks;
- c. red water problems; and
- d. a combination of the above.

Where corrosive (aggressive) water exists, red water, loss of capacity, and excessive breaks are common occurrences. The rusting of the pipe interiors, which causes red water, also results in flow inhibiting tubercles and a weakening of the pipe wall. Scale forming water deposits a calcium carbonate layer on the pipe walls and protects it from rusting. However, excessive deposits will reduce the smoothness of the pipe wall and cause excessive friction resistance to flow. More importantly, deposits will reduce the internal diameter of the pipe, resulting in a greater impediment to the flow. Sometimes, both rusting and scaling exist in the same system due to a change in the chemical makeup of the water from location to location, or to a change in the water source or treatment. Rehabilitation can include restoring the flow capacity of existing pipes by cleaning (e.g., "pigging"), cleaning followed by cement-mortar lining, pipe replacement or addition.

PROCEDURE

6. Unless the system is known to be hydraulically adequate, the basis for flow capacity decisions should be the results of a hydraulic analysis to determine what sizes and what friction factors are required for the pipes to provide adequate flows (see Attachment B). These analyses can range from knowledge of adequacy or simple pipe flow calculations to full scale computer modeling. They can be performed by the activity engineering office, by LANTNAVFACENCOM via ESR, or by an A&E contract. Comparing the required pipe sizes with the existing sizes determines the replacement decision. Except for unusual circumstances (such as large sizes or locations where replacement is very expensive), it is more economical to replace the pipe with a larger pipe or supplement it with a new parallel pipe, than to clean it and add a second pipe to provide the additional capacity.

7. Testing prior to Rehabilitation (select tests which are consistent with the existing system/problem). These tests should be done by an A&E testing contract.

a. Valve leakage and Pipe Flow Tests

Experience with Navy water systems show that many valves leak and cannot be sufficiently closed to sectionalize the systems. Often valves are frozen and cannot be operated at all. This is especially true for older or saltwater systems. Test valve conditions by manipulating them for free operation. Test valves for leakage by flowing a downstream hydrant while manipulating the valve. Leakage can be observed by a change in the hydrant flow, and heard in the valve by sonic listening devices. A small amount of leakage will not seriously affect pipe flow and pressure tests, but will determine the quantity of water needed for pressure tests. All leakage may not be detected and judgement is needed to estimate how much of the detected leakage can be tolerated. Excessively leaking valves are to be replaced.

A sufficient supply of replacement valves should be stocked to prevent undue testing delays. The exterior and interior of connecting pipes are to be examined for size, type of material, corrosion, scale and cement lining while they are exposed for valve work.

Prior to selecting a water pipe for rehabilitation, the pipe is next flow tested as prescribed in Attachment C for its Hazen Williams "C" (friction factor). The results will be compared with the required "C" factors from the hydraulic analysis of paragraph (6) to decide if the present conditions are adequate, or pipe cleaning is desired. Take a sample of the water from the system where the pipe is located and field measure the temperature and pH. Have the water analyzed by a laboratory and the Langelier index computed. The lab analysis forms are shown in Attachment D. The hydrant flow tests can also be used in the field by a pipe cleaning contractor to determine if the cleaning has met specifications; by an inspector to check the results of a cleaning operation; by maintenance to determine the internal condition of a pipe; and by engineers performing a hydraulic study of the water system.

b. Pressure and Leakage Tests


Prior to rehabilitating a water pipe selected from 7a, make pressure and leakage tests according to AWWA C600-44, Section 4.1 and 4.2. Test pressures should be those determined as a result of the hydraulic analysis (including surge and factor of safety). Older valves often leak and high pressures cannot be obtained with a hand pump. A motor-driven pump may be necessary. Repair any incurred ruptures. Close service connections if the pressure tests could damage customer's plumbing. All ruptured pipes may not need replacement. The rupture and maximum pressure, prior to rupture (corrected to the elevation of the rupture point) will be the basis for deciding if the pipe is to be cleaned or replaced. If the pressure test causes a break in a pipe length (not in the joint), and the break can be attributed to a weakening of the pipe wall because of rusting, the pipe should be replaced. If the break is a result of a joint failure (not pipe strength), restoration should be considered. The rupture pressure should also be considered. If the elevation corrected pressure is substantially above the maximum pressure determined for that location from the hydraulic analysis, replacement would not be indicated based upon pressure test results alone, especially for an older pipe. In the absence of a surge or water hammer analysis, a rupture pressure one and one-half times the expected maximum should be acceptable. The decision to replace or restore the pipe should then be based upon economics. If leakage is high and water is scarce or expensive, the economic analysis should include the cost of repairing leaks identified by the leakage survey, and the cost savings associated with reduced water leakage. Bear in mind that cleaning and cement-mortar lining will reduce leaks, but cleaning alone will not.

c. Pipe Examination (Exterior)

Prior to cleaning a water pipe selected from 7b, copper sulfate potential measurements as shown in Attachment F and electrical resistivity tests as specified in U.S. Navy Corrosion Prevention and Control Manual (NAVDOCKS MC 306, Section 2) should be made for the system. Excavate the pipes where the tests indicate corrosive soils, and examine the exterior for deterioration. Rust, pits, and soft spots will be noted. Striking suspicious looking places with a hammer will often reveal soft or deteriorated pipe. Note pieces flaking off when struck. If a pipe is fairly new and is found to be badly deteriorated on the outside, replacement with an exterior protected pipe is indicated. If the pipe is old, and the exterior deterioration is minimal, it can be assumed that there are many more years of useful life remaining for the pipe, and restoration should be considered. Exterior examination of pipes should also be made during valve replacements and repairs.

d. Pipe Examination (Interior)

While the pipe is excavated for 7c, remove a section of the pipe and examine the pipe interior for lining (cement), and type of interior buildup. Examine the interior of the insitu pipe, as well as the removed spool. Determine the type of incrustation (Rust tuberculation, scale), its thickness, hardness, color, and adherence to pipe walls. Interior pipe examinations can also be made during valve repair/replacement work.




The method of cleaning pipes selected for cleaning will depend upon the type of material to be removed. If the water analysis indicates a low (less than 5 ppm) silica content and the pipe interior inspection reveals that the material inside the pipe is a soft and loosely bonded calcium scale (positive Langelier index), polly pigs can be used. If the water analysis indicates high silica content (above 5 ppm), and the corrosion or scale material is hard and/or firmly bonded to the pipe walls, then cleaning should be done by either mechanical pigs or rodding.

Unlined pipes with rust tuberculation (negative Langelier index) are to be mechanically cleaned and cement lined as specified in AWWA Standard C602-76. An alternative to cement lining (which is expensive) is cleaning followed by water treatment. The treatment is to raise the Langelier Index to a slightly positive value, followed by the addition of sodium hexametaphosphate for corrosion control. The equipment needed for treatment is listed in Attachment D.


8. Repair or rehabilitation of valves and pipes identified for work and not needed for tests should be done by a construction or maintenance repair contract. Work should be done first on those valves and pipes that are known to need work and are connected to each other. The other valves that need work should be done next. When the valves are opened or removed and the interior of the pipes connected to the valves are examined for interior conditions and identification of linings, those that show more than minimal internal corrosion during this inspection should also be considered for replacement or rehabilitation in addition to those pipes already identified during the testing contracts. This procedure may require an incremental contract or two contracts, but should result in the best water system at the lowest cost.

9. Each system decision is site specific and should be considered in light of its own test data. Under normal circumstances, it will be found that rehabilitation cost increases can be expected as follows: Lowest in cost is pigging, then cleaning and lining, and the most expensive is pipe replacement for the larger sizes. Also, replacement will be indicated in more cases for the smaller size pipes (less than 10-inch) than the larger pipes. Water treatment items to consider, cleaning/lining costs for pipes, and an economic analysis guide are listed in Attachment E.

10. Excessive breaks can be the result of pipe deterioration caused by corrosion or cavitation, excessive pressures caused by system surges, or water hammer. Surging can be seen on a pressure gage connected to the system. Corrosion can be noted by the color of water (red water) from a fire hydrant at the start of a flow test. Cavitation generally occurs at pumps, pipe diameter changes, valves, fittings, etc., and can be identified by sound. Cavitation sounds like gravel or popping at or near the fittings or pump. Water hammer can be noted by banging or thumping noises in the system, especially when a pump stops or a valve or hydrant is suddenly closed. Rust (red or black water) problems were addressed in paragraph (5). When warranted, water hammer and/or cavitation analyses should be made to determine their magnitude and suitable corrective actions. These analyses are specialized and should be performed via ESR or contract.



11. Operation Plan: Before any testing or repair work begins, a complete operation plan showing the valves and hydrants to be used and all access points for the work should be made and reviewed by all the parties involved. The plan should be submitted in advance so that an adequate supply of equipment (especially valves) can be stocked, water users can be advised of interruptions in service, and arrangements can be made for traffic, or other problems that may occur.



CONDENSED GUIDE - ATTACHMENT A

This condensed guide is a quick reference to be used as a supplement for the "Pipe Rehabilitation Guide". The arrows indicate a probable sequence of steps, and use of condensed guide should be tailored to site specific conditions. () denotes associated paragraphs in the guidance.

I. PROBLEM

GO TO STEP

- | | |
|------------------------------|-----------|
| Loss of Pressure | II |
| Red Water | II |
| Excessive Breaks and/or Wear | III |
| Excessive Leakage | II or III |
| Poor Maps and/or Records | IV |

II. Determine Fire and Domestic Water and Pressure Needs (Present & Future)
Go to Step V

- | | |
|--|---------------------------------|
| III. Waterhammer and/or Cavitation Analysis Leakage Survey | IV. Upgrade Maps and/or Records |
|--|---------------------------------|

V. Hydraulic Analysis to Determine System Component Needs (Size & Condition)

If existing pipes are inadequately sized, replace or add pipe unless unusual circumstances exist.

VII. Valve and Internal Pipe Condition (7a,b)
"C" Factor Flow Tests,

Repair/replace valves needed for tests. Others noted for construction contract.

Pressure Tests
Sample for Water
Chemical Makeup

Low "C" factor due to corrosion is often accompanied with excessive internal pitting and weakening of pipe wall.

If pipe strength from pressure tests is inadequate, replace pipes.

Take water sample for Langelier Index, Silica, and Calcium Content.


VI
(7,c) VALUES / PIPES

FIELD TEST VALUES
LEAKAGE SURVEY
SOIL RESISTIVITY & COPPER
SULFATE REFERENCE
SURVEY (CATHODIC PROTECTION
SURVEY)

TO DETERMINE WHERE TO EXCAVATE
AND INSPECT PIPES

EXCAVATE & INSPECT PIPES

IF EXTERIOR IS POOR - PIPE
IS TO BE REPLACED



VII. External Inspection
 (7c) Resistivity Tests,
Excavate & Inspect Pipe
Exterior.

If pipe exterior is poor, replace pipes.

VIII. Internal Inspection
 (7d) Langelier Index, and
Chemical Test Results.
Inspect insitu pipe
interior.

Select pipe rehalitation method from IX below.

IX. Pipe Rehabilitation

Pipe is Cement Lined
and/or Calcium Buildup
(+) Langelier Index,

Pipe is unlined, rust
tuberculation, red water,
(-) Langelier Index

Special Circumstances


<u>Low Silica</u>	<u>High Silica</u>
Soft, poor	Hard, firm
pipewall	pipewall
bonding	bonding
(Pig Lines)	(Clean*)

<u>Low Silica</u>	<u>High Silica</u>
Soft, poor	Hard, firm
pipewall	pipewall
bonding	bonding
Pig & Treat**	Clean* &
Water	Cement Line Pipes

-Sandblast & Epoxy Coat
 -Insitu Plastic Lining

*Mechanically Clean.

**Treat to positive Langelier index and add sodium hexametaphosphates.




ATTACHMENT B
HYDRAULIC ANALYSIS METHOD FOR STEP 6
OF THE WATER REHABILITATION GUIDE

While this method does not have to be rigidly followed, it is included as a guide for hydraulic analyses of water systems and should be used or adapted when appropriate for the system being studied. Computer model water and pressure demands are to be modified according to available information. For example, the future growth of a station may not be 25 percent to 50 percent as presented herein. All future planned water using projects served by the water system shall be located on a map or in a table, indicating average, daily and peak water consumptions. These values will be added to existing water demands for the appropriate computer model demands.

Hydraulic analyses should ordinarily be done by hand computations, and computers used when the system is so looped or complicated as to make hand computation tedious or impossible. Hand computations are easier to review than checking computer input/output data. Simple sketches facilitate reviewing both hand and computer computations.

Wherever possible, water distribution systems should be skeletonized and reduced by using equivalent pipes. This will decrease hand computations and model input data, reduce the opportunity for mistakes and the time needed for corrections. Skeletonizing will also make the results more conservative. Takeoff's from a computer models's main looped system can be done by hand computations. Water distribution maps showing pipe sizes, lengths, materials, junctions, junction elevations, demands and model pipe/junction identification notations are needed to understand computer data inputs and results. Pump curves should also be included, along with a sketch of the pumps and all the elevated towers, showing their elevation relationship with each other and to the common datum used for the distribution maps. Pump station and other significant minor losses should be carefully computed and included in the model data or hand computations.



HYDRAULIC ANALYSIS

1. Determine the total metered demand for as long a period as convenient (at least one year) and compute the average, lowest and peak days.
2. Divide system into areas according to type of structures (housing, commercial, industrial, piers, storage, maintenance, training, hangars, power/steam plants, etc.).
3. Compute the expected consumption for each area in GPD.

a. Housing/Barracks = 90 GPCD x (number of 24-hour persons)
offbase residents (e.g., civilians) = 1/3 of a 24-hour resident

b. Piers - 50 GPCD x (number of 24-hour ships personnel)

c. Other - known water usage GPD

d. Expected water consumption - Total of Lines (a), (b), and (c)

e. Daily consumption per junction = Lines ((a) + (b), + (c)),
divided by number of junctions in the area

f. Total expected consumption = sum of all areas from (d) _____

g. Unaccounted for water = total metered daily (average) - Line (f) _____

h. Unaccounted for water/junction = Line (g)/total number of
junctions _____

i. Average Day GPM demand (Assign to each junction) = (Line (e) +
Line (h)) divided by 1,440

j. Maximum Day GPM (each junction) = (2.25 x Line (e) + Line (h))
divided by 1,440

k. Peak Hour GPM (each junction) = (4 x Line (e) + Line (h))
divided by 1,440

l. Fire flows for each area - Add the maximum fire consumption GPM
at most critical appropriate junction to the Average Flow
for that junction (Line (i)).

m. Extended period simulations (EPS) - Flow variations during the
day. ¹




Gallons Per Minute on Maximum Day for each junction by hour

Midnight - 6 A.M.:	(0.45	(²) x Line (e) + Line (h))	divided by 1,440
6 A.M. - 9 A.M.:	(3.60	x Line (e) + Line (h))	divided by 1,440
9 A.M. - 11 A.M.:	(5.63	x Line (e) + Line (h))	divided by 1,440
11 A.M. - 11 A.M.:	(2.81	x Line (e) + Line (h))	divided by 1,440
5 P.M. - 8 P.M.:	(3.04	x Line (e) + Line (h))	divided by 1,440
8 P.M. - Midnight:	(0.79	x Line (e) + Line (h))	divided by 1,440


NOTES:

- (1) Hourly industrial/commercial, etc. variations may be different from housing/barracks patterns, but considering them the same does not ordinarily introduce much error. If the industrial/commercial non-housing/barracks water using facility (Line (c)) consumes a large portion (more than 25 percent) its total area consumption, it should be computed separately for growth, peaking, and hourly variations (i.e., for hourly variations, it should not be included in EPS demands as part of Lines (c) and (e), but added to the hours of the EPS according to its own past hourly usage patterns).
- (2) Twenty percent of maximum day for early AM hours = $0.2 \times 2.25 = 0.45$



4. Criteria for Analyses:

- a. Maximum day and peak hour minimum system pressure greater than 35 psig
 - b. Pumps sized so all peaks can be met with the largest pump down (out of service).
 - c. Fire pump suction greater than 20 psig when taking suction from a distribution system
 - d. Elevated tanks should not empty during Extended Period Simulations (EPS).
 - e. Storage will be for at least one average day's demand or fire protection needs plus 1/2 average day's demand, whichever is greater.
 - f. If fire protection is provided by system water pumps, elevated tank altitude valves should close when pumps are turned on.
 - g. Water supply/treatment should be able to provide the maximum day's demand in one day, or the average day's demand and replenish water within 48 hours used for the greatest fire, whichever is greater.
 - h. Hazen Williams "C" friction factors tests will be done in accordance with Navy "Water Pipe Rehabilitation Guide" - Attachment C.
 - i. Fire Flow Analysis, Line (1) should meet fire protection flow/pressure requirements for sprinklered and non-sprinklered buildings in accordance with MIL-HABK-1008 30 April 1985 (MHB). Hose stream demands can be divided between the hydrants that can service the building (See MHB Section 5 and Table 5-2). Sprinkler requirements not computed directly from the sprinkler system layout can be determined by the flow computed from the density design and areas (MHB Section 6 and Table 5-1).
 - j. The model will be calibrated by changing "C" factors and optionally the pipe diameters, so that "C" factor field tests and model results (flow and pressure) are reasonably close. The computer calibration pressure results should be less than those found in the field tests (i.e., greater head losses).
5. Computer simulations will be run to determine how well the criteria of paragraph 4 are met. System changes in pumping, changing "C" factors to C=110 and pipe diameters to nominal diameters (to simulate pipe cleaning), and making pipe additions will be selectively made until the computer model results are adequate. The pipes that are found to need cleaning will be noted for Step 7 (testing) of the "Water Pipe Rehabilitation Guide."



ATTACHMENT C
HAZEN WILLIAMS "C" FACTOR
BY FLOW TEST

This flow test is to evaluate the internal condition of a pipe in regard to its resistance (friction) to water flow for a given pipe size (i.e., increased roughness or decreased diameter because of internal pipe buildup).

Energy in the form of pressure is needed to overcome the friction resistance. As the flow increases, the friction increases and there is a pressure (energy) loss to overcome the friction and maintain the flow.

This flow test measures the pressure (energy) loss between two pressure gages on a pipe line for a given hydrant flow. The flow is related to the pressure loss and the friction factor "C" by the Hazen Williams formula below.

Hazen Williams Formula: $V = 1.318 C R^{0.63} S^{0.54}$

Where V is the water velocity in feet/second, C is the Hazen Williams factor, R is the hydraulic radius equal to one fourth of the pipe diameter in feet (D/4) for a pipe flowing full, and S is the hydraulic gradient in feet/foot.

The line is valved so that all the measured water that is discharged through the flow hydrant passes both gages (Figure 1).


The "C" values are computed on Form 1 using a modification of the Hazen Williams formula where again C is the Hazen Williams factor, Δp is the pressure loss in (psig), d is the internal pipe diameter in inches, L is the pipe length between gages in feet, and Q is the flow hydrant discharge in gpm. The Form 1 graphs solve the equation for the flow with C=100 from L/ Δp and d values. The pipe C factor is then calculated by dividing the actual flow by the graph flow. Examples are shown following Form 1.

Modified Hazen Williams:

$$C = \left[\frac{4.52 L}{\Delta p d^{4.87}} \right]^{0.54} Q$$

NOTES:

- (1) STATIC PRESSURES (STAT) are pressures taken prior to opening a hydrant and flowing water (little or no flow of water). If the pressure gage fluctuates, it is the average of the fluctuations.
- RESIDUAL PRESSURES (RESID) are pressures taken after a hydrant is opened (large flow of water is being maintained).
- (2) Three calibrated (0 to 100) psig pressure gages with fittings to connect them to hydrant nozzles or hose bibs are required.



3. The test is most accurate when performed during the hours of low water use (night time). In most cases, the error caused by water usage during the day is not great. The "C" value calculated during the day can be used because water usage flow is generally much less than the fire hydrant test flow. (Exception - if a gage is mounted on a building hose bib, water usage to the building through the relatively small building connection can seriously affect the results.)

4. Pipeline length "L" can be scaled from water system maps in feet.

5. This method has been used many times and the form is easy to fill out and use in the field.

6. All inoperative and leaky valves should be replaced prior to flow testing.

7. Be sure to open all line valves and close hydrants when the tests are completed.

8. The test may be made while the line is set up for cleaning. Figure 2 is a typical "pigging" set up. If a valve (VD) is attached to the downstream end of the pipe, it can be closed between pig runs, and the upstream valve (VU) opened to pressurize the line. The test can then be made in the normal manner from a hydrant between the upstream gage mounted on the launcher, and the downstream gage near the retrieval "T".

9. The parallel pipe method of testing the internal condition of a water pipe to measure its Hazen Williams "C" factor may be used in lieu of three gages (Figure 3). It should be used for larger diameter pipes (10-inch and above). The method requires laying hose between hydrants, but is more precise and a smaller head loss can be accurately measured (see Method 2 for details). A differential pressure gage is used to measure the pressure drop. This is an advantage for larger pipes because it avoids the immense discharge of water that is required to produce the head loss needed when the three gage method is used on larger pipes.


Note:

The differential gage should be a Dwyer Model 4205B or equivalent. Cost is under \$200.

10. Figure 6 shows how a flow test can be made when the pipe cannot be isolated because of inoperative or leaking valves. The valves must be completely open. Gages 1 and 3 are mounted on hydrants connected to lines that have functioning valves that can be closed so that Gages 1 and 3 reflect the pressures at the left and right pipe junctions. A small amount of leakage through the operative valves should not significantly affect the results.

Judicious use of this method to allow testing with inoperative or leaking valves identified during the preliminary valve tests should reduce the number of valves that have to be repaired or replaced for the A/E pipe testing and inspection contract.

The equation is cumbersome to use, but it can be done with a programmable calculator. A computer program in basic is available from this office.



(1) TEST# _____ (2) LOCATION _____ (3) DATE _____ (4) TIME _____

(C=100) FLOW IN GALLONS PER MINUTE




FIG 5



(5) UP GAGE LOCATION (HYD#) _____
 (6) DOWN GAGE LOCATION (HYD#) _____
 (7) FLOW GAGE LOCATION (HYD#) _____

DIAMETER OF PIPE
 (INSIDE)


TEST BY _____ ADDRESS _____ PHONE # _____

FIRM _____

$\frac{1000 \Delta P}{L}$




SKETCH



- (8) HIGH STAT P = _____
- (9) STAT P = _____
- (10) _____
- (11) RESID P = _____
- (12) _____ } TO FIG 4
- (13) $\Delta P =$ _____
- (14) $1000 \times \Delta P / L =$ _____ } TO FIG 5
- (15) $C = \frac{\text{FIG 4}}{\text{FIG 5}} \times 100 =$ _____

PHONE _____

FORM 1



METHOD I - THREE GAGE
PROCEDURE (FIGURE 1) - USE FORM 1

- A. Fill in heading information (1) through (7).
- B. Complete sketch.
- C. Enter the upstream (furthest from the flow hydrant) and downstream (closest to the flow hydrant) static pressures on line (9). Enter the larger of the two on line (8). Subtract lines (9) from (8) on line (10). One column should be "0", and the other column should contain a pressure difference that compensates for ground surface elevation differences between the two gages.
- D. Open the flow hydrant and when the gages are steady, read all three gages. The residual pressures, are entered on line (11) with the upgage, downgage and flow hydrant pressures in their respective places. Add lines (10) and (11) for upgage and downgage totals (line 12)), then subtract the downgage total from the upgage total for p Line (13). Multiply p by 1,000 and divide by line length L Line (14).
- E. Enter Figure 4 with flow hydrant residual pressure (line (11-flow)). Cross to appropriate hydrant nozzle curve then down to hydrant flow (GPM). Enter hydrant flow in numerator, line (15). Enter Figure 5 with $1,000 \times p/L$ from line (14). Draw straight line from $1,000 \times p/L$ through pipe diameter to C=100 flow (GPM). Enter this flow in denominator of line (15). Solve line (15) for "C" factor.






FIGURE 1 (METHOD 1)



PIPE END OR
CLOSED VALVE




SHEET NO. OF
JOB NO.

SUBJECT

DATE
DATE

BY
CHKD. BY



(1) TEST# 6 (2) LOCATION NAUSTA NDRUA (3) DATE 10/17/85 (4) TIME 14:50

EXAMPLE

(C=100) FLOW IN GALLONS PER MINUTE




FIG 5

(5) UP GAGE LOCATION (HYD#) D-48
 (6) DOWN GAGE LOCATION (HYD#) D-47
 (7) FLOW GAGE LOCATION (HYD#) D-46

DIAMETER OF PIPE
 (INSIDE)

TEST BY J. K. Wood

ADDRESS NAVAL STA., NORFOLK, VA PHONE # 445 2930 (804)

FIRM CODP 114, LANTOIN

1000 AP
23511






FIG 4




SKETCH



- (8) HIGH STAT P = 70
- (9) STAT P = 65
- (10) RESID P = 5
- (11) UP 55
- (12) DN 70
- (13) ΔP = 8
- (14) $1000 \times \Delta P / L = \frac{8 \times 1000}{740} = 10.8$ } TO FIG 5
- (15) $C = \frac{\text{FIG 4}}{\text{FIG 5}} \times 100 = \frac{815}{910} \times 100 = 89$

PHONE

FORM 1





BY
DRAWN BY


DATE
DATE

SUBJECT *M*

SHEET NO. OF
JOB NO.

FIGURE 2 (METHOD 1)






METHOD 2
FORM 1
HAZEN WILLIAMS "C"
FACTOR BY HYDRANT FLOW TEST FORM
PARALLEL PIPE METHOD

PROCEDURE (FIGURE 3) USE FORM 1

- A. Fill in heading info (1) through (6).
- B. Complete sketch.
- C. Connect garden hose from hydrants to differential pressure gage (upstream hydrant to high pressure). Open upstream and downstream hydrants and bleed air from hose.
- D. Note any initial pressure before flowing hydrant. Enter on line (12 DN).
- E. Open the flow hydrant, read differential pressure again and enter on line (12 up). If differential pressure is greater than 5 psig, reduce flow hydrant discharge. If differential pressure is less than 0.5 psig, increase flow by using two hydrant nozzles, the 4-1/2 inch pumper connection, or flow two hydrants and use two flow hydrant gages. Correct by subtracting initial pressure (12 DN) from final pressure (12 up) and enter as p on line (13). Multiply p by 1,000 and divide by length (L) Line (14). Continue the same as Method 1 - i.e., look up hydrant flow on Figure 4, flow for $C=100$ from Figure 5, and calculate C from Line 15.



FLOW TEST - PARALLEL PIPE METHOD

PRESSURE CONNECTIONS






FIGURE 3
PARALLEL PIPE METHOD

8
 SUBJECT
 DATE
 BY
 CHKD. BY



(1) TEST# 7

(2) LOCATION NAUTILA NORVA


(3) DATE 10/17/85

(4) TIME 1610

EXAMPLE

FIG 5

FLOW IN GALLONS PER MINUTE



(5) UP GAGE LOCATION (HYD#) G-12
 (6) DOWN GAGE LOCATION (HYD#) G-16
 (7) FLOW GAGE LOCATION (HYD#) G-14



DIAMETER OF PIPE (INSIDE)

TEST BY J. Harwood


ADDRESS NAVAL STA, NORFOLK VA PHONE # (804) 445 2930

FIRM CODE 114, LANTOLV

1000 GP
23511
2



SKETCH



- (8) HIGH STAT P =
- (9) STAT P =
- (10)
- (11) RESID P =
- (12) $2.6 - 0.2 = 2.4$ } TO FIG 4
- (13) $\Delta P = 2.4$
- (14) $1000 \times \Delta P / L = \frac{2.4 \times 1000}{2810} = 0.85$ } TO FIG 5
- (15) $C = \frac{FIG. 4 \times 100}{FIG. 5} = \frac{1675 \times 100}{1440} = 116$

PHONE

FORM 1





FIGURE 6



$$C = \frac{2.26 Q_T}{D^{2.63} \left\{ \left[\frac{(d_2 - d_1)}{L_1} + \left(\frac{L_2}{L_3} \right) \frac{(d_2 - d_3)}{L_1} \right]^{1.54} + \left[\frac{(d_2 - d_3)}{L_3} \right]^{1.54} \right\}}$$

Where C = HAZEN WILLIAMS "C" FACTOR

d_1 = STATIC (1) - RESIDUAL (1)


d_2 = " (2) - " (2)

d_3 = " (3) - " (3)

L_1, L_2, L_3 AS SHOWN ABOVE (FEET)

D = PIPE I.D. (INCHES)

Q_T = HYDRANT (F) FLOW (GPM) FROM RESID (F) & GRAPH - FORM 1, FIG 4.



STATIONS AND PHYSICAL ANALYSIS OF WATER

FROM: (Station or unit) _____ DATE _____

TO: (Name and location of laboratory) _____

SAMPLE FROM (Location of sampling point) _____

COLLECTED BY _____ DATE _____ HOUR _____ SOURCE (Designate ground, surface, etc., etc.) _____

REASON FOR EXAMINATION _____ EXAMINATION REQUESTED BY _____

NOTE: All results reported in parts per million unless otherwise noted except for pH, temperature, and special conductance. One liter of potable water is assumed to weigh one kilogram.

I. FIELD ANALYSIS			III. ROUTINE LABORATORY ANALYSIS (CHECK ONE)	
1. pH	TEMPERATURE		REQUESTED	NOT REQUESTED
	°F	°C		
ITEM	PPM			
2. CARBON DIOXIDE (CO ₂)			1. COLOR	
3. DISSOLVED OXYGEN (O ₂)			2. TURBIDITY	
4. HYDROGEN SULFIDE (H ₂ S)			3. ALKALINITY (CaCO ₃)	
5. CHLORINE DEMAND (Cl ₂)				
FIELD ANALYSIS BY				
			4. TOTAL HARDNESS (CaCO ₃)	
DATE OF ANALYSIS			5. NON-CARBONATE HARDNESS (CaCO ₃) (By Computation)	


II. SPECIAL LABORATORY ANALYSES

Check (X) individual items to be included in the Special Analysis. Request determination only of those substances suspected of being present in significant amounts.

(X)	ITEM	PPM	ITEM	PPM
	1. As		9. CALCIUM (Ca)	
	2. Se		10. MAGNESIUM (Mg)	
	3. Pb		11. SODIUM (Na) AND POTASSIUM (K)	
	4. B		12. HYDROXIDE (OH) ^o	
	5. Cu		13. BICARBONATE (HCO ₃) ^o	
	6. Zn		14. CARBONATE (CO ₃) ^o	
	7. Cr (Hexavalent)		15. SULFATE (SO ₄)	
	8. PO		16. CHLORIDE (Cl)	
	9. Cd		17. NITRATE (NO ₃)	
	10. Cl		18. IRON (Fe) TOTAL	
	11. Phenolic Compounds (PPB)		19. MANGANESE (Mn)	
	12. Others (Specify)		20. SILICA (SiO ₂)	
	13.		21. FLUORIDE (F)	
	14.			
	15.			
	16.			

REMARKS (Such as unusual appearance, taste, odor, etc.) _____

LABORATORY ANALYSIS BY _____ DATE OF ANALYSIS _____



WATER TREATMENT INFORMATION

When the costs of replacement or cleaning and cement lining are compared with cleaning and water treatment, the following costs should be added to the latter.

1. Present value of treatment equipment (20-year life)

a. To raise Langelier index (pH & alkalinity)

Small Systems: (Less than 1 MGD) Soda ash feeders & solution tank.

Large Systems: (More than 1 MGD) Lime feeders, slaking tanks, sedimentation tanks, filters, CO₂ addition.

b. For corrosion control - (small & large)

Chemical feeders - Sodium Hexametaphosphate.

2. Present Value (20 years) of annual

a. Operation & maintenance costs,

b. Energy costs,

c. Chemical costs.

3. Present value (20 years) estimation of annual water cost savings in leakage reduction that would result from cement lining or pipe replacement. (Significant only if leakage is large and water is expensive).

ECONOMIC ANALYSIS

- I. Cost of New Pipe _____ I
- II. Cost of Cleaning and Cement Lining _____ II
- III. Cost of Pigging or Cleaning without Lining _____

If water is aggressive (negative Langelier Index),
add to III.

a. Cost of treatment equipment ¹ _____

b. Annual costs

O&M _____

Power _____

Chemicals _____

Leakage ² _____

Total _____ X 8.933 ³ = _____

Total = _____ III


Select most cost effective I, II, or III.

NCTE: Power escalation rate is omitted above but should be considered on a case by case basis (unusually high power costs or large repair projects (10 MGD)).


- (1) From equipment vendors.
- (2) Cost of estimated leakage reduction expected from new pipes or cement lining. (In absence of better information, leakage can be taken as one-half of the unaccounted for water).
- (3) Discount rate for 20 years at 10 percent.

COPPER SULFATE REFERENCE ELECTRODE MEASUREMENTS

ATTACHMENT E




ELEVATION



PLAN

SOIL RESISTIVITY - COPPER SULFATE POTENTIAL RELATIONSHIPS.

Potential of Ferrous Pipe in Volts to a Copper Sulphate Reference Electrode	Soil Resistivity Ohms per Centimeter Cube For Short (ohm-cm)		
	Very low to low (500 to 1,000)	Medium (1,000 to 10,000)	High to Very High (10,000 to 100,000)
-0.4 or ^{more} less	possibly possibly corrosive	possibly probably corrosive	noncorrosive
-0.4 to -0.5	mildly corrosive	possibly probably corrosive	possibly probably corrosive
-0.5 to -0.6	corrosive	mildly corrosive	possibly possibly corrosive
-0.6 or ^{higher} less	very corrosive	corrosive	mildly corrosive



ATTACHMENT B

WATER PIPE SYSTEM REHABILITATION
STEPS TO DETERMINE CONDITION OF EXISTING
SYSTEM AND MAKE IMPROVEMENTS

Contracts

- I. To Locate Areas for Inspection and Test.
 - A. Field Test Valves and Leaking Survey - Pages I, II and III
 - B. Cost Estimate and Pages IV, V, VI and VII
 - C. Cathodic Potential Survey
 - D. Water Sampling Analysis (Treatment Needs)

- II. To Determine What the System Requirements Are.
 - A. Hydraulic Analysis (incl preliminary friction "C" Factor flow tests, data Gathering (system, polulation, maps, industrial, washing, and ship potable water usage, future expansion plans ... etc., ...)
 - B. Water Treatment Design Study.

- III. To inspect and Test System
 - A. Purchase and Install Valves (From I-A)
(Inspect and Record Pipe Condition) - Page VIII
 - B. Excavate Pipes (From I-C)
(Inspect and Record Pipe Condition) - Page VII
 - C. Do "C" Factor Flow Tests (If Needed) - Attachment A
 - D. Do Pressure test (If Needed)

- IV. Construction Project to Improve System
 - A. Install Pipes/Pumps etc., (From II)
 - B. Replace Pipes/Hydrants etc., (From III)
 - C. Clean Pipes if needed (From II-B and III)
 - D. Construct/install treatment (From I-D and II-B)

ATTACHMENT B

WATER PIPE SYSTEM REHABILITATION
STEPS TO DETERMINE CONDITION OF EXISTING
SYSTEM AND MAKE IMPROVEMENTS

Continued

I. To Locate Areas for Inspection and Test.

- A. Field Test Valves and Leaking Survey - Pages I, II and III
- B. Cost Estimate and Pages IV, V, VI and VII
- C. Cathodic Protection Survey
- D. Water Sampling Analysis (Treatment Needs)

II. To Determine what the System Requirements Are.

- A. Hydraulic Analysis (find preliminary friction "C" water flow rates, data gathering (system, collection, map, industrial, residential, and other potable water usage, future expansion plans ... etc., ...)
- B. Water Treatment Design Study.

III. To Inspect and Test System

- A. Reinspect and Field Test Valves (From I-A)
(Inspect and Record Pipe Condition) - Page VIII
- B. Reinspect Pipes (From I-B)
(Inspect and Record Pipe Condition) - Page VII
- C. Do "C" Factor Flow Tests (If needed) - Attachment A
- D. Do Pressure Test (If needed)

IV. Construction Project to Improve System

- A. Install Pipe/Joints etc., (From II)
- B. Replace Pipes/Joints etc., (From III)
- C. Clean Pipes if needed (From II-B and III)
- D. Construct/Install Treatment (From I-B and II-B)

SCOPE OF WORK
PIPE AND VALVE INSPECTION
LEAKAGE DETECTION SURVEY
AND DESIGN OF VALVE REPLACEMENT WORK

General Intention. It is the intention of this contract to provide a survey of the potable water valve and distribution systems at the MCAS, New River and Camp Geiger, Camp Lejeune, North Carolina.

NOTE: The term "Engineer" shall refer to the parties associated with the recipient of this contract.

The term "Navy" shall refer to the office designated to act for the Navy.

1. General Requirements. The engineer shall furnish all labor and material necessary to perform a survey of the underground valve and distribution lines in accordance with this specification.

a. Workmanship. All work shall be accomplished as directed by and to the satisfaction of the Navy.

The Navy Public Works Department shall furnish station plans of the existing water distribution system. Also, the Navy shall be responsible to oversee the manipulation of necessary valves as required, and provide other minor assistance during the survey. Normally it is anticipated that the Contractor shall perform his work with minimum requirements from the Public Works Department.

b. Scheduling the work. Immediately after award, the Contractor shall meet with the Navy and prepare a schedule of work. The Contractor shall conduct his operation so as to cause the least possible interference with normal operation of the activity. The normal working hours are from 7:30 A.M. to 4:30 P.M., Monday through Friday.

c. Security Requirements. No employee or representative of the Contractor shall be admitted on the site unless he furnishes satisfactory proof that he is a citizen of the United States or if an alien, that his residence within the United States is legal.

1. Services. The engineer shall conduct on-site surveys of the fresh water distribution systems to determine the location of inoperative valves, leaks and other sources of water waste. There are approximately 25 miles of water lines to be surveyed and 560 valves and 215 hydrants to be tested.

2. Detail Requirements.

a. Conduct a water leakage survey of all potable water mains, laterals, feeders, hydrants and valves. Manipulate valves and hydrants to insure proper operation. Detection of the leaks can be accomplished by the use of electronic sonic devices or other instruments or means. The use of these

SCOPE OF WORK
PUMP AND VALVE INSPECTION
LEAKAGE DETECTION SURVEY
AND DESIGN OF VALVE REPLACEMENT WORK

General Intention. It is the intention of this contract to provide a survey of the potable water and distribution systems at the MCRS, New River and Camp Geiger, Camp Lejeune, North Carolina.

NOTE: The term "Contractor" shall refer to the parties associated with the recipient of this contract.

The term "Navy" shall refer to the office designated to act for the Navy.

1. General Requirements. The engineer shall furnish all labor and material necessary to perform a survey of the underground valve and distribution lines in accordance with this specification.

a. Workmanship. All work shall be accomplished as directed by and to the satisfaction of the Navy.

The Navy Public Works Department shall furnish station plans of the existing water distribution system. Also, the Navy shall be responsible to oversee the manipulation of necessary valves as required, and provide other labor assistance during the survey. Normally it is anticipated that the Contractor shall perform the work with minimum requirements from the Public Works Department.

b. Scheduling the work. Immediately after award, the Contractor shall meet with the Navy and prepare a schedule of work. The Contractor shall conduct his operation as to cause the least possible interference with normal operation of the activity. The normal working hours are from 7:30 A.M. to 4:30 P.M., Monday through Friday.

c. Security Requirements. No employee or representative of the Contractor shall be admitted on the site unless he furnishes satisfactory proof that he is a citizen of the United States or its ally, that his residence is within the United States or its ally.

d. Services. The engineer shall conduct on-site surveys of the fresh water distribution system to determine the location of inoperative valves, leak and other sources of water waste. There are approximately 12 miles of water lines to be surveyed and 200 valves and 215 hydrants to be tested.

2. Detail Requirements.

a. Conduct a water leakage survey of all potable water mains, laterals, leaders, hydrants and valves. Manipulate valves and hydrants to insure proper operation. Detection of the leak can be accomplished by the use of electronic sonic devices or other instruments or means. The use of these

instruments shall be by trained and qualified persons. Detecting locating, and quantifying water leaks shall be carried out from the surface. During the survey, there should normally be no need to expose the underground pipes or valve. Identify, when possible, pipe material (i.e., P.V.C., R.C., asbestos-cement or cast iron). Valve leakage can be determined by selectively flowing hydrants, manipulating valves, noting hydrant flow rates and listening to valve leakage noises with sonic electronic equipment (leak detector). Make cassette recording tapes of the valve leakage noise at various leakage rates for each valve size and type. This can be done by manipulating a valve and measuring flows from a connecting hydrant in an isolated part of the system. These tapes then can be used to facilitate subsequent valve leakage tests.

The tapes with leakage noises and associated flows will become the property of the Navy upon completion of the Contract.

3. Provide a draft written report to include a description of the systems, a description of the survey identifying and locating by sketch or table hydrant and valve numbers and each leak showing location and flow. In addition to valves located on the map, each valve will be identified by number or number scheme so that it can be cross referenced to the map. The following information shall be given for each valve:

Valve number, location, (map number, grid)
Valve size, rotation to close (right, left)
Valve opens/closes completely and freely (Y/N) describe if no
Valve leakage (much, some, little, none)

NOTES: (i.e., Buried, hard to gain access and why, etc.)

Include a representative leak repair cost per type of leak, and a list locating valves and hydrants with conditions and rehabilitation recommendations. Also, provide design plans and specifications showing the locations, sizes, details of the valve replacements with cost estimates. The draft is for comments and will be followed by a final report which will also address the draft comments.

4. The Marine Corps Base, Camp Lejeune shall be furnished two copies of the draft and the original final report, plans and specifications after it has been reviewed, corrected, collated, summarized, indexed and bound. Provide one copy of the draft and final reports to each of code 405, 408, 1013G, 2011B and 114, Atlantic Division, Naval Facilities Engineering Command, Naval Station, Norfolk, Virginia 23511-6287.

5. Time for Completion. The work and a draft report shall be completed within ninety days after date of receipt of a notice of award authorizing the contractor to proceed. The Navy review time is 15 days, and the final report is required 15 days after the review.

6. The Marine Corps will:

a. Provide (1) experienced personnel to monitor valve operation, (2) appropriate lights and shelter boxes for protection of the engineer's measuring instruments.

Installments shall be by trained and qualified persons. Detecting, locating, and quantifying water leaks shall be carried out from the surface. During the survey, there should normally be no need to expose the underground pipes or valve. Identify, when possible, pipe material (i.e., P.V.C., etc.), asbestos-cement or cast iron). Valve leakage can be determined by selectively flowing hydrants, manipulating valves, noting hydrant flow rates and listening to valve leakage noises with sonic electronic equipment (leak detector). Make cassette recording tapes of the valve leakage noises at various leakage rates for each valve size and type. This can be done by manipulating a valve and measuring flows from a connecting hydrant in an isolated part of the system. These tapes then can be used to facilitate subsequent valve leakage tests.

The tapes with leakage noises and associated flows will become the property of the Navy upon completion of the contract.

3. Provide a draft written report to include a description of the systems, a description of the survey identifying and locating by sketch or table hydrant valve numbers and each leak showing location and flow. In addition to valve location on the map, each valve will be identified by number or number scheme so that it can be cross-referenced to the map. The following information shall be given for each valve:

- Valve number, location, (map number, grid)
- Valve size, rotation to close (right, left)
- Valve type/closes completely and freely (Y/N) describe if no
- Valve leakage (none, some, little, none)
- Notes: (i.e., buried, hard to gain access and why, etc.)

Include a representative leak repair cost per type of leak, and a list of locations and hydrants with conditions and rehabilitation recommendations. Also, provide design plans and specifications showing the locations, sizes, details of the valve replacements with cost estimates. The draft report shall be followed by a final report which will also address the draft comments.

4. The Marine Corps user, upon request shall provide two copies of the draft and the original final report, plans and specifications after it has been reviewed, corrected, collated, summarized, indexed and bound. Provide one copy of the draft and final reports to each of code 402, 408, 4030, 2011B and 11A, Atlantic Division, Naval Facilities Engineering Command, 2091 Station, Norfolk, Virginia 23511-011A.

5. Time for completion. The work and a draft report shall be completed within thirty days after date of receipt of a notice of work authorizing the contractor to proceed. The review time is 15 days, and the final report is required 15 days after the review.

6. The Marine Corps will:

- a. Provide (1) experienced personnel to monitor valve operation, (2) appropriate lights and safety boxes for protection of the engineer's working instruments.

b. Make available old and current system prints to facilitate locating "abandoned" but flowing lines.

c. Provide all necessary labor and materials to repair any leaks caused by valve manipulation or accidental breaks in accordance with a schedule to be determined by the Government.

d. Furnish to the engineer all available drawings of the water distribution and collection system that are needed for the contract.

h. Make available old and current system prints to facilitate locating "abandoned" but flowing lines.

c. Provide all necessary labor and materials to repair any leaks caused by valve manipulation on accidental breaks in accordance with a schedule to be determined by the Government.

d. Furnish to the engineer all available drawings of the water distribution and collection system that are needed for the contract.

COST ESTIMATE FOR VALVE/PIPE INSPECTIONS

Cost estimate - inspect 560 valves (6 inches and larger) and 215 hydrants and hydrant valves. Assume average size = 8 inches (adjusted for increased difficulty closing larger sizes), - four persons testing - 16 valves/day and 25 hydrant and valves/day (1 engineer/3 technicians).

	<u>Man Days</u>			
	<u>Project Manager</u>	<u>Engineer</u>	<u>Technician</u>	<u>Typist</u>
1. Review records, interview personnel, obtain info on pipe and valve cond. and age.		1		
2. Plan Valve Tests		3	3	
3. Field Test Valves and Hydrants (2)		44	3 persons @ 44 days = 147	
4. Write report and cost estimate for design contract	1	3		4
	—	—	—	—
Man days	1	51	132	4
Day cost/persons (2)	<u>144</u>	<u>128</u>	<u>112</u>	<u>96</u>
Subtotals	<u>144</u>	<u>6528</u>	<u>14,784</u>	<u>384</u>
Totals	21,840			
OH&P at 100 percent	21,840			
Contingencies at 5 percent	<u>2,184</u>			
Valve Inspections	45,864			

Expenses:

Travel - 4 persons at \$304/Roundtrip =	1,216
Per Diem days: Records and Planning = 4 days	
Inspect and test = 44 days	
6 weekends	<u>12</u>
60 days x 4 @ 50 =	12,000
Car rental 1 car x 60 days @ 50/day	= <u>3,000</u>
Total Expenses	= 16,216
Total valve inspection and test cost (45,864+16,216)	= 62,080

COST ESTIMATE FOR VALVE/PIPE INSPECTIONS

Cost estimate - inspect 500 valves (6 inches and larger) and 215 hydrants and hydrant valves. Assume average size = 4 inches (adjusted for increase in difficulty clearing larger sizes) - four persons working - 1 valve/day and 25 hydrant and valves/day (1 engineer/3 technicians).

Man Days
Project Manager/Engineer/Technician (total)

1	Review records, interview personnel, obtain info on pipe and valve cond. and age.	1	1	1
2	Plan Valve Tests	3	3	3
3	Field Test Valves and Hydrants (2)	44	44	44
4	Write report and cost estimate for design contract	3	3	3
<hr/>				
		51	51	51
		132	132	132
		388	388	388
		1,384	1,384	1,384
		132	132	132
		96	96	96
		388	388	388
		1,384	1,384	1,384
		132	132	132
		96	96	96
		388	388	388
		1,384	1,384	1,384

Expenses:

Travel - 4 persons at \$704/round-trip = 1,280

Per Diem days: Records and Planning = 4 days = 400

Inspect and test = 44 days = 4,400

6 weekends = 1,200

Car rental 1 car x 60 days @ 20/day = 1,200

Total Expenses = 8,160

Total valve inspection and test cost (42,880+10,218) = 53,098

COST ESTIMATE FOR LEAKAGE SURVEY

	<u>Man Days</u>			
	<u>Project Manager</u>	<u>Engineer</u>	<u>Technician</u>	<u>Typist</u>
<u>A&E</u>				
Review records/maps			2p x 2 days	
Plan Survey			= 4 M.D.	
Report	$\frac{3}{3}$		<u>4</u>	$\frac{4}{4}$
Rate	144		112	96
	432		448	384

Total = 1264
 OH and Prof @ 100% 1264

Subtotal = 2,528

Survey 25 mi x $\frac{\text{day}}{1.5 \text{ miles}}$ = 17 days x \$600/day = 10,200

Expenses:

Travel - 2 persons at \$304/Roundtrip = \$ 608
 Per Diem - 17 days + 3 weekends
 = 23 days for 2 persons x \$50 = \$ 2300
 Car - 23 days at \$50 = \$ 1150

Total Expenses = 4,058

Total leakage survey contract = 16,786

Total Valve pipe leakage contract

Valve Inspections	\$62,080
Pipe Leakage	<u>\$16,786</u>
	<u>\$78,866</u>

SAY \$80,000

NOTES:

- (1) 511 valves counted on water map and estimated in pump houses + 10 percent for map and count errors = 560 valves and 215 hydrants
- (2) 560 valves/16 valves/day = 35 days + 215 hydrants/25 per day = 8.6 days = Total = 44 days
- (3) Man Day Costrs:

	<u>Project Manager</u>	<u>Engineer</u>	<u>Technician</u>	<u>Typist</u>
Cost/hour	18	16	14	12
Cost/day	144	128	112	96

COST ESTIMATE FOR LEAKAGE SURVEY

Project Manager Engineer Technician Typist

Rate	Days	Cost
144	3	432
112	4	448
96	4	384

Total = 1264
OR and Prof @ 100% 1264

Subtotal = 2,528
Survey 25 mi x day = 17 days x \$150/day = 2,550

Expenses:

Travel - 2 persons at \$500/weekend = \$1000
Per Diem - 17 days + 3 weekends = \$2800
= 23 days for 2 persons x \$80 = \$1840
Car - 23 days at \$50 = \$1150

Total expenses = 4,098
Total leakage survey contract = 10,780

Total Valve pipe leakage contract = \$12,080
Valve Inspectors = \$10,780
Pipe Leakage = \$1,300

\$13,080

NOTES:

- (1) 211 valves counted on water meter and estimated in pump houses + 10 percent for map and count errors = 230 valves and 215 hydrants
- (2) 230 valves/10 valves/day = 23 days + 115 hydrants/23 per day = 5.0 days = Total = 28 days
- (3) 1000 per day for Project Manager Engineer Technician Typist

Rate	Days	Cost
144	3	432
112	4	448
96	4	384

NOTES:

(1) 624 valves/16 valves/day = 39 days

(2) Man Day Costs:	<u>Project Manager</u>	<u>Engineer</u>	<u>Technician</u>	<u>Typist</u>
Cost/hour	18	16	14	12
Cost/day	144	128	112	96

LEAKAGE SURVEY

	<u>Man Days</u>			
	<u>Project Manager</u>	<u>Engineer</u>	<u>Technician</u>	<u>Typist</u>
Review records/maps			2p x 2 days	
Plan Survey			= 4 M.D.	
Report	$\frac{3}{3}$		<u>4</u>	$\frac{4}{4}$
Rate	144		112	96
	432		448	384
	Total =		1264	
	OH and Prof @ 100%		<u>1264</u>	
	Subtotal		= 2528	
Survey 40.1 mi x $\frac{\text{day}}{1.5 \text{ miles}}$ = 27 days x \$600/day			= 16040	

Expenses:

Travel - 2 persons at \$304/Roundtrip	= \$ 608
Per Diem - 27 days + 4 weekends	
= 31 days for 2 persons x \$104	= \$ 6448
Car - 31 days at \$50	= <u>\$ 1550</u>
Total Expenses	\$ 8,606
Total leakage survey contract	\$27,174
Total contract: Valve pipe leakage	
Valve Inspections	\$41,698
Pipe Leakage	<u>\$27,174</u>
	<u>\$68,872</u>
SAY	\$70,000

Notes:

(1) 820 valve/day = 22 days

(2) 1200 valve/day = 10 days

Cost/day	Person	Project Manager	Technician	Typical
120	1200	120	120	12
120	1200	120	120	20

TRAVEL SURVEY

Project Manager, Technician, Typical

20 x 1 days = 4 M.I.

Review records, Plan survey

Rate	Person	Project Manager	Technician	Typical
120	1200	120	120	12
120	1200	120	120	20
Total =		1200	1200	1200

Survey 40.1 mi x day = 27 days x 4800/day = 130000
 1.2 miles

Expenses:

Travel - 2 persons at \$300/roundtrip = \$ 600
 Per Diem - 27 days + 4 weekends = \$ 648
 Gas - 21 days at \$30 = \$ 630

Total expenses \$ 8,600


Total leakage survey contract \$27,174

Total contract: Valve pipe leakage \$41,098
 Valve inspectors \$27,174
 Pipe leakage \$13,924
 Total \$82,196

VALVE UNIT COST ESTIMATE FOR MAINTENANCE CONTRACT

	<u>Material</u>	<u>Labor</u>	<u>Total</u>	<u>25 percent O&P</u>	<u>Total</u>
3 and 4-inch replace	240	200	440	110	550
6-inch replace	295	200	495	124	619
8-inch replace	425	200	625	156	781
10-inch replace	650	250	900	225	1,125
12-inch replace	800	250	1,050	263	1,313
14-inch replace	1,600	250	1,850	463	2,313
16-inch replace	2,300	280	2,580	645	3,225
18-inch replace	3,500	300	3,800	950	4,750

Pit excavation for valve work and pipe examination




Cost/Pit = \$88

For bituminous pavement removal and replacement add \$455

For reinforced concrete pavement removal and replacement add \$1,031

Sheeting and Shoring add \$400

Dewatering (Well Point) - 8 hours/pit - \$25,000/month



SPECIAL SPECIFICATIONS FOR VALVE REPAIR WORK

Excavate the valve and examine the exteriors of connecting pipes for corrosion and pitting. When the valve is removed examine the interior of the connecting pipes for cement lining or corrosion buildup. Determine the type of incrustation (Rust tuberculation, scale), its thickness, hardness, color, and adherence to pipe walls. Interior pipe examination should also be made during valve inspection work. If the pipe exteriors or interiors are deteriorating or have a rust buildup, record this for future pipe replacement. Replace valve with a properly operating, non-leaky valve.

PIPE EXAMINATION (EXTERIOR)

Excavate about 7 feet of pipe where the tests shown in Corrosion Survey indicate corrosive soils, and examine the pipe exteriors for deterioration. Rust, pits, and soft spots will be noted. Striking suspicious looking places with a hammer will often reveal soft or deteriorated pipe. Note pieces flaking off when struck. If a pipe is fairly new and is found to be badly deteriorated on the outside, replacement with an exterior protected pipe is indicated. If the pipe is old, and the exterior deterioration is minimal, it can be assumed that there are many more years of useful life remaining for the pipe. Exterior examination of pipes should also be made during valve excavation and replacements.

STANDARD SPECIFICATIONS FOR VALVE REPAIR WORK

Excavate the valve and examine the exterior of connecting pipes for corrosion and pitting. When the valve is removed examine the interior of the connecting pipes for cement lining or corrosion buildup. Determine the type of incrustation (rust tuberculation, scale), its thickness, hardness, color, and adherence to pipe walls. Interior pipe examination should also be made during valve inspection work. If the pipe exterior or interior are deteriorating or have a rust buildup, record this for future pipe replacement. Replace valve with a properly operating, non-leaky valve.

PIPE EXAMINATION (EXTERIOR)

Excavate about 7 feet of pipe where the tests shown in Corrosion Survey indicate corrosive soils, and examine the pipe exterior for deterioration. Rust, pits, and scale spots will be noted. Striking suspicious looking places with a hammer will often reveal soft or deteriorated pipe. Note places flaking off when struck. If a pipe is fairly new and is found to be badly deteriorated on the outside, replace and with an exterior protected pipe is indicated. If the pipe is old, and the exterior deterioration is minimal, it can be assumed that there are many more years of useful life remaining for the pipe. For the examination of pipe should also be made during valve excavation and replacement.

SECTION A FOR USE BY REQUESTER	1. FROM (Activity and location) Commanding General, Marine Corps Base Camp Lejeune, NC 28542		2 TO Commander, Atlantic Division, Naval Facilities Engineering Command Norfolk, VA 23511 (Attn: O9A21B3/M. Bryant.)	
	3. REFERENCE(S)		4. ESR IDENTIFICATION NUMBER (if applicable) 9E84	
	5. ENCLOSURE(S) (check) <input type="checkbox"/> NAVCOMPT 140 <input type="checkbox"/> OTHER (specify) <input type="checkbox"/> NAVCOMPT 2038 <input type="checkbox"/> NAVCOMPT 372		6. TYPE OF FUNDING (check) <input type="checkbox"/> O&MN <input checked="" type="checkbox"/> OTHER (specify) <input type="checkbox"/> NIF O&MMC <input type="checkbox"/> NAF	
	7. TYPE OF SERVICES REQUESTED Engineering Study to investigate Water Distribution System at Marine Corps Air Station (Helicopter)		8. DESIRED COMPLETION DATE January 1985	
SECTION B FOR USE BY EFD	9. DESCRIPTION OF WORK I. GENERAL: Provide an engineering study to investigate the Water Distribution System at Marine Corps Air Station (Helicopter), New River, Jacksonville, NC. II. BACKGROUND: a. Presently, the MOQ area is served by an 8-inch dead end distribution line. This creates stagnant water and low water pressure. MOQ 2003 is an			
	10. FOR INFORMATION CONSULT (Name and phone) G. S. JOHNSON, JR. AV: 484-5161		11. OFFICIAL REPRESENTATIVE (Signature) C. A. JOHANNESMEYER By direction	
	1. SCOPE OF SERVICES		12. DATE 26 JUN 1984	
			2. DATE RECEIVED 16 July 1984	
SECTION C INTERIM ENDORSEMENT	1. REMARKS			
	2. EST. COMPLETION DATE 31 JAN 1986		3. AUTHORIZED REPRESENTATIVE (Signature) J.R. Bailey	
			4. DATE 24 SEP 1985	
SECTION D FINAL ENDORSEMENT	1. ENCLOSURE(S) <input type="checkbox"/> DRAWINGS AND MAPS <input type="checkbox"/> SPECIFICATIONS <input checked="" type="checkbox"/> REPORT <input type="checkbox"/> OTHER (specify)			
	2. EST. COST (if applicable) \$		3. AUTHORIZED REPRESENTATIVE (Signature) J. R. BAILEY By direction	
		4. DATE OF COMPLETION 6 APR 1987		

COPY TO FAC; COMP: MAIN

18101

10/10/10

10/10/10

8

emergency pumping station with a 300,000 gallon ground storage reservoir for emergency fire protection. This station is considered inadequate for a potable water source. Presently, water is wasted by overflowing the reservoir to maintain the minimum chlorine residual.

b. Presently, the whole Camp Geiger area is served by an 8-inch line. If the demand is not met by Marine Corps Air Station, it is assisted by TC-501 pumping station at Camp Geiger. TC-501 contains a ground water storage tank with a capacity of 872,000 gallons. If too much water is delivered through this line, the nearest elevated tank at Camp Geiger (TC-1070) will overflow while the other elevated tank (TC-606) will decline. The controls for the distribution pumps located in TC-501 are controlled from TC-606 elevated tank.

c. The only method of filling the 872,000 gallon reservoir is through a gate valve located in the distribution line at TC-501. If the valve is opened too much, the water being pumped from TC-501 will recirculate through the distribution line and return to the reservoir. As this occurs, the distribution pressure continues to drop since no water is being delivered except from MCAS. If this continues, the elevated tank (TC-1070) will overflow.

III. DETAILS OF WORK:

a. Investigate water distribution system for Camp Geiger and MCAS(H), New River, including delivered water pumps and water tanks.

b. Determine the size of distribution lines, pumping systems, and storage tank capacities.

c. Provide preliminary drawings and a cost estimate to develop a project to correct deficiencies.

IV. TIME REQUIREMENTS: Completion of study is required by January 1985 to maintain fire protection system.

V. FUNDS AVAILABLE: This Command will furnish O&MMC funds on request.

VI. POINT OF CONTACT: Mr. G. S. Johnson or Mr. David Southerland, Base Maintenance Division, AV: 484-5161; FTS: 676-5161.






FIGURE 1 - MAXIMUM DAY

BY _____ DATE _____
 CHKD. BY _____ DATE _____
 SUBJECT _____
 SHEET NO. _____ OF _____
 JOB NO. _____




ENCL (G)



BY _____ DATE _____
 CHKD. BY _____ DATE _____


SUBJECT _____


SHEET NO. _____ OF _____
 JOB NO. _____






DEMAND GPM

FIG 1 - MAXIMUM DAY
 SCHEME II - IMPROVED SYSTEM 4" 10" DIA TO CP 6162K







SKETCH

(8)	HIGH SMT P =	65	65	2000 GPM
(9)	STAT P =	63	65	
(10)		2	50	
(11)	RESID P =	62	50	14# [TO FIG 4]
(12)		64	50	(4 1/2\"/>

(13) ΔP = 14#


(14) $1000 \times \Delta P / L = \frac{14000}{1300} = 10.8'$ (TO FIG 5)

(15) $C = \frac{FIG 4 \times 100}{FIG 5} = \frac{2000}{1700} \times 100 = 119$



TEST BY _____ ADDRESS _____ FIRM _____ PHONE _____

ENCL (1)

ENCL (1)



(1) TEST# 2 (2) LOCATION MCAS NEW RIVER (MO & AREA) (3) DATE 4/17/87 (4) TIME 11:00 AM




SKETCH

	UP	DN	FLOW
(8) HIGH STAT P =	64 #	64 #	
(9) STAT P =	62 #	64 #	
(10)	2	-	2 1/2\"/>
(11) RESID P =	+17	10	7.5 # [TO FIG 4]
(12)	19		
(13)	10		
(13)	ΔP = 9		
(14)	$1000 \times \Delta P / L = \frac{9000}{938} = 9.7$ (TO FIG 5)		
(15)	$C = \frac{FIG 4 \times 100}{FIG 5} = \frac{45000}{405} = 111$ (O.K.)		

TEST BY _____ ADDRESS _____ FIRM _____ PHONE _____

ENCL (1)

ENCL (1)





WATER BUDGET

AV WATER DEMAND

= 896 K GPD

POPULATION-WATER USAGE DISTRIBUTION

CAMP GETTYSBURG - 24 HR POP

PERMANENT PARTY =	2996	} 6 JETS
STUDENTS	1020	
ON BASE BILLETTS	<u>2494</u>	

$$6510 \times 50 \text{ GPCD} = 325,500 \text{ GPD}$$

$$325,500 (1440 \times 6 \text{ jets}) = 37.7 \text{ gpm/jet (1,2,3,4,5,6)}$$

$$\text{SHR (CIU)} = 300/3 = \frac{100 \times 50}{100} = 5,000 \text{ GPD}$$

$$\text{TOTAL 24 HR} = \underline{6610}$$

EXPECTED WATER CONSUMPTION = 330,000 GPD

MCAAS NEW RIVER

$$\text{MOQ} = 114 \text{ HSG UNITS} \times 4 \text{ PERS @ 50} = 22,800 \text{ GPD}$$

$$22,800 / (4 \text{ jets} \times 1440) = 4 \text{ gpm/jet (28,29,30,31)}$$

$$\text{MEQ} = 321 \text{ UNITS} \times 4 \text{ PERS @ 50} = 64,200 \text{ GPD}$$

$$64,200 / (6 \text{ jets} \times 1440) = 7.4 \text{ gpm/jet (10,11,12,13,14,15)}$$

$$\text{BEQ (4000 AREA)} = 1386 \times 50 = 69,300 \text{ GPD}$$


$$69,300 / (3 \text{ jets} \times 1440) = 16.0 \text{ gpm/jet (25,26,27)}$$

$$\text{(2ND AREA)} = 814 \text{ PERS @ 50} = 40,700 \text{ GPD}$$

$$40,700 / (1 \text{ jet} \times 1440) = 28.3 \text{ gpm/jet (17)}$$

ENCL (2)

ENCL (2)



$$\text{BEQ/BOQ (700 AREA)} = 195 \text{ pens @ 50} = 9750 \text{ gpd}$$

$$9750 / (1440 \times 1 \text{ jet}) = 6.8 \text{ gpm (16)}$$

SHR POP: MIL = 2500
 CIV = 300
 TOT = 3100 @ 50 / 3 = 51,670 GPD

$$51,670 / (1440 \times 32 \text{ jets}) = 1.1 \text{ gpm / jet}$$

258,920 GPD - MCAS
 41,080 GPD - INDUSTRIAL USE

 300,000 GPD - TOTAL MCAS
 330,000 " - TOTAL CP GEIGER

 630,000 GPD - TOTAL EXPECTED USAGE

TOTAL AU DEMAND = 886 K GPD
 " EXP. CONSUMPTION = 630 K GPD

 UNACCOUNTED FOR WATER = 266 K GPD = 5.8 gpm / jet
 1440 x 32 jets

SHR PERJ USAGE


CP GEIGER = 5000 gpd
 MCAS = 51670

 56670 gpd / (1440 x 32 jets) = 1.2 gpm / jet


ALL JETS = 7.0 gpm / jet

ENCL (1)

ENCL (2)




SKETCH - SKELETONIZED SYSTEM PIPES AND EQUIPMENT PIPES



ENCL (3)



ENCL (3)




HORIZONTAL SPLIT CASE
CENTRIFUGAL PUMPS

RATING CURVES
MCAE PUMP 514 (LARGE)

R-L-U
6L-3






ENCLOSED IMPELLER


DATED
SUPERSEDES PAGE 411
DATED JULY 1971

JULY 1976

MCA'S AIR SEPARATION (SMALL PUMPS)



1750
R.P.M.



1150
R.P.M.




AURORA PUMP
A UNIT OF GENERAL SIGNAL
800 AIRPORT ROAD · NORTH AURORA, ILLINOIS · 60542

ENCL (4)

CURVES

ENCL (4)



MCAS

TO MODIFY PUMP CURVE

PUMPS 1 + 2 (AURORA PUMPS)

$$H = \frac{10.45 \times 501}{84.87} \left(\frac{Q}{100} \right)^{1.852} = 4.14 \times 10^{-5} Q^{1.852}$$

Q	0	800	1000
H	170	240	115
ΔH	-	10	15
H _{MOD}	170	130	100

PUMP # 3 (WORTHINGTON)


$$H = \frac{10.45 \times 460.7}{84.87} \left(\frac{Q}{100} \right)^{1.852} = 3.8 \times 10^{-5} Q^{1.852}$$

Q	0	1000	1900
H	215	201	145
ΔH	-	14	45
H _{MOD}	215	187	100

ENCL (4)

ENCL (4)








MCAJ TRI PLANT PUMP CURVE MODIFICATIONS FOR MINOR LOSSES (EXISTING SYSTEM)

EQ 8" FITTINGS FOR PUMPS 1 & 2 CURVE MOD = 501' $\Delta H = 10.45 \left(\frac{Q}{100} \right)^{1.85} / 8^{4.87}$
 EQ 8" " " " 3 " " = 502'


PIPE 145 = 88' 8" EQ

	PUMPS #1 & 2 (AURORA)			PUMP #3 (WORTHINGTON)		
Q	0	500	1000	0	1000	1900
H	170	140	115	215	201	145
ΔH		10	15		15	50
H _{MOD}	170	130	100	215	189	95



ENCL (4)

ENCL (4)



MCAS -

NPSH - PUMP #3


WATER @ 100°F = 0.9 lbs/ft³ = 2.3' ATM PRESSURE = 14.7 lbs/in² = 34'

ATM HEAD AVAILABLE @ 100°F = 37.5' - 4.0' HL = 33.5'

$\Delta H_f = 10.45 \times 113.5 \left(\frac{Q}{100}\right)^{1.85} / 84.87 =$


Q	500	1000	1500	2000
ΔH_f	0.9	3.4	7.2	12.2

NOTE PUMPS 1 AND 2 NOT AS CRITICAL
NPSH REQ IS LESS THAN PUMP #3




ENCL (4)

ENCL (4)



MCA'S EXISTING SYSTEM - PIPE (46)



INTAKE = 50'-8"

DISCH = $(5/10)^{4.87} (80+13+4+15) = 38'-8" \text{ EQ}$

LINE = 88'-8" EQ

PUMP MINOR LOSSES TO MOD PUMP CURVES
PUMP #?

MINOR LOSSES

SUCTION
1-8" TR @ 45
1-8" GATE @ 4.5
48.5'

DISCH
1-6" GATE @ 3.5
1-6" CK @ 40
1-6" 90° EL @ 16
1-6" TR @ 36
6" PIPE 16
TOTAL = 111.5'


$(5/6)^{4.87} \times 111.5 + 48.5 = 501'-8" \text{ EQ}$

SUCTION
1-8" CK @ 50
1-8" GATE @ 4.5
2-90° EL'S @ 21 = 42
8" PIPE = 7
105.5'


DISCH
1-6" GATE = 3.5
2-6" 90° EL @ 16 = 32
1-6" TR = 36
6" PIPE = 16
87.5'

$(5/6)^{4.87} \times 87.5 + 105.5 = 460.7'-8" \text{ EQ}$

EWCL (S)



CAMP GEIGER




EQUIVALENT 8" PIPE SUCTION


- 1-10" FOOT VALVE @ 170 = 170
- 1-10" GATE " @ 7 = 7
- 3-10" 90° ELS @ 32 = 96
- 28.4'-10" PIPE = 28.4
- (8/10)^{4.87} x 301.4' = 42'-8" EQ

DISCH


- 1-8" CK @ 54'
- 1-8" GATE @ 4.5
- 2-8" 90° ELS @ 22 44
- 1-8" T @ 45
- 29.2'-8" PIPE 29.2
- 219'-8" EQUIV

FOR 2 PUMPS JOINTLY $(2 \times 219^{0.24})^{-1.852} = \underline{\underline{60.6'-8" EQUIV}}$





NEW 8" PVC CONNECTION TO CAMP GEIGER RESERVOIR



ORIFICE PLATE FOR RESERVOIR FILLING RATE OF 450 gpm

MAX HEAD WHEN CAMP GEIGER & MCAS PUMPS ARE ON


TDH OF MCAS PUMP @ 1000 gpm (450 gpm to RES) =	240'
H _f FOR 5120'-8" PVC = $\frac{10.45 \times 5120}{8 \times 4.87} \left(\frac{450}{140}\right)^{1.852}$ =	18.6'
	221.4'
MCAS RES FULL, =	20'
CP GEIGER RES LOU =	10'
	241.4'

ORIFICE SIZE FOR 450 gpm @ SH = 241.4'

$$\left(\frac{450}{449}\right) = 0.6 \frac{\pi}{4} \left(\frac{d}{12}\right)^2 \sqrt{64.4 \times 241.4}, \quad d = 1.7"$$

ENCL (6b)

ENCL (6b)



FLOW WHEN PUMPS ARE OFF AND HEAD AT CAMP
 GEIGER CONNECTION IS CONTROLLED BY LOW WL IN
 TOWER :

TOWER LWL = 158'
 CP GEIGER HGS HIGH = $\frac{30''}{128'}$

FOR ORIFICE = 1.7"

$$Q = 449 \times 0.6 \times \frac{\pi \left(\frac{1.7}{12}\right)^2}{4} \sqrt{64.4 \times 128} = 385 \text{ gpm}$$

OK

COMPUTER SPREAD SHEET CHECK FOR ORIFICE CAVITATION

DEVICE	FLOW CFS	TEMP % FNHT	ID IN	SIZES DL/DS	PU PSI	PD PSI	VEL FPS
ORIFIC	1.00	80.00	8.00	2.67	70.00	0.00	2.86
PVG PSI	SIGMA SYSTEM	PVGD " PSI	CD PSI	SIG ID ID	PUD PSI	PDD " PSI	
-12.50	0.18	-12.20	0.03	0.07	90.00	-5.81	
SSE SSE	X ADJ	PSE EQN	SM-LG SIGMA	LG-SM ADJU	DO/D EQN	DO IN	AD SQ IN
0.95	0.19	1.14	0.03	0.07	0.26	2.05	3.29


$\frac{Q}{1 \text{ CFS}}$	$\frac{J_{SVS}}{0.18}$	$\frac{J_{TBS}}{0.08}$	$\frac{P_{UP}}{70 \text{ psig}}$	$\frac{P_{ON}}{0 \text{ psig}}$	NOTES OK
(449 gpm)					


RESERVOIR FILLING TIME

$$\left(\frac{385 + 430}{2}\right) \times 1440 = 6 \text{ M.G. / DAY OK}$$

ENCL (6b)


ENCL (6b)





SKETCH - SKELETONIZED SYSTEM - PIPES ARE EQUIVALENT PIPES


SCALE: 1" = 71'





SCALE: 1" = 71'

ENCL (7a)

ENCL (7a)









ENCLOSED IMPELLER

DATED FEBRUARY 1977

SUPPLEMENT PAGE 419
DATED APRIL 1971




AURORA PUMP
 A UNIT OF GENERAL SIGNAL
 800 AIRPORT ROAD · NORTH AURORA, ILLINOIS · 60542


9

CURVES


ENCL (9)



MCAS TRT PLANT NEW AURORA 6X6X18A PUMPS - PLANT PIPES MODIFIED
 15 1/4" IMPELLER - 1750 RPM




ENCL (9)



FIRE RESERVE - CAMP GIGLER

REQ: 1500 GPM FOR 100 MIN = 150,000 GAL
 FOR 2 EL TWR5 = 75000 GAL / TWR
TWRS 606 + 1070



USABLE VOL = 300,000
 - 14,150
 85,850 GAL

$85,850 = \pi (14)^2 (7.5) h$
 $h = 18.6'$

$LWL = 168 - 18.6 = 149.4'$

FIRE RESERVE = $\frac{75000}{85850} \times 18.6 = 16.2'$

DISTRIBUTION STORAGE = 85,850 - 75,000

$VOL = 1.1 \times 7^2 (3 \times 14 - 7) \times 7.5 = 14,150 GAL$


USABLE STORAGE = 85,850 - 75,000 = 10,850 GAL

NOT ENOUGH, GND STORAGE IS STILL REQ.



MCAS -

REQ - 7000 GPM - 60 MIN = 420,000 GAL
 FOR 2 EL TWRs = 210,000 GAL / TWR




FIRE STORAGE " " " " " "
 $210000 = \pi(24)^2(h)(7.5)$
 $\therefore h = 15.5'$

$V = 1.1 \times 10^2 (3 \times 24 - 10) \times 7.5 = 51,150 \text{ GAL}$

	<u>TWR 3/0</u>	<u>TWR 4/30</u>
	350,000 GAL	300,000 GAL
	- 51,150	- 51,150
USABLE STORAGE =	298,850 GAL	248,850 GAL
FIRE " "	210,000	210,000
DISTRIBUTION " "	88,850 GAL	38,850 GAL
TOTAL " " " "	127,700 OK	

DISTRIBUTION height
 $88,850 = \pi(24)^2 h (7.5), h = 6.5'$
 $38,850 = \pi(24)^2 h (7.5), h = 2.8'$



WATERFLOW TEST DATA

LOCATION	MEASUREMENTS:				
	STATIC PSI	RESIDUAL PSI	FLOW GPM	AVAILABLE GPM @ 20 PSI	REQUIRED GPM @ PSI
New Exchange	70	50	965	1600	1100 @ 20
Vehicle Shop 4157	62	60	1230	6000	1250 @ 20
MOQ Area	63	12	200	180 *	500 @ 20
Warehouse 3525	60	12	150	135 *	1800 @ 40
Hangar 840	64	10	380	340	2500 @ 20
O-Club	70	20	630	630 *	1000 @ 20

* These areas depend upon the two 750 GPM @ 85 PSI booster pumps in Building 2003 to provide the required pressure and volume. Only one of the two pumps is operational and this pump is set on "manual" rather than automatic. Tests were conducted on the basis of "normal" conditions.


8. ENGINEERING RECOMMENDATIONS

a. Priority:

These recommendations involve major life safety hazards or conditions which could severely impact on the activity's ability to accomplish vital missions, and are those for which attention and resources should be directed.

ENCL (11a)

ENCL (11a)



7. WATER SUPPLY SYSTEM

a. Description: The water supply for fire protection and domestic use is furnished through a single 8-inch main from the adjoining Marine Corps Air Station New River Water Treatment Plant. The water is delivered under sufficient pressure to maintain 600,000-gallon and 272,000-gallon concrete reservoirs located at Camp Geiger. From these reservoirs two 700 GPM automatic electric pumps and one 900 GPM manual-start pump take suction and pump into the distribution system and two 100,000-gallon elevated tanks. The water supply and distribution system is adequate.


WATERFLOW TEST DATA

LOCATION	STATIC PSI	MEASUREMENTS:		AVAILABLE GPM @ 20 PSI	REQUIRED GPM @ 20 PSI
		RESIDUAL PSI	FLOW GPM		
Bldg. TC-910 "A" St. and 10th St. Hydrant #6-72-8	63	31	1500	1770	1500
Bldg. TC-1047 11th St. Hydrant #6-78-8	65	56	1180	2745	1000

NOTE: Three main breaks occurred during the water flow test, therefore no additional tests were made during this survey. The water supply is considered adequate in all of the areas of Camp Geiger, but the condition of the mains is questionable as evidenced from this experience.

ENCL (11b)

ENCL (11b)




MOQ PUMP HOUSE (AS 0003.)

FOR FIRE PROTECTION

2- FAIRBANKS MORSE FIRE PUMPS
 750 gpm @ 85 psig (TDH)

PUMP STATION



SUCTION

1- GATE = 5
 2- 90° EL @ 21 = 42
 1- TR = 45
 8" PIPE = 5
 97

DISCH

1- GATE = 5
 1- CHECK = 52
 1- TR = 45
 8" PIPE = 3
 105'

PUMP CURVE MODIFICATIONS


$$\Delta p = \frac{4.52 \times (97 + 105)}{84.87} \left(\frac{Q}{110} \right)^{1.852} = 6.05 \times 10^{-6} Q^{1.852}$$

Q	400	500	1000
Δp	0.4	1.4	3

PUMP STATION MINOR LOSSES

SUCTION

8" PIPE = 200'



DISCH

2- 90° L'S @ 21 = 42
 8" PIPE = 20
 62'

ASSUME RESERVOIR WL = 10' / 2.31 = 4.3 psig

$$\Delta p = \frac{4.52 \times (200 + 62)}{84.87} \left(\frac{Q}{110} \right)^{1.852} - 4.3 = 7.8 \times 10^{-6} Q^{1.852}$$

ENCL (12a)

ENCL (12a)


MOQ PUMP HOUSE (AS 2003)

FIRE PUMPS - 2 - FAIRBANKS MORSE - 750 GPM @ 85 LBS

THE CURVES WERE NOT AVAILABLE -
TYPICAL FIRE PUMP CURVE BELOW USED


S.O = 120% RATED HEAD

HIGH FLOW = 120% RATED DISCH @ 65% RATED HEAD



ENCL (12 b)


ENCL (12 b)



FIRE PROTECTION IMPROVEMENTS FOR CERTAIN AREAS

AS 901 AREA (NCO CLUB)

REQ 1000 GPM @ 20 PSIG



- PIPE L = 540 + 400 + 980 = 1920' - 8"

$$\Delta p = \frac{4.52 \times 1920}{84.87} \left(\frac{1000}{100} \right)^{1.85} = 24.7 \text{ LBS}$$


$$\begin{aligned} \text{RESID} &= 20 \text{ LBS} \\ 1000 \text{ GPM @ } & 44.7 \text{ LBS REQ.} \end{aligned}$$

FROM ENCL (12), 1000 GPM @ 65 LBS AVAILABLE FROM ONE EXISTING FIRE PUMP

$$\text{RESID AT NCO CLUB} = 65 - 24.7 = 40.3 \text{ PSIG} > 20 \text{ OK}$$


ENCL (13)

ENCL (13)



OFFICERS HOUSING (MOU)

REQ. 1000 GPM @ 20 psig.



EQUIV 6" (PS TO A)

$$\left(\frac{6}{8}\right)^{4.87} \times 540 + \left\{ \left[\left(\frac{6}{8}\right)^{4.87} \times 400 + 1100 \right]^{-1.54} + [1650]^{-1.54} \right\}^{-1.852} + \left(\frac{6}{8}\right)^{4.87} \times 200$$

$$= 133 + 387 + 49 = 569'$$

A TO DISCH

$$\left\{ \left[(800^{-1.54} + 1350^{-1.54})^{-1.852} + 300 \right]^{-1.54} + [1360]^{-1.54} \right\}^{-1.852} = 235'$$

804'-6" EQ

$$\Delta p = \frac{4.52 \times 804 \left(\frac{1000}{100}\right)^{1.852}}{6^{4.87}} = 42 \text{ lbs}$$

$$\text{RESID} = 20 \text{ lbs}$$


$$\text{PUMP REQ} = 1100 \text{ gpm @ } 62 \text{ lbs}$$

FROM ENCL (12), 1100 GPM @ 96 LBS IS AVAILABLE FROM 2 EXISTING FIRE PUMPS.

$$\text{RESID AVAILABLE AT END OF HSG} = 96 - 42 = 54 > 20 \text{ OK}$$


ENCL (14)

ENCL (14)



WAREHOUSE AS 3525

SPRINKLER REQ. = 1800 gpm @ 40 Lbs (XTRA HAZARD)



EQUIVALENT 8" PS AS 2003 TO WHSE AS 3525

$$\left\{ \left[\left(\frac{8}{C} \right)^{4.87} \times 1430 \right]^{-1.54} + \left[400 + \left(\frac{8}{C} \right)^{4.87} \times 1320 \right]^{-1.54} \right\}^{-1.852} + 250 + 550 + 900 + 1080 + 900 + 900 + 200 + 540$$

= 7123'-8" EQUIV

$$\Delta H = \frac{10.45 \times 7123}{8^{4.87}} \left(\frac{1800}{120} \right)^{1.852} = 448" \text{ (194 psig)}$$

CL IRON PIPE

TOO HIGH - NEED STORAGE + PUMP STATION AT WAREHOUSE LOCATION


Q REQ FOR XTRA HAZARD = 0.3 x 3000 + 750 = 1800 GPM
 FOR 105 MIN x 105
189,000 GAL

USE 0.2 MG GND RESERVOIR

SELECT PUMP TO DELIVER AT LEAST 1800 gpm @ 40 Lbs


ENCL (15)

ENCL (15)



HANGAR AS 840

REQ. 3500 GPM @ 125 lbs



SAY PRESSURE LOSS FROM NEW PUMP HOUSE TO HANGAR
= 25 psig

$$25 = \frac{4.52 \times 400}{d^{4.87}} \left(\frac{3500}{140} \right)^{1.852}$$

$$d = \left[\frac{4.52 \times 400}{25} \left(\frac{3500}{140} \right)^{1.852} \right]^{1/4.87} = 8.2''$$

USE 8" PIPE:

$$\Delta p = \frac{4.52 \times 400}{8^{4.87}} \left(\frac{3500}{140} \right)^{1.852} = 28 \text{ lbs} + 125 \text{ lbs REQ.} = 153 \text{ lbs}$$


SELECT PUMP TO DELIVER 3500 gpm @ 153 lbs TO
THE PUMP HOUSE EXIT PIPE.

ENCL (16)

ENCL (16)



TRAILER PARK (OFF SET 7 OF MODEL)



EQUIV. 6" PIPE

$$\left\{ \left[\left(\frac{6}{8} \right)^{4.87} \times 900 + 1700 \right]^{-.54} + \left[3600 \right]^{-.54} \right\}^{-1.812} + \left(\frac{6}{10} \right)^{4.87} \times 4380$$

$$710' + 364 = \underline{1074}'$$

FOR 1000 GPM PIPE FLOW TO SOUTH END OF TRC PK.

$$\Delta P = \frac{4.52 \times 1074}{6^{4.87} \left(\frac{1000}{110} \right)^{1.812}} = 47 \text{ psig}$$

RESIDUAL	=	<u>20</u>	"
TOTAL REQ	=	67	"
AVAILABLE	=	<u>54.8</u>	

SYSTEM NEEDS IMPROVEMENT.

ΔP AVAILABLE	=	54.8	lbs
RESIDUAL	=	<u>20</u>	
		34.8	lbs

$$\text{TOTAL EQUIV. 6" PIPE REQ} = \frac{34.8}{54.8} \times 1074 = 682'$$

$$\text{EQUIV 6" FOR 10' CONNECTING PIPE} = \underline{364}'$$

$$\text{EQUIV 6" TRC PARK PIPE REQ} = 318'$$

TRY 8" PVC C=130, L=3000'

$$\left\{ \left[\left(\frac{110}{130} \right)^{1.812} \times 3000 \right]^{-.54} + 710 \right\}^{-1.812} = 313' < 318' \text{ OK}$$

ENCL (17)



EM CLUB WITH PIPES CLEANED (C=120) (AS 4038)

REQ = 1000 gpm @ 20 psig

AVAILABLE OFF JCT 33 OF MONTE

$$\text{@ 1000 gpm} = 61 \text{ psi}$$

$$\text{RESID} = 20 \text{ psi}$$

$$\text{AVAILABLE FOR LOSS} = 41 \text{ psi}$$

3870'-8" [37]

AS 4038
EM CLUB

REQ = 1000 gpm @ 20 psig

$$\Delta P = \frac{4.52 \times 3870}{89.67} \left(\frac{1000}{110} \right)^{1.852} = 41 \text{ psig} \approx 41 \text{ psig AVAILABLE}$$

O.K.

IF PIPE IS CLEANED TO C=120

$$40 \times \left(\frac{110}{120} \right)^{1.852} = 36 \text{ psig} < 41 \text{ psig AVAILABLE FOR LOSS}$$

O.K.


ENCL (18)

ENCL (18)



CONTAMINATED FUEL TANKS OFF JCT 24 OF MONBL

REQ = 3000 GPM @ 20 psig



AVAILABLE @ JCT 24 @ 3000 GPM = 61 psig
RESIDUAL = 20 "
AVAILABLE FOR LOSS = 41 "

$$\Delta p = \frac{1.52 \times 2400}{84.47} \left(\frac{3000}{120} \right)^{1.852} = 170 \text{ psig REQ} > 41 \text{ psig AVAILABLE}$$

NEED RESERVOIR AND PUMP HOUSE AT TANK SITE

STORAGE REQ 3000 GPM X 200 MIN = 0.6 MG.

SUPPLY PUMPS THAT WILL DELIVER 3000 GPM @ 20 psig

ENCL (19)


ENCL (19)



MCA5 O' CLUB (AS 710) OFF JCT 16 OF MONEL

REQ = 1000 gpm @ 20 psig

AVAILABLE AT JCT 16 @ 1000 gpm = 49 psig



AVAILABLE

1000 gpm @ 49 lbs

REQ = 1000 gpm @ 20 lbs

$$\Delta P \text{ AVAILABLE} = 49 - 20 = 29 \text{ lbs}$$

$$\Delta P \text{ REQ} = \frac{4.52 \times 2620}{84.87} \left(\frac{1000}{110} \right)^{1.852} = 24 \text{ lbs} < 29 \text{ AVAILABLE}$$

OK

ENCL (20)

ENCL (20)

