DRAWING AND SPECIFICATION TRANSMITTAL LOCKWOOD GREENE ENGINEERS. INC.

SPARTANBURG. SOUTH CAROLINA 29304 P.O. BOX 491 (803)582-235

TO Naval Facilities Engineering DATE Dec. 10, 1979
Command JOB NO. 77239.16

TRANSMITTAL NO. 183 SHEET 1 OF 1

Atlantic Division Norfolk, Va. 23511


JOB NAMENaval Regional Medical Center ORDER NO.

Contract Number N-62470-77-C-7526

ATTN. Mr. John Grubbs - Code 05

	DOCUMENT NO.	REV. NO.	D	XXHEREWI	UN	DER SEPARATE COVE
1 1 1		M	Equipment Lists: Nourishment Cer IV Prepration a Ifg. Data for Abo nstall Instructi hop Drawings for	Pharmacet Med nters, Autopsy Storage Cent ove Equipment	ers	VENDOR Amp. Continenta Metal Products Co., Inc. "" ""
A - IN	OOD GREENE DOO	CUMENTS		DE FOR		VENDOR DOCUMENTS
A - IN B - RE C - AP	NFORMATION EVIEW PPROVAL EVISED DWG.(SE		E - B1 F - CC G - PU DN) H -		K - NO CORR L - MAKE CO M - REVISE	VENDOR DOCMENTS RECTIONS NOTED PRECTIONS NOTE AND RESUBMIT D(SEE REMARKS)
A - IN B - RE C - AF D - RE	NFORMATION EVIEW PPROVAL	EE REVISIO	E - B1 F - C0	ID ONSTRUCTION URCHASING	K - NO CORR L - MAKE CO M - REVISE	RECTIONS NOTED PRECTIONS NOTE AND PESUBMIT

PLEASE ACKNOWLEDGE RECEIPT BY IMMEDIATE RETURN OF SIGNED COPY OF THIS TRANSMITTAL TRANSMITTED BY Richard McKnight



DEPARTMENT OF THE NAVY
RESIDENT OFFICER IN CHARGE OF CONSTRUCTION
NAVAL REGIONAL MEDICAL CENTER
FIELD OFFICE

FIELD OFFICE CAMP LEJEUNE, NC 28542 353-3455

IN REPLY REFER TO: RDC:jj N62470-77-C-7526

APR 1 6 19911

From: Resident Officer in Charge of Construction, Naval Regional Medical Center,

Field Office, Camp Lejeune, North Carolina

To: Commander, Atlantic Division, Naval Facilities Engineering Command,

Norfolk, Virginia (Attn: Code 05)

Subj: Contract N62470-77-C-7526, 205 Bed Hospital, Naval Regional Medical Center, Camp Lejeune, North Carolina

Ref: (a) Telecon btwn J. McLaren, LANTDIV and R. Coley, ROICC NRMC

Encl: (1) Cardinal Contracting Co., Inc. 1tr dtd 4 Apr 80


1. In accordance with reference (a), enclosure (1) providing additional information on the contractor's submittal #568 is forwarded for your information and records.

R. D. COLEY By direction

Copy to:

Lockwood-Greene/Six Assoc. w/enclosure

Sub. #568 W/Enel Reading file





FIRST NATIONAL BANK BUILDING . SUITE 875 1401 MAIN ST. COLUMBIA, S.C. 29201 A/C 803-254-9064

> PLEASE ADDRESS REPLY TO: P. O. BOX 8408 CAMP LEJEUNE, N.C. 28542 April 4, 1980

Resident Officer in Charge of Construction Naval Regional Medical Center Field Office Camp Lejeune, North Carolina 28542

Attention: LCDR R. E. Carlson

205 Bed Hospital RE:

Naval Regional Medical Center Camp Lejeune, North Carolina Contract No: N62470-77-C-7526

Transmittal #568, Item M-5552, SUBJ:

Nourishment Center

Gentlemen:

We transmit copy of the March 24, 1980, letter from Continental Metal Products Company for your advice in further reviewing the above captioned transmittal.

Very truly yours,


CARDINAL CONTRACTING COMPANY, INC.

William J. Haymaker CQC Representative

WJH: mw

Attachment as noted

cc: Dallas Office Columbia Office



CONTINENTAL METAL PRODUCTS CO.INC.
35 OLYMPIA AVE., WOBURN, MASSACHUSETTS 01801
TELEPHONE (617) 935-4400

March 24, 1980

Cardinal Contracting Co., Inc.
P.O. Box 8408
Camp LeJeune, North Carolina 28542
Att: Mr. William J. Haymaker

Re: 205 Bed Hospital, Naval Regional Medical Center
Camp LeJeune, North Carolina

Dear Mr. Haymaker:

Reference is made to our previous telephone conversation concerning Section 11702, Item #M-5552, Nourishment Center.

- 1. Size of cold water supply "CMP" submittal drawings indicates 3/4" cold water supply required, where-as 1/2" has been roughed for connections to this equipment. The 1/2" supply line will adequately suffice without impairing the performance or function of this equipment. The cold water supply is domestic tap water and does not have to be pre-chilled.
- 2. Water cooled compressor vs. air cooled. The "CMP" Nourishment Station employs a water cooled compressor unit for the icemaker as it is more efficient in high humidities and less overheating and eventual service is experienced, since the compressor is cooled by water and not warm air. It also requires less maintenance as there is no dust collecting condenser to vacuum periodically. An additional water connection is not required as all interpiping is performed at the factory.


Very truly yours,

CONTINENTAL METAL PRODUCTS

Paral Maine him

Paul Malenchini Vice President

PM:g



DEPARTMENT OF THE NAVY RESIDENT OFFICER IN CHARGE OF CONSTRUCTION NAVAL REGIONAL MEDICAL CENTER FIELD OFFICE CAMP LEJEUNE, NC 28542

TELEPHONE NO. 353-3455

IN REPLY REFER TO: JR:jj N62470-77-C-7526

JAN 1 0 1980

Cardinal Contracting Co., Inc. Post Office Box 8408 Camp Lejeune, North Carolina 28542

RE: Contract N62470-77-C-7526, 205
Bed Hospital, Naval Regional
Medical Center, Camp Lejeune,
North Carolina

SUBJ: Medical Equipment, Submittals (ME-4, 5, 6, 7)

Gentlemen:

Submittal 568 through 571 have been returned from the A&E with various comments on the equipment. In addition to the comments made by the A&E, your attention is brought to the following items.

- 1. For the pantry unit, single oven (ME-5) certification of the shielding of the micro-wave oven is required. See specification Section 11702, paragraph 7.5.2 (m).
- 2. For the autopsy table (ME-6), the table height shall be 36 inches. See specification Section 11702, paragraph 7.6.1.


If you have further questions on this subject, please advise.

Sincerely,

R. D. COLEY Assistant Resident Officer in Charge of Construction

Copy to: LANTDIV (Code 05)

Gen. Corr.
Submittal ME-4, 5, 6, 7
Rem. Reading file




NAVAL REGIONAL MEDICAL CENTER

CAMP LEJEUNE, N. C. 28542

MCLO:HEP:ca 8 Nov 1979

MEMORANDUM FOR THE RESIDENT OFFICER IN CHARGE OF CONSTRUCTION, NAVAL REGIONAL MEDICAL CENTER, CAMP LEJEUNE, NORTH CAROLINA 28542

- Subj: Review of Equipment Submittals on Medical Equipment Items ME-4, ME-5, ME-6, and ME-7
- Encl: (1) Cardinal Contracting Company Submittal dtd 26 Oct 1979 on subject items
 - (2) MCLO ltr 37-HEP:va to Lockwood Greene/Six Associates dtd 23 Aug 1978
- 1. The information contained in enclosure (1) on the subject medical equipment items has been reviewed and the following comments are returned:
- a. Medical Equipment Item ME-4, <u>Medicine Service Center</u>: The Continental Metal Products unit offered meets all contract specifications and is an acceptable unit for use.
- b. Medical Equipment Item ME-5, Pantry Unit, Single Oven: The Continental Metal Products unit offered appears to meet all contract specifications. Although, Cardinal has not provided the information required on the operation of the microwave oven under Section 11702.7.5.2[d], nor have they provided the required information on oven shielding for the protection of pacemaker wearers required under Section 11702.7.5.2[m]. Submission of this information is required before the unit can be totally approved.
- c. Medical Equipment Item ME-6, Autopsy Table: The Continental Metal Products unit submitted has numerous shortcomings. The unit is only 34" high vice the 36" height required by Section 11702.7.6.1. Working height is a significant factor in physician fatigue during an extended autopsy. We would view the 36" height as a minimum height desirable in an acceptable autopsy table. The submission does not identify the number of body slats that will be provided. It is assumed that Cardinal will provide the five required by Section 11702.7.6.2[h]. The irrigation assembly on the Continental Metal Products table does not meet the requirement for a knee operated valve as called for under Section 11702.7.6.2[f]. This table also lacks the Perimeter Flushing System used in cleaning the table required by Section 11702.7.7.2[j]. This capability is required to maintain an adequate level of sanitation on an autopsy table. Finally, the submission provides no information on the $\frac{1}{2}$ horsepower waste disposal unit required by Section 11702.7.6.2[1]. Due to the numerous problems cited, it is not felt the Continental Metal Products autopsy table meets the required contract specifications and should be rejected.
- d. Medical Equipment Item ME-7, $\underline{\text{IV Additive Station}}$: The Continental Metal Products unit offered does not meet any of the contract requirements



and is totally unacceptable. The contract specification speaks to the requirement for a 4' long and 6' long laminar flow hood. By this, we mean the working surface that is covered by filtered air. Enclosure (2) is provided for your information and contains the basic requirements that were included in the specification for this piece of equipment. It also contains two possible sources of supply for the type of unit desired. Provision of the correct unit will in fact result in a significant savings to the contractor.

2. Should there be any questions with regard to the comments above, or any additional information that can be provided on the subject items, please contact me.

H. E. PHILLIPS LCDR, MSC, USN

Medical Construction Liaison Officer

