

UNITED STATES MARINE CORPS

2d Marine Division, Fleet Marine Force Camp Lejeune, North Carolina 28542-5500



Divo 5100 19 1 1 2 2 May 1985 ENED 1987

DIVISION ORDER 5100.3

From: Commanding General To: Distribution List

Subj: Light Amplification by Stimulated Emission of Radiation (LASER) Safety

Ref: (a) American National Standard for the Safe Use of Lasers
ANSI Z136.1-1980 (NOTAL)

(b) SECNAVINST 5100.14A (NOTAL)
(c) NAVMEDCOMINST 6470.2 (NOTAL)
(d) NAVELEXINST 5100.12 (NOTAL)

(e) E0410-BA-GYD-010/7034 Laser (NOTAL)

(f) MCO P3570.1A

(g) ForO 5100.8 (NOTAL)

Encl: (1) Laser Annual Inventory Report Format

(2) Laser Range Firing Log

(3) Laser Safety Inspection Checklist

(4) Laser Maintenance Safety Precautions

Report Required: I. Laser Annual Inventory Report


1. <u>Purpose</u>. To promulgate guidelines and assign responsibilities for the safe use of laser systems within the 2d Marine Division, in accordance with references (a) through (f).

2. Information

a. The term laser refers to a device emitting or amplifying visible, infrared and/or ultraviolet radiation primarily by the process of controlled stimulated emission.

- b. Exposure to laser beams above the maximum permissible exposure limits can result in serious radiation burns, particularly to the eyes. While maximum permissible exposure (MPE) levels have been established by reference (a), unnecessary exposure to laser radiation is to be avoided.
- 3. Action. All 2d Marine Division personnel and all Reserve units, units of other U. S. Armed Forces, and foreign National units, when hosted by the 2d Marine Division will comply with the safety instructions and provisions of this Order.


H. M. NELSON Chief of Staff



CONTENTS

~	U	h	P	m	-	D
·	п	г.		_	Ľ	\mathbf{r}


1	LASER SAFETY ORGANIZATION
2	LASER SAFETY REGULATIONS
3	ACTIVITY AUDIT OF LASERS
4	LASER SAFETY TRAINING PROGRAM
5	LASER PROTECTIVE GOGGLES
6	MEDICAL SURVEILLANCE PROGRAM
7	ACCIDENT INVESTIGATION/REPORTING PROCEDURES
8	RECORDS



CHAPTER 1

LASER SAFETY ORGANIZATION

		PARAGRAPH	PAGE
LASER	SYSTEM SAFETY OFFICER	1001	1-3
RANGE	LASER SAFETY OFFICER	1002	1-3
LASER	SAFETY COMMITTEE	1003	1-3



CHAPTER 1

LASER SAFETY ORGANIZATION


- 1001. LASER SYSTEM SAFETY OFFICER (LSSO). All regiments and separate battalions utilizing lasers shall establish a laser hazard control program which shall include at a minimum:
- 1. A Laser System Safety Officer. An individual shall be designated by name as the laser systems safety officer with direct access to the commanding officer and sufficient technical competence and authority to approve or disapprove the local use of lasers. He shall:
- a. Maintain a list of all lasers and their location at his activity. Submit an annual list (enclosure 1) of all class IIIb, class IV and military exempt lasers to the Division Safety Office by 15 October each year.
- b. Maintain records as prescribed in paragraph 8001, on all personnel exposed to lasers. These records are to be submitted to the medical officer for medical surveillance.
- c. Investigate laser radiation accidents and initiate appropriate corrective actions.
- d. Establish and promulgate laser safety regulations. This includes standard operating procedures for safety for laser operations.
- 1002. RANGE LASER SAFETY OFFICER (RLSO). These responsibilities shall include operational procedures; a log of all laser range firings (enclosure 2), and assisting the LSSO in meeting laser hazard control. A copy of enclosure (2) must be delivered to the Range Control Officer upon completion of lasing. The operational procedures shall include:
- a. Becoming familiar with MCO P3570.1A Chapter 19 and the FM and TM applicable to the particular laser devices to be used.
- b. Briefing unit personnel who work with laser devices, including an explanation of laser-related hazards and safety devices.
- c. Knowing the azimuths and elevations of each range, firing positions, and targets to be used.
 - d. Insuring protective eyewear is used when required.
- e. Insuring compliance with the unit SOP for laser operations and training.

- f. Maintaining continuous communication with personnel in the target area and stop lasing immediately if communication is lost.
- g. Stop lasing promptly if positive control of the beam is lost.
- 1003. <u>LASER SAFETY COMMITTEE</u>. Comprised of Regimental and separate Battalion LSSO's to assist the Division LSSO in maintaining an up to date laser hazard control program.

CHAPTER 2

LASER SAFETY REGULATIONS

		PARAGRAPH	PAGE
POLICY		2001	2-3
SOP FOR MAINTENANCE F	PACILITIES	2002	2-3
SOP FOR RANGES		2003	2-3



CHAPTER 2

LASER SAFETY REGULATIONS

2001. POLICY. Control measures will be outlined for the firing of a laser on a given installation or range. Some of the control measures will be specific for a given installation or range, however, there are some general guidelines that can be adapted to every installation and laser system.

2002. STANDARD OPERATING PROCEDURES FOR MAINTENANCE FACILITIES

- 1. Most of the eye injuries from laser radiation have occurred in the laboratory. These have usually involved experienced laser specialists who had failed to wear protective eye wear. Control measures for the maintenance facility should be designed to protect not only the laser user, but the noncontrolled personnel having access to the area.
- 2. Control measures could be mechanical, administrative, or a combination of the two. The control measures initiated should be prescribed for the highest class laser in operation.

2003. STANDARD OPERATING PROCEDURES FOR RANGES


- 1. Range control procedures for laser operations. The controls to prevent exposure to hazardous levels of laser radiation are: beamstops, controlled access, restricted airspace, and a buffer zone around the target area.
- 2. Prior to laser operations on a given range, remove all specular reflectors such as glass, plexiglass, highly polished flat surfaces, chrome bumpers, mirrors, windshields and the head and tail lamps. If a tank is to be used as a target, the flat glass surfaces in the tank viewblocks and optics should be removed. Target areas should be inspected to determine if any large pieces of broken glass are present. Areas that could have ponds or standing water after precipitation should be avoided as a target area if possible. Snow does not usually present a problem unless melting and then freezing occurs, or if the melting creates a pool of water. Inspection of the target area is recommended after any precipitation to insure that standing water is not present.
- 3. If specular reflectors cannot be removed from the target area, the restricted airspace shall be evaluated to insure that noncontrolled aircraft do not enter the zone of hazardous radiation. All mountains, hills, observation towers, etc. within the nominal occular hazard distance (NOHD) where optically aided viewing of the laser location may occur should be identified and evaluated to insure that no occupied areas could be within a reflected beam path.

- 4. The following general rules apply to all laser range operations:
- a. The range boundary must be posted to advise personnel of laser operations.
- b. The laser beam and its associated buffer zone must be contained within controlled areas.
- c. Any personnel within the target area must wear appropriate laser eye protection when laser firing is in progress.
 - d. Officer-in-charge of firing must be RLSO qualified.
- e. Laser operations must be scheduled and approved by range control prior to any lasing.
- f. Laser operations must be conducted in accordance with the installation range SOP/Regs.
- g. Laser operations must be conducted in accordance with references (a), (b), and (f).

CHAPTER 3

ACTIVITY AUDIT OF LASERS

	PARAGRAPH	PAGE
LASER EQUIPMENT INVENTORY	3001	3-3
USER IDENTIFICATION	3002	3-3
LASER INSTALLATION SAFETY SURVEY	3003	3-3




CHAPTER 3

ACTIVITY AUDIT OF LASERS

3001. LASER EQUIPMENT INVENTORY


- 1. A laser audit must be completed to establish a laser equipment inventory, identify personnel who require medical surveillance, and provide safety survey inspections of laser installation. This audit will be conducted by the Regimental or separate Battalion LSSO annually, using the sample inspection checklist contained in enclosure (3) of this Order, and other applicable directives.
- 2. A laser equipment inventory and classification of laser hazards is required for hazard control. The inventory records should identify the type of laser, operating characteristics, hazards classification, application, frequency of operation, physical location, and the individual(s) responsible for disposition (if applicable), as contained in reference (b), and other applicable directives.
- 3002. USER IDENTIFICATION. During the laser audit, all personnel who operate or are exposed to laser radiation should be identified. Risk category may be established identifying (low, moderate, or high) risk exposure situations, as explained in Chapter 4. Personnel exposure records must be kept regarding the equipment used, job assignments, laser education, training, time on the job, and laser related medical history. All records shall be maintained for a period of five (5) years with the exception of the medical records which shall be maintained at the regional Medical Center for a period of fifty (50) years as per reference (c).
- 3003. LASER INSTALLATION SAFETY SURVEY. Each individual laser installation must be thoroughly inspected at least once a calendar year to ensure that it meets and continues to meet safety requirements. Inspections must include, but is not limited to, a review of the standing operating procedures, operator training, equipment condition, and the condition and use of protective eye wear and all other protective equipment. In addition the installation must be inspected to assure that the required warning systems and signs are posted in all appropriate locations for the protection of all personnel from the laser radiation. Safety survey inspections are done by the Naval Surface Weapons Center in Dahlgren, Virginia, and are requested by Marine Corps Base.



CHAPTER 4

LASER SAFETY TRAINING

															P	ARAGRAPH	PAGE	
CLASS	I LAS	ERS.	•				•									4001	4-3	
CLASS	II LAS	SERS	and the	•			•	•	•		•		•	•		4002	4-3	
CLASS	IIIA 1	LASER	s.			•			•		•	•		•		4003	4-3	
CLASS	IIIB A	AND C	LASS	3 1	v	L	ASE	ERS			•			•	•	4004	4-3	
MILITA	ARY EXE	EMPT	LASE	ERS	3.		•		•				•			4005	4-4	



CHAPTER 4

LASER SAFETY TRAINING


- 4001. CLASS I LASERS. Class I lasers are nonhazard devices which may be viewed directly or indirectly without any protective devices over extended periods of time.
- 4002. CLASS II LASERS. Class II lasers are low-risk laser devices which are hazardous only if viewed continuously without protective devices. Class I and II lasers require no special training.
- 4003. CLASS IIIA LASERS. Class IIIA lasers are moderate risk laser devices which require protective equipment for personnel and specific mechanical safety devices to ensure personnel safety during laser operations. Simple review of the lasers characteristics and hazards is sufficient training.
- 4004. CLASS IIIB AND IV LASERS. Class IIIB and IV lasers are high risk laser devices which require protective equipment for personnel and extensive mechanical safety devices to ensure personnel and physical safety during laser operations. These lasers require the following formal classroom training:
- a. Type of eye protection to be worn (when and where, appropriate optical density for appropriate wavelength and proper periodic inspection).
- b. Potential hazards in the target area, maintenance area, etc., types of warning signs to be posted and specific procedures to avoid these hazards.
- c. Thorough briefing on all range procedures with specific emphasis to ensure that:
- (1) Two way communications with all involved ships, aircraft, personnel, etc. are established before laser operations commence.
- (2) Acquisition, identification and tracking of the specifically assigned target are established prior to laser activation.
- (3) No lasing occurs until cleared by the range control officer.
- (4) Lasing shall cease immediately whenever the laser is not pointed in the immediate vicinity of assigned targets or the Range Officer terminating the run.

- (5) Personnel know where to post signs, range barriers, or range guards and for what purpose.
- (6) The importance of interlocks for maintenance buildings.
 - (7) Biological effects if any.
 - (8) Specular reflections (mirror like reflections).
- (9) Diffuse reflections (refers to objects which can scatter the beam's reflection such as rocks, trees, etc.)
 - (10) The medical surveillance requirements.
- 4006. MILITARY EXEMPT LASERS. These are all lasers which due to their military application and/or security classification are not specifically identified as to class, function of purpose and which may be exempt from the requirements contained in reference (a) and other applicable regulatory publications. However, safety requirements for use and operation do apply.

CHAPTER 5

LASER PROTECTIVE GOGGLES


	PARAGRAPH	PAGE
GENERAL	5001	5-3
INSPECTION AND MAINTENANCE	5002	5-3



CHAPTER 5

LASER PROTECTIVE GOGGLES


- 5001. GENERAL. When lasers are put into operation, the using command must ensure that all exposed personnel, both in work areas and down range, are adequately protected from laser radiation. Goggles must be permanently labeled for their optical density. There should be sufficient goggles with the proper optical density at the appropriate wavelengths to issue to all personnel who require one and to handle any visitors required to be in the laser hazard area.
- 5002. PERIODIC INSPECTION AND MAINTENANCE. Periodic inspections shall be made by using commands of protective eyeware to ensure the maintenance of satisfactory conditions. This shall include:
- a. Inspection of the attenuator material for pitting, cracking and discoloration.
 - b. Inspection of the frame for mechanical integrity.
- c. Inspection for light leaks that would permit hazardous intrabeam viewing. Eyeware in suspicious condition should not be used until tested for acceptability.



CHAPTER 6

MEDICAL SURVEILLANCE PROGRAM


	PARAGRAPH	PAGE
MEDICAL SURVEILLANCE PROGRAM	. 6001	6-3
MEDICAL SAFETY	. 6002	6-3
MEDICAL EXAMINATIONS	. 6003	6-3
REFERENCE	. 6004	6-3



CHAPTER 6

SURVEILLANCE PROGRAM


- 6001. MEDICAL SURVEILLANCE PROGRAM. A medical surveillance program is required for class IIIB and class IV laser systems. All personnel designated as incidental laser personnel should have a documented visual acuity screening examination prior to assignment to laser systems operations. Laser personnel should have examinations as required by paragraph 6003.
- 6002. MEDICAL SAFETY. Personnel designated as incidental or laser personnel by their Regimental or separate Battalion LSSO's, shall be required to wear the proper eye protection when engaged in force-on-force tactical exercises. Additionally, any incidental personnel involved in work downrange, i.e., moving targets, shall wear approved eye protection.
- 6003. MEDICAL EXAMINATIONS. Prior to designation or commencement of tasks directly related to laser operations or maintenance; or if any individual is exposed to laser radiation and an eye injury is suspected or observed, a complete medical examination shall be performed as soon as possible. The examination shall consist of:
- a. A medical history with emphasis on occular systems and history of medication usage (particularly potentially photosensitizing drugs).
 - b. Visual acuity determinations.
 - c. Examinations of various structures of the eye.
- d. Polaroid color photographs of the posterior pole of the funds including the area of the macula and optic nerve.
- e. Any other protocol recommended by the cognizant medical officer or by consultation with the Commander, Naval Medical Command (MEDCOM-21).
- 6004. REFERENCE. The medical surveillance program is in accordance with reference (c).



CHAPTER 7

ACCIDENT INVESTIGATION/REPORTING PROCEDURES


								PARAGRAPH	PAGE
ACCIDENT INVESTIGATION.	•	•	•			.•		7001	7-3
REPORTING PROCEDURES								7002	7-3



CHAPTER 7

ACCIDENT INVESTIGATION/REPORTING PROCEDURES


- 7001. ACCIDENT INVESTIGATION. When an individual is exposed to laser radiation and an injury is suspected or observed, a complete medical examination shall be performed as soon as possible. Examination procedures are covered in Chapter 6. The Commanding Officer will direct the Regimental or separate Battalion LSSO's to conduct an accident investigation. This investigation will be forwarded to the appropriate installation commander (Attn: Range Control) in accordance with the requirements of reference (f).
- 7002. REPORTING. A letter report shall be submitted to the Commander, NAVMEDCOM (MEDCOM-21) via the Commanding General, 2d Marine Division (ATTN: Surgeon) within fifteen (15) days of the incident. As a minimum, the report shall contain a list of personnel exposed, an estimate of the exposure received, a copy of medical examinations performed, and a narrative summary of events leading to the incident.



CHAPTER 8

RECORDS


					i.					PARAGRAPH	PAGE
RECORDS.										8001	8-3



CHAPTER 8


RECORDS

- 8001. RECORDS. At a minimum, the exposure records shall contain a list of exposed personnel, an estimate of the exposure received, and a description of the physiological symptoms. This report should also include as an enclosure, a description and examination of the situation and the corrective measures/recommendations necessary to prevent future occurrences. Records will include, but need not be limited to:
- a. A log to record all operational, maintenance or training laser firings to include date, time, location, target, laser range officer, operator, purpose and personnel present. If the laser is fired airborne, include type aircraft, Bureau Number (BUNO), location/heading, altitude, and designated target. Additional documentation may also be included, as deemed appropriate.
- b. An inventory record of all command held laser devices along with a Description and Analysis Report will be maintained, as required by references (b) and (d).
- c. A current listing of all units and personnel who are authorized to engage in laser operations and their specific function/limitations. Such a list should be readily accessible to the LSSO, and range control and periodically updated when changes occur.
- d. Training records of all personnel who engage in laser operations, maintenance or training, to include times and dates of training received, as well as copies of designations and assignments for laser operations.




LASER ANNUAL INVENTORY REPORT FORMAT

Fro	m:	
To:		Commanding General, 2d Marine Division, FMF (Attn: Div Safety)
Sub	j:	Exempt LASER Inventory Report for FY
Ref	:	(a) NAVELEXINST 5100.12
1. is	In subr	accordance with the reference, the following annual report
	a.	LASER Type
	b.	Manufacturer
	c.	Part Number (if available)
	d.	Contact Number (if available)
	e.	Number of LASERS
	f.	National Stock Number (if available)
	g.	Exempt Qualification (check applicable boxes)
		Combat Training
		Classified
2.	STA	TUS
	a.	Number of LASERS:
		In use In storage Awaiting Disposition
		Transferred within DOD to Date ASD approval date (Provide Serial Numbers)
		Disposed outside of DOD to Date ASD approval date (Provide Serial Numbers)



LASER RANGE FIRING LOG

COMMAND	DATE	RANGE_	Andrew St.
LASER SYSTEM	LASER	SERIAL NUMBER	
LEFT LIMIT (AZIMUTHS)	RIGHT (AZIMU	LIMITTHS)	
MAX. RANGE AUTHORIZED_	MI	N. RANGE AUTHORIZED_	Top to a
TIME CLEARED FOR USE	TI	ME SECURED FROM USE_	
LASER SAFETY OFFICER	RANK	UNIT	
OPERATOR #1 NAME	RANK	TIME USED FROM_	TO
OPERATOR #2 NAME	RANK	TIME USED FROM	TO
OPERATOR #3 NAME	RANK	TIME USED FROM_	то
OPERATOR #4 NAME	RANK	TIME USED FROM	_то
WAS A FILTER REQUIRED WHICH FILTER WAS USED	YES NO		



LASER SAFETY INSPECTION CHECKLIST

	the state of the s	YES/NO
	Does the command have Class III or IV LASERS or military exempt LASERS?	
REFERENCE	If yes, continue with the following:	
NAVELEXINST 5100.12 Encl (4)	Has a LASER hazard control program been established?	
NAVELEXINST 5100.12 Encl (4)	Has a LASER Systems Safety Officer (LSSO) been designated in writing and does he have direct access to the CO?	
NAVELEXINST 5100.12 Encl (4)	Does the LSSO have sufficient technical competence and authority to approve or disapprove the local use of LASERS?	/_
NAVELEXINST 5100.12 Encl (5)	Has the LSSO received a minimum of 20 hours of formal classroom training in LASER radiation? (LASER Safety School or equivalent)	
NAVELEXINST 5100.12 Encl (4)	Has a local LASER Safety Organization or Committee been established to assist the LSSO in discharging his responsibilities? (If warranted by the magnitude of the Potential hazard in local operations)	
NAVELEXINST 5100.12 Encl (4)	Has each local LASER user been approved or submitted for safety approval to higher authority by the LSSO?	_/
NAVELEXINST 5100.12 Encl (4)	Does the LSSO maintain a list of all LASERS and their locations?	_/_
NAVELEXINST 5100.12 Encl (4)	Is a list of Class IIIB and IV LASERS and Military Exempt LASERS submitted annually to NAVELEXSYSCOM? (Due 15 October)	,

DivO 5100.3 22 May 1985

NAVELEXINST 5100.12 Encl (4)	Have local LASER safety regulations been established including standing operating procedures for indoor maintenance and outdoor operational LASER operations?	_/_
NAVELEXINST 5100.12 Encl (4)	Have safety responsibilities been written for LASER or LASER System Operations which include normal operational procedures, emergency procedures and documentation of all LASER firing?	
NAVELEXINST 5100.12 Encl (4)	Are all local LASER Ranges surveyed at least annually for safety?	/
NAVELEXINST 5100.12 Encl (4)	Are warning systems and signs placed in appropriate locations to protect all personnel from LASER radiation?	
NAVELEXINST 5100.12 Encl (5)2.e	Has a LASER protective goggles program been established? Are they properly labeled and periodically inspected and evaluated?	
NAVELEXINST 5100.12 Encl (5)	Have all personnel in areas with LASERS been informed by formal classroom training about the potential hazards associated with accidental exposure to LASERS?	
NAVELEXINST 5100.12 Encl (4)	Are local LASER radiation accidents and incidents investigated with appropriate recommendations and corrective actions initiated?	_/_
NAVMEDCOM INST 6470. 2.5 d&e	Is medical evaluation performed and an incident report submitted via the chain of command to COMNAVMEDCOM (MEDCOM 21) within 30 days of the incident with a copy to NAVELEXSYSCOM (ELEX 7034)?	
	Medical Surveillance	
NAVMEDCOM INST 6470. 2.5.b	Has the LSSO determined and designated incidental and LASER personnel? NOTE: Incidental personnel - Those	

whose work make it possible but unlikely for them to be exposed to LASER energy sufficient to damage eyes or skin. (e.g., range personnel)


	(e.g., range personner)	
	operate laser devices.	_/_
NAVELEXINST 5100.12 Encl (4)	Has the LSSO submitted records of personnel exposed to LASER emissions to the medical officer for medical surveillance?	
NAVMEDCOM INST 6470. 2.5.b	Are all personnel designated either as Incidental or LASER Personnel enrolled in the appropriate medical surveillance program?	
NAVMEDCOM INST 6470. 2.5.b	Are the required examinations performed prior to participation in and upon termination of LASER work and following any suspected LASER injury?	
NAVMEDCOM INST 6470. 2 Encl (2)	Have incidental personnel received eye examinations for visual acuity?	_/_
NAVMEDCOM INST 6470. 2 Encl (2)	Do LASER personnel receive visual acuity determinations and eye examinations based on the wave length of LASER radiation? Is a medical history taken?	
NAVMEDCOM INST 6470. 2.5.b	Are there any military exempt LASERS? (Those designed for combat, combat training or classified)	_/_
	If yes	
SECNAVINST 5100.14A 7.c(1)	Have all military exempt LASERS in use been reviewed and approved safe by the NAVY LASER Safety Review Board? (Contact NAVELEXSYSCOM (ELEX 7034)).	_/
SECNAVINST 5100.14A 7.b(2)	Is the required caution label affixed to all military exempt LASERS?	_/
SECNAVINST 5100.14A 7.c(3)	Is an inventory and record of the status of all exempted LASER products maintained?	

DivO 5100.3 22 May 1985 Is a report on military exempt LASERS SECNAVINST provided to NAVELEXSYSCOM by 15 5100.14A 7.c October of each year? Is approval received from the Deputy SECNAVINST 5100.14A Assistant Secretary of Defense for 7.c(5) Equal Opportunity and Safety Policy, via COMNAVELEXSYSCOM, prior to the transfer or disposal of any military

exempt LASER?

LASER MAINTENANCE SAFETY PRECAUTIONS

- 1. LASER hazard warning signs shall be posted on all entrances to LASER maintenance areas in accordance with reference (b), so as to minimize the risk of accidental exposure. The LASER units and test benches shall be marked with warning signs as well.
- 2. All personnel engaged in essential duties concerned with LASER firing shall wear approved, eye protection during firing. Non-essential personnel shall leave the LASER area during firing.
- 3. All functional entrances to bench and boresight LASER firing areas shall be interlocked so that opening such a door will stop LASER emission.
- 4. Equipment interlocks shall be maintained in operating condition at all times. In the event required and approved maintenance procedures can only be performed by circumventing some interlock feature, that procedure will be performed only under the supervision of a designated LASER Safety Supervisor, with prior approval of a qualified LASER Systems Safety Officer or qualified Maintenance Officer. In all such cases, a documented quality assurance inspection shall be performed at the completion of that work to ensure that proper interlock operation has been restored.
- 5. Appropriate and adequate LASER safety radiation containment procedures and devices shall be in effect whenever any LASER is fired. Examples of containment devices are lens covers, diffusers, shields, and enclosures.
- 6. The LASER test area shall be kept clear of all specular reflectors or diffuse surfaces with a high coefficient of reflection.
- 7. During LASER operations, the minimum amount of personnel (normally two) shall be present.
- 8. Where practical, a countdown procedure shall be followed prior to LASER firings.







UNITED STATES MARINE CORPS

2d Marine Division, Fleet Marine Force Camp Lejeune, North Carolina 28542-5500

> DivO 5100.3 32:ASF:mem 22 May 1985

DIVISION ORDER 5100.3

From: Commanding General To: Distribution List

Subj: Light Amplification by Stimulated Emission of Radiation

(LASER) Safety

Ref: (a) American National Standard for the Safe Use of Lasers ANSI Z136.1-1980 (NOTAL)

(b) SECNAVINST 5100.14A (NOTAL)
(c) NAVMEDCOMINST 6470.2 (NOTAL)
(d) NAVELEXINST 5100.12 (NOTAL)

(e) EO410-BA-GYD-010/7034 Laser (NOTAL)

(f) MCO P3570.1A

(g) ForO 5100.8 (NOTAL)

Encl: (1) Laser Annual Inventory Report Format

(2) Laser Range Firing Log

(3) Laser Safety Inspection Checklist

(4) Laser Maintenance Safety Precautions

Report Required: I. Laser Annual Inventory Report


1. <u>Purpose</u>. To promulgate guidelines and assign responsibilities for the safe use of laser systems within the 2d Marine Division, in accordance with references (a) through (f).

2. Information

- a. The term laser refers to a device emitting or amplifying visible, infrared and/or ultraviolet radiation primarily by the process of controlled stimulated emission.
- b. Exposure to laser beams above the maximum permissible exposure limits can result in serious radiation burns, particularly to the eyes. While maximum permissible exposure (MPE) levels have been established by reference (a), unnecessary exposure to laser radiation is to be avoided.
- 3. Action. All 2d Marine Division personnel and all Reserve units, units of other U. S. Armed Forces, and foreign National units, when hosted by the 2d Marine Division will comply with the safety instructions and provisions of this Order.

H. M. NELSON Chief of Staff


DISTRIBUTION: A



CONTENTS

CHAPTER


1	LASER SAFETY ORGANIZATION
2	LASER SAFETY REGULATIONS
3	ACTIVITY AUDIT OF LASERS
4	LASER SAFETY TRAINING PROGRAM
5	LASER PROTECTIVE GOGGLES
6	MEDICAL SURVEILLANCE PROGRAM
7	ACCIDENT INVESTIGATION/REPORTING PROCEDURES
8	RECORDS



CHAPTER 1

LASER SAFETY ORGANIZATION


						PARAGRAPH	PAGE
LASER	SYSTEM SAFETY OFFICER.	•				1001	1-3
RANGE	LASER SAFETY OFFICER .		٠			1002	1-3
LASER	SAFETY COMMITTEE				•	1003	1-3



CHAPTER 1

LASER SAFETY ORGANIZATION


- 1001. LASER SYSTEM SAFETY OFFICER (LSSO). All regiments and separate battalions utilizing lasers shall establish a laser hazard control program which shall include at a minimum:
- 1. A Laser System Safety Officer. An individual shall be designated by name as the laser systems safety officer with direct access to the commanding officer and sufficient technical competence and authority to approve or disapprove the local use of lasers. He shall:
- a. Maintain a list of all lasers and their location at his activity. Submit an annual list (enclosure 1) of all class IIIb, class IV and military exempt lasers to the Division Safety Office by 15 October each year.
- b. Maintain records as prescribed in paragraph 8001, on all personnel exposed to lasers. These records are to be submitted to the medical officer for medical surveillance.
- c. Investigate laser radiation accidents and initiate appropriate corrective actions.
- d. Establish and promulgate laser safety regulations. This includes standard operating procedures for safety for laser operations.
- 1002. RANGE LASER SAFETY OFFICER (RLSO). These responsibilities shall include operational procedures; a log of all laser range firings (enclosure 2), and assisting the LSSO in meeting laser hazard control. A copy of enclosure (2) must be delivered to the Range Control Officer upon completion of lasing. The operational procedures shall include:
- a. Becoming familiar with MCO P3570.1A Chapter 19 and the FM and TM applicable to the particular laser devices to be used.
- b. Briefing unit personnel who work with laser devices, including an explanation of laser-related hazards and safety devices.
- c. Knowing the azimuths and elevations of each range, firing positions, and targets to be used.
 - d. Insuring protective eyewear is used when required.
- e. Insuring compliance with the unit SOP for laser operations and training.



CHAPTER 2

LASER SAFETY REGULATIONS

					PARAGRAPH	PAGE
POL	ICY.				 2001	2-3
SOP	FOR	MAINTENANCE	FACILITIES		 2002	2-3
SOP	FOR	RANGES		e de la	 2003	2-3



CHAPTER 2

LASER SAFETY REGULATIONS


2001. POLICY. Control measures will be outlined for the firing of a laser on a given installation or range. Some of the control measures will be specific for a given installation or range, however, there are some general guidelines that can be adapted to every installation and laser system.

2002. STANDARD OPERATING PROCEDURES FOR MAINTENANCE FACILITIES

- 1. Most of the eye injuries from laser radiation have occurred in the laboratory. These have usually involved experienced laser specialists who had failed to wear protective eye wear. Control measures for the maintenance facility should be designed to protect not only the laser user, but the noncontrolled personnel having access to the area.
- 2. Control measures could be mechanical, administrative, or a combination of the two. The control measures initiated should be prescribed for the highest class laser in operation.

2003. STANDARD OPERATING PROCEDURES FOR RANGES


- 1. Range control procedures for laser operations. The controls to prevent exposure to hazardous levels of laser radiation are: beamstops, controlled access, restricted airspace, and a buffer zone around the target area.
- 2. Prior to laser operations on a given range, remove all specular reflectors such as glass, plexiglass, highly polished flat surfaces, chrome bumpers, mirrors, windshields and the head and tail lamps. If a tank is to be used as a target, the flat glass surfaces in the tank viewblocks and optics should be removed. Target areas should be inspected to determine if any large pieces of broken glass are present. Areas that could have ponds or standing water after precipitation should be avoided as a target area if possible. Snow does not usually present a problem unless melting and then freezing occurs, or if the melting creates a pool of water. Inspection of the target area is recommended after any precipitation to insure that standing water is not present.
- 3. If specular reflectors cannot be removed from the target area, the restricted airspace shall be evaluated to insure that noncontrolled aircraft do not enter the zone of hazardous radiation. All mountains, hills, observation towers, etc. within the nominal occular hazard distance (NOHD) where optically aided viewing of the laser location may occur should be identified and evaluated to insure that no occupied areas could be within a reflected beam path.



CHAPTER 3

ACTIVITY AUDIT OF LASERS

	PARAGRAPH	PAGE
LASER EQUIPMENT INVENTORY	. 3001	3-3
USER IDENTIFICATION	. 3002	3-3
LASER INSTALLATION SAFETY SURVEY	. 3003	3-3




CHAPTER 3

ACTIVITY AUDIT OF LASERS

3001. LASER EQUIPMENT INVENTORY


- 1. A laser audit must be completed to establish a laser equipment inventory, identify personnel who require medical surveillance, and provide safety survey inspections of laser installation. This audit will be conducted by the Regimental or separate Battalion LSSO annually, using the sample inspection checklist contained in enclosure (3) of this Order, and other applicable directives.
- 2. A laser equipment inventory and classification of laser hazards is required for hazard control. The inventory records should identify the type of laser, operating characteristics, hazards classification, application, frequency of operation, physical location, and the individual(s) responsible for disposition (if applicable), as contained in reference (b), and other applicable directives.
- 3002. USER IDENTIFICATION. During the laser audit, all personnel who operate or are exposed to laser radiation should be identified. Risk category may be established identifying (low, moderate, or high) risk exposure situations, as explained in Chapter 4. Personnel exposure records must be kept regarding the equipment used, job assignments, laser education, training, time on the job, and laser related medical history. All records shall be maintained for a period of five (5) years with the exception of the medical records which shall be maintained at the regional Medical Center for a period of fifty (50) years as per reference (c).
- installation must be thoroughly inspected at least once a calendar year to ensure that it meets and continues to meet safety requirements. Inspections must include, but is not limited to, a review of the standing operating procedures, operator training, equipment condition, and the condition and use of protective eye wear and all other protective equipment. In addition the installation must be inspected to assure that the required warning systems and signs are posted in all appropriate locations for the protection of all personnel from the laser radiation. Safety survey inspections are done by the Naval Surface Weapons Center in Dahlgren, Virginia, and are requested by Marine Corps Base.



CHAPTER 4

LASER SAFETY TRAINING


												P	ARAGRAPH	PAGE
CLASS	I LASERS												4001	4-3
CLASS	II LASERS .			•	•								4002	4-3
CLASS	IIIA LASERS												4003	4-3
CLASS	IIIB AND CL	AS	5 :	IV	L	ASI	ERS	3.			•		4004	4-3
MILITA	ARY EXEMPT L	ASI	ERS	5.									4005	4-4



CHAPTER 4

LASER SAFETY TRAINING


- 4001. CLASS I LASERS. Class I lasers are nonhazard devices which may be viewed directly or indirectly without any protective devices over extended periods of time.
- 4002. <u>CLASS II LASERS</u>. Class II lasers are low-risk laser devices which are hazardous only if viewed continuously without protective devices. Class I and II lasers require no special training.
- 4003. CLASS IIIA LASERS. Class IIIA lasers are moderate risk laser devices which require protective equipment for personnel and specific mechanical safety devices to ensure personnel safety during laser operations. Simple review of the lasers characteristics and hazards is sufficient training.
- 4004. CLASS IIIB AND IV LASERS. Class IIIB and IV lasers are high risk laser devices which require protective equipment for personnel and extensive mechanical safety devices to ensure personnel and physical safety during laser operations. These lasers require the following formal classroom training:
- a. Type of eye protection to be worn (when and where, appropriate optical density for appropriate wavelength and proper periodic inspection).
- b. Potential hazards in the target area, maintenance area, etc., types of warning signs to be posted and specific procedures to avoid these hazards.
- c. Thorough briefing on all range procedures with specific emphasis to ensure that:
- (1) Two way communications with all involved ships, aircraft, personnel, etc. are established before laser operations commence.
- (2) Acquisition, identification and tracking of the specifically assigned target are established prior to laser activation.
- (3) No lasing occurs until cleared by the range control officer.
- (4) Lasing shall cease immediately whenever the laser is not pointed in the immediate vicinity of assigned targets or the Range Officer terminating the run.



CHAPTER 5

LASER PROTECTIVE GOGGLES


	PARAGRAPH	PAGE
GENERAL	5001	5-3
INSPECTION AND MAINTENANCE	. 5002	5-3



CHAPTER 5

LASER PROTECTIVE GOGGLES


- 5001. GENERAL. When lasers are put into operation, the using command must ensure that all exposed personnel, both in work areas and down range, are adequately protected from laser radiation. Goggles must be permanently labeled for their optical density. There should be sufficient goggles with the proper optical density at the appropriate wavelengths to issue to all personnel who require one and to handle any visitors required to be in the laser hazard area.
- 5002. <u>PERIODIC INSPECTION AND MAINTENANCE</u>. Periodic inspections shall be made by using commands of protective eyeware to ensure the maintenance of satisfactory conditions. This shall include:
- a. Inspection of the attenuator material for pitting, cracking and discoloration.
 - b. Inspection of the frame for mechanical integrity.
- c. Inspection for light leaks that would permit hazardous intrabeam viewing. Eyeware in suspicious condition should not be used until tested for acceptability.



CHAPTER 6

MEDICAL SURVEILLANCE PROGRAM


									P	ARAGRAPH	PAGE
MEDICAL :	SURVEILLANCE	PR	OGRA	M.			•			6001	6-3
MEDICAL :	SAFETY				•	•				6002	6-3
MEDICAL 1	EXAMINATIONS						•		X.	6003	6-3
REFERENCI	E									6004	6-3



CHAPTER 6

SURVEILLANCE PROGRAM


- 6001. MEDICAL SURVEILLANCE PROGRAM. A medical surveillance program is required for class IIIB and class IV laser systems. All personnel designated as incidental laser personnel should have a documented visual acuity screening examination prior to assignment to laser systems operations. Laser personnel should have examinations as required by paragraph 6003.
- 6002. MEDICAL SAFETY. Personnel designated as incidental or laser personnel by their Regimental or separate Battalion LSSO's, shall be required to wear the proper eye protection when engaged in force-on-force tactical exercises. Additionally, any incidental personnel involved in work downrange, i.e., moving targets, shall wear approved eye protection.
- 6003. MEDICAL EXAMINATIONS. Prior to designation or commencement of tasks directly related to laser operations or maintenance; or if any individual is exposed to laser radiation and an eye injury is suspected or observed, a complete medical examination shall be performed as soon as possible. The examination shall consist of:
- a. A medical history with emphasis on occular systems and history of medication usage (particularly potentially photosensitizing drugs).
 - b. Visual acuity determinations.
 - c. Examinations of various structures of the eye.
- d. Polaroid color photographs of the posterior pole of the funds including the area of the macula and optic nerve.
- e. Any other protocol recommended by the cognizant medical officer or by consultation with the Commander, Naval Medical Command (MEDCOM-21).
- 6004. REFERENCE. The medical surveillance program is in accordance with reference (c).



CHAPTER 7

ACCIDENT INVESTIGATION/REPORTING PROCEDURES

								PARAGRAPH	PAGE
ACCIDENT INVESTIGATION.	•	•	•			.•		7001	7-3
REPORTING PROCEDURES	•	•		•	•			7002	7-3




CHAPTER 7

ACCIDENT INVESTIGATION/REPORTING PROCEDURES

7001. ACCIDENT INVESTIGATION. When an individual is exposed to laser radiation and an injury is suspected or observed, a complete medical examination shall be performed as soon as possible. Examination procedures are covered in Chapter 6. The Commanding Officer will direct the Regimental or separate Battalion LSSO's to conduct an accident investigation. This investigation will be forwarded to the appropriate installation commander (Attn: Range Control) in accordance with the requirements of reference (f).


7002. REPORTING. A letter report shall be submitted to the Commander, NAVMEDCOM (MEDCOM-21) via the Commanding General, 2d Marine Division (ATTN: Surgeon) within fifteen (15) days of the incident. As a minimum, the report shall contain a list of personnel exposed, an estimate of the exposure received, a copy of medical examinations performed, and a narrative summary of events leading to the incident.



CHAPTER 8

RECORDS


										PARAGRAPH	PAGE
RECORDS.										8001	8-3



CHAPTER 8

RECORDS

- 8001. RECORDS. At a minimum, the exposure records shall contain a list of exposed personnel, an estimate of the exposure received, and a description of the physiological symptoms. This report should also include as an enclosure, a description and examination of the situation and the corrective measures/recommendations necessary to prevent future occurrences. Records will include, but need not be limited to:
- a. A log to record all operational, maintenance or training laser firings to include date, time, location, target, laser range officer, operator, purpose and personnel present. If the laser is fired airborne, include type aircraft, Bureau Number (BUNO), location/heading, altitude, and designated target. Additional documentation may also be included, as deemed appropriate.
- b. An inventory record of all command held laser devices along with a Description and Analysis Report will be maintained, as required by references (b) and (d).
- c. A current listing of all units and personnel who are authorized to engage in laser operations and their specific function/limitations. Such a list should be readily accessible to the LSSO, and range control and periodically updated when changes occur.
- d. Training records of all personnel who engage in laser operations, maintenance or training, to include times and dates of training received, as well as copies of designations and assignments for laser operations.




ENCLOSURE (1)

LASER SAFETY

LASER ANNUAL INVENTORY REPORT FORMAT

From: To:	Commanding General, 2d Marine Division, FMF (Attn: Div Safety)
Subj:	Exempt LASER Inventory Report for FY
Ref:	(a) NAVELEXINST 5100.12
1. In is sub	accordance with the reference, the following annual report
a.	LASER Type
b.	Manufacturer
c.	Part Number (if available)
d.	Contact Number (if available)
e.	Number of LASERS
f.	National Stock Number (if available)
g.	Exempt Qualification (check applicable boxes)
	Combat Training
	Classified
2. STA	TUS
a.	Number of LASERS:
	In use In storage Awaiting Disposition
	Transferred within DOD to Date ASD approval date (Provide Serial Numbers)
	Disposed outside of DOD to Date ASD approval date (Provide Serial Numbers)
	//SIGNATURE//




LASER RANGE FIRING LOG

COMMAND	DATE	RANGE	
LASER SYSTEM_	LASER	SERIAL NUMBER	Lou 12
LEFT LIMIT (AZIMUTHS)	RIGHT (AZIMU	LIMITTHS)	
MAX. RANGE AUTHORIZED	MI	N. RANGE AUTHORIZED	4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
TIME CLEARED FOR USE	TI	ME SECURED FROM USE	
LASER SAFETY OFFICER	RANK	UNIT	
OPERATOR #1 NAME	RANK	TIME USED FROM	то
OPERATOR #2 NAME	RANK	TIME USED FROM	то
OPERATOR #3 NAME	RANK	TIME USED FROM	то
OPERATOR #4 NAME	RANK	TIME USED FROM_	то
WAS A FILTER REQUIRED WHICH FILTER WAS USED	YES NO		

SAMPLE FORMAT LASER RANGE FIRING LOG

ENCLOSURE (2)



LASER SAFETY INSPECTION CHECKLIST

		YES/NO
	Does the command have Class III or IV LASERS or military exempt LASERS?	
REFERENCE	If yes, continue with the following:	
NAVELEXINST 5100.12 Encl (4)	Has a LASER hazard control program been established?	
NAVELEXINST 5100.12 Encl (4)	Has a LASER Systems Safety Officer (LSSO) been designated in writing and does he have direct access to the CO?	
NAVELEXINST 5100.12 Encl (4)	Does the LSSO have sufficient technical competence and authority to approve or disapprove the local use of LASERS?	,
NAVELEXINST 5100.12 Encl (5)	Has the LSSO received a minimum of 20 hours of formal classroom training in LASER radiation? (LASER Safety School or equivalent)	
NAVELEXINST 5100.12 Encl (4)	Has a local LASER Safety Organization or Committee been established to assist the LSSO in discharging his responsibilities? (If warranted by the magnitude of the Potential hazard in local operations)	
NAVELEXINST 5100.12 Encl (4)	Has each local LASER user been approved or submitted for safety approval to higher authority by the LSSO?	
NAVELEXINST 5100.12 Encl (4)	Does the LSSO maintain a list of all LASERS and their locations?	
NAVELEXINST 5100.12 Encl (4)	Is a list of Class IIIB and IV LASERS and Military Exempt LASERS submitted annually to NAVELEXSYSCOM? (Due 15 October)	
	그는 그들은 그들은 그 살아왔다. 그는 사람들은 이 그 이 나는 그 그들은 그들은 그들은 그들은 그들은 그들은 그를 보는 것이 되었다. 그는 그를 보는 것은 그를 보고 하는 그를 보는 것이 되었다.	

Div	70	51	100).3
22				

	는 12도로 보면 있는 12도 17명에 17명에 17명이 17명이 12명을 보고 있는 12도로 보면 12명을 보고 있는 12명을 보고 있는 12명이 12명이 12명이 12명이 12로 12명이 12로	
NAVELEXINST	Have local LASER safety regulations been	
5100.12	established including standing operating	
Enc1 (4)	procedures for indoor maintenance and	
A Styling South A State	outdoor operational LASER operations?	_/_
William Street		
NAVELEXINST	Have safety responsibilities been	
5100.12	written for LASER or LASER System	
Encl (4)	Operations which include normal	
	operational procedures, emergency	
	procedures and documentation of all	
	LASER firing?	_/_
NAVELEXINST	Are all local LASER Ranges	
5100.12	surveyed at least annually for	
	safety?	1
Encl (4)	salety	
NAVELEXINST	Are warning systems and signs placed	
5100.12	in appropriate locations to protect all	
Encl (4)	personnel from LASER radiation?	1
Dict (4)		
NAVELEXINST	Has a LASER protective goggles program	
5100.12	been established? Are they properly	
Encl (5)2.e	labeled and periodically inspected and	
	evaluated?	_'_
MANUEL BUTNOM	Have all personnel in areas with LASERS	
NAVELEXINST	been informed by formal classroom	
5100.12	training about the potential hazards	
Encl (5)	associated with accidental exposure to	
	LASERS?	1
	LASERS:	
NAVELEXINST	Are local LASER radiation accidents and	
5100.12	incidents investigated with appropriate	
Encl (4)	recommendations and corrective actions	
	initiated?	_/_
**************	To medical evaluation newformed and an	
NAVMEDCOM	Is medical evaluation performed and an incident report submitted via the chain	
INST 6470.	incident report submitted via the Chain	
2.5 d&e	of command to COMNAVMEDCOM (MEDCOM 21)	
	within 30 days of the incident with a	,
	copy to NAVELEXSYSCOM (ELEX 7034)?	
	Medical Surveillance	
NAVMEDCOM	Has the LSSO determined and designated	
INST 6470.	incidental and LASER personnel?	
2.5.b	NOTE: Incidental personnel - Those	
2.3.5	moral Postonial Postonial	

whose work make it possible but unlikely for them to be exposed to LASER energy sufficient to damage eyes or skin. (e.g., range personnel)

	그 그리고 있는 그 전에 가장 하는 경기를 하는 것이 되었다. 그리고 있는 것이 없는 것이 없는 것이 없는 것이 없는 것이 없는 것이 없는 것이다.	
	<u>LASER personnel</u> - those who operate laser devices.	
NAVELEXINST 5100.12 Encl (4)	Has the LSSO submitted records of personnel exposed to LASER emissions to the medical officer for medical surveillance?	_/_
NAVMEDCOM INST 6470. 2.5.b	Are all personnel designated either as Incidental or LASER Personnel enrolled in the appropriate medical surveillance program?	_/_
NAVMEDCOM INST 6470. 2.5.b	Are the required examinations performed prior to participation in and upon termination of LASER work and following any suspected LASER injury?	_/_
NAVMEDCOM INST 6470. 2 Encl (2)	Have incidental personnel received eye examinations for visual acuity?	
NAVMEDCOM INST 6470. 2 Encl (2)	Do LASER personnel receive visual acuity determinations and eye examinations based on the wave length of LASER radiation? Is a medical history taken?	
NAVMEDCOM INST 6470. 2.5.b	Are there any military exempt LASERS? (Those designed for combat, combat training or classified)	_/_
	If yes	
SECNAVINST 5100.14A 7.c(1)	Have all military exempt LASERS in use been reviewed and approved safe by the NAVY LASER Safety Review Board? (Contact NAVELEXSYSCOM (ELEX 7034)).	_/_
SECNAVINST 5100.14A 7.b(2)	Is the required caution label affixed to all military exempt LASERS?	_/_
SECNAVINST 5100.14A 7.c(3)	Is an inventory and record of the status of all exempted LASER products maintained?	_/_

DivO 5100.3

22 May 1985

SECNAVINST

Is a report on military exempt LASERS
provided to NAVELEXSYSCOM by 15

October of each year?

SECNAVINST

Is approval received from the Deputy
Assistant Secretary of Defense for
Comparison of Comparison

exempt LASER?

LASER MAINTENANCE SAFETY PRECAUTIONS

- 1. LASER hazard warning signs shall be posted on all entrances to LASER maintenance areas in accordance with reference (b), so as to minimize the risk of accidental exposure. The LASER units and test benches shall be marked with warning signs as well.
- 2. All personnel engaged in essential duties concerned with LASER firing shall wear approved, eye protection during firing. Non-essential personnel shall leave the LASER area during firing.
- 3. All functional entrances to bench and boresight LASER firing areas shall be interlocked so that opening such a door will stop LASER emission.
- 4. Equipment interlocks shall be maintained in operating condition at all times. In the event required and approved maintenance procedures can only be performed by circumventing some interlock feature, that procedure will be performed only under the supervision of a designated LASER Safety Supervisor, with prior approval of a qualified LASER Systems Safety Officer or qualified Maintenance Officer. In all such cases, a documented quality assurance inspection shall be performed at the completion of that work to ensure that proper interlock operation has been restored.
- 5. Appropriate and adequate LASER safety radiation containment procedures and devices shall be in effect whenever any LASER is fired. Examples of containment devices are lens covers, diffusers, shields, and enclosures.
- 6. The LASER test area shall be kept clear of all specular reflectors or diffuse surfaces with a high coefficient of reflection.
- 7. During LASER operations, the minimum amount of personnel (normally two) shall be present.
- 8. Where practical, a countdown procedure shall be followed prior to LASER firings.

