Memorandum

DATE: 1 4 MAY 1986

4280 MAIN

FROM: Service Contract Manager, Base Maintenance Division,

Marine Corps Base, Camp Lejeune


Resident Officer in Charge of Construction, Facilities Support TO: Contracts, Marine Corps Base, Camp Lejeune

SUBJ: FACILITIES SUPPORT CONTRACT, ELEVATOR MAINTENANCE CONTRACT N62470-85-6301

- Encl: (1) QAE Memo, on Recent Safety Inspection and Certification of Elevators at MCAS, Naval Hospital, and MCB, CLNC
 - 1. The enclosure is provided for your information and action for the subject contract.
 - As mentioned by the QAE in paragraph two of the enclosure, it is requested that the contractor be notified by the AROICC of the discrepancies which are the contractor's responsibility to correct. Any assistance required of Base forces by the contract will be provided.
 - 3. The discrepancies annoted Base Maintenance responsibility will be corrected by in house forces as soon as possible. If any discrepancies are beyond Base Maintenance capability to correct, we will probably pursue a change order on the subject contract or request a one time contract.
 - 3. Point of contact is Greg Shoemaker, Base Maintenance, x5809.

G. SHOEMAKER

Shoemaker



Memorandum

DATE: 14 MAY 1986

4280 MAIN

FROM:

Quality Assurance Evaulator, Base Maintenance Division,

Marine Corps Base, Camp Lejeune

TO:

Service Contract Manager, Base Maintenance Division,

Marine Corps Base, Camp Lejeune

SUBJ:


SAFETY INSPECTION & CERTIFICATION OF ELEVATORS AT MARINE CORPS AIR STATION, NAVAL HOSPITAL AND MARINE CORPS BASE, CAMP LEJEUNE MAINTAINED ON CONTRACT N62470-85-6301

Encl: (1) Certified Inspector's Summary of Certifications & Dates
Approved

(2) Certified Inspector's Report of Discrepancies for Each Elevator

- 1. Mr. Robert Kucharski, (a certified Elevator inspector from the Naval Public Works Center, Norfolk, Va.) completed the required subject safety inspection on 1 May 1986.
- 2. All the elevators were certified for operation as stated in enclosure (1).
- 3. In enclosure (2) discrepancies which require attention were listed by elevator. Each discrepancy is annoted with a "C" for contractor or "M" for maintenance, indicating who is responsible for each listing.

T. LANIER



INSPECTION SUMMARY - ELEVATORS

5NDPWC 4730/6 (New-7/76)

Commanding Officer, Navy Public Works Center, Norfolk, VA 23511

DATE OF THIS REPORT 5/6/86

Commanding General, Marine Corps Base, Camp Lejeune, N.C. 28540

FOR QUARTER ENDING

1.00	DENTIFICATION	17-5			INSPECTION		CONDITION
ELEVATOR NO.	BUILDING OR : LOCATION	USE	TYPE OR DRIVE	INSPECTION DATE	REMARKS	SATIS- FACTORY	A Paris 1
1	2	3	4	5	6		
1	H-1	P	4/E./	4/28/86	Certified for Operation .	7	8
2	H-1	P	Е	4/28/86	Certified for Operation		X
3	H-1	P	E	4/28/86	Certified for Operation		X
4	H-1	P	Е	4/28/86	Certified for Operation		X
5	H-1	P	Е	4/28/86	Certified for Operation		Х
6	H-1	P	E	4/28/86	Certified for Operation		Х
1	15	P	E	4/28/86	Certified for Operation		X
1	1041	P	Н	4/28/86	XXCertified for Operation (SEE ITEM (a) OF		X
					ATTACHED INSPECTION REPORT		X
1	900	F	н	4/28/86	Certified for Operation		
NOTE: Insp	ector's report	s are a	ttache	ed.			X

CODE FOR COLUMN 3

D = DUMBWAITER

E = ESCALATOR

F = FREIGHT ELEVATOR

L = PLATFORM LIFT

P = PASSENGER ELEVATOR

CODE FOR COLUMN 4

ELEVATORS, PLATFORM LIFTS, DUMBWAITERS

E = ELECTRIC

H = HYDRAULIC

M = HAND

ESCALATORS

C = CHAIN


D = COUPLING

G = GEAR

ATTACHMENTS

9 INSPECTOR'S REPORTS (For items with X in column 8) SIGNATURE

BY DIRECTION



INSPECTION SUMMARY - ELEVATORS

5NDPWC 4730/6 (New-7/76)

FROM Commanding Officer, Navy Public Works Center, Norfolk, VA 23511 DATE OF THIS REPORT

Commanding General, Marine Corps Base, Camp Lejeune, N.C. 28540

5/6/86 FOR QUARTER ENDING

	IDENTIFICATION				INSPECTION		100 100 100
ELEVATOR NO.	BUILDING OR ' LOCATION	USE	TYPE OR DRIVE	INSPECTION DATE	REMARKS	SATIS- FACTORY	CONDITION CORRECTION REQUIRED
1	2	3	4	5	6		
1	670	F	Н	4/29/86	Certified for Operation	7	8
1	AS 705	P	Н	4/29/86	Certified for Operation		X
2	AS 705	P	Н	4/29/86	Certified for Operation		X
1	NH 100	P	E	4/30 86	Certified for Operation		X
2	NH 100	P	E	4/30/86	Certified for Operation		X
4	NH 100	P	Е	4/30 86	Certified for Operation		Х
5	NH 100	P	E	4/30/86	Certified for Operation		X
7	NH 100	P	E	4/30/86	Certified for Operation		X
8	NH 100	P	E	4/30/86	Certified for Operation		X
9	NH 100	P	н	5/1/86	Certified for Operation		Х
13	NH 100	P		5/1/86	Certified for Operation		X

D = DUMBWAITER

E = ESCALATOR

F = FREIGHT ELEVATOR

L = PLATFORM LIFT

P = PASSENGER ELEVATOR

CODE FOR COLUMN 4

ELEVATORS, PLATFORM LIFTS, DUMBWAITERS

E = ELECTRIC

H = HYDRAULIC

M = HAND **ESCALATORS**

C = CHAIN


D = COUPLING

G = GEAR

ATTACHMENTS

INSPECTOR'S REPORTS (For items with X in column 8) SIGNATURE

BY DIRECTION



INSPECTION SUMMARY - ELEVATORS

5NDPWC 4730/6 (New-7/76)

SHEET 3 OF 3

Commanding Officer, Navy Public Works Center, Norfolk, VA 23511

DATE OF THIS REPORT 5/6/86

Commanding General, Marine Corps Base, Camp Lejeune, N.C. 28540

FOR QUARTER ENDING

	IDENTIFICATION	-	1	1	INSPECTION	T	COMPITION
ELEVATOR NO.	BUILDING OR ' LOCATION	USE	TYPE OR DRIVE	INSPECTION DATE	REMARKS	SATIS- FACTORY	CORRECTION REQUIRED
1	2	3	4	5	6	1	
15	NH 100	P	Н	5/1/86	Certified for Operation	7	8
16	NH 100	P	Н	5/1/86	Certified for Operation		X
12	NH 100	P	н	5/1/86	Certified for Operation		X
11	NH 100	P	н	5/1/86	Certified for Operation		Х
14	NH 100	P	н	5/1/86	Certified for Operation		Х
10	NH 100	P	Н	5/1/86	Certified for Operation		Х
					ostorized for operation		X
e e							
		4.7					
	1 1 TO 1 TO 1						
OR COLUMN 3							

CODE FOR COLUMN 3

D = DUMBWAITER

E = ESCALATOR

F = FREIGHT ELEVATOR

L = PLATFORM LIFT

P = PASSENGER ELEVATOR

CODE FOR COLUMN 4

ELEVATORS, PLATFORM LIFTS, DUMBWAITERS

E = ELECTRIC

H = HYDRAULIC

M = HAND

ESCALATORS

C = CHAIN

D = COUPLING


G = GEAR

ATTACHMENTS

6 INSPECTOR'S REPORTS
(For items with X in column 8)

SIGNATURE

BY DIRECTION



1. FACILITY NO.


Instructions for completing form are

FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE	Te summer			EIS CONTROL INSPECTI
			5. FUNCT. ACCT. NO.			8 MGR. INSPECTION BE
AS 705 DESCRIPTION AND LO				SCHE		PANTE /
SESCRIPTION AND LO	CATION					
		And the second second second second		4	/29/86	1800 61.18
		Station Communication		1 24	/29/86	895 [08
B.O.O. Mar	ine Corps Air S	Station, Camp Leje	une, N.C.			1897 < 10/8
B.O.O. Mar	ine Corps Air S	Station, Camp Lejeu	une, N.C.			12. SHEET NO.

INSPECTION & CERTIFICATION OF #1&2 ELEVATORS.

- General. Subject elevators are maintained by Montgomery Elev. Co. The service being provided is considered fair and the equipment is operating satisfactorily.
- Inspection. Inspection of the elevators did not uncover any major safety problems. Discrepancies to be corrected are:
- Elevator #1.
- a. Replace damaged door safety edge.
- Repair/Replace car emergency light. __ b.
- c. Adjust door closure.
- d. Replace burnt out indicator light bulbs.
- Elevator #2.
- __ a. Replace damaged door safety edge.
- b. Adjust door closure.
- c. Repair/Replace car emergency light.
- M d. Pump out water from the pit. Locate source of leak and
- 5. Elevator Inspection Certificates, NAVFAC 9-11014/33, was posted
- 6. The next scheduled inspection is November 1986.


an Wurlack



Instructions for completing form are contained in NAVFAC MO-322, Vol. I

	contained in NAVFAC MO-322, Vol. I	
#15	2. GOST ACCOUNT NO. 3. F.A.C. 4. CATEGORY CODE 5. FUNCT. ACCT NO. 6. L.M.C. 7. D/ SCHEE	O. MGR. INSPECTION BE
9. DESCRIPTION AND LOC	CATION	28/86 MAL DATE
Naval Dental	Clinic, MCB Camp Lejeune, N.C.	20100 att 20108
10. INSPECTOR	nos camp Lejeune, N.C.	
Kucharski, N	Navy Public Works Center, Norfolk A/V 564-7921	TIME USED 12. SHEET NO.
rice in a transfer of the	13. DESCRIPTION OF 175	1 OF 1
	13. DESCRIPTION OF ITEM AND DEFICIENCY	
	INSPECTION & CERTIFICATION OF #1 ELEVATOR	
	1. General. Subject elevator is maintained by Mon The service being provided is considered	
7.50	The service being provided is considered good a is operating satisfactorily.	tgomery Elev. Co.
	is operating satisfactorily.	nd the equipment
	Inspection of the	lincover
	safety problems. Discrepancies to be corrected	are:
	M - a. Install a car France	
	a. Install a car Emergency light.	
	b. Replace over sized fuses to	
	proper size. b. Replace over sized fuses in the control	panel, with
	c. Replace missing car exhaust fan.	the transfer of the
	d. Install in the pit a stop switch and lig	ht fire
	3.	ne lixture and
	 Elevator Inspection Certicate, NAVFAC 9-11014/33 in the car. 	, was posted
	4. The next Scheduled inspection is November 1986.	

as Kushand



Instructions for completing form are contained in NAVFAC MO-322, Vol. I

FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE	15 5000		DEIS LINSPECT
1041			5. FUNCT. ACCT. NO.	6. L.M.C. 7. DATE SCHED:	8. MGR. INSPECTION
DESCRIPTION AND LOCA	TION			The state of the s	28/86 DATE 16/
					20100 1111 2/9
Brig, MCB Ca	mp Lejeune, N				20,00 1417 2/6/
Brig, MCB Ca	mp Lejeune, N				12/0/0/
Brig, MCB Ca	mp Lejeune, N	.C. rks Center, Norfol	k A/V 564-79	11. INSPECTION TIN	1210/10/


INSPECTION & CERTIFICATION OF #1 ELEVATOR

- 1. <u>General.</u> Sublect elevator is maintained by Montgomery Elev. Co. The service being provided is considered good and the equipment is operating satisfactorily.
- 2. <u>Inspection</u>. Inspection of the elevator did uncover a Potential Safety Problem. Discrepancy to be corrected is:

a. The Flexible Hose Shall be Replaced beyond 6 years of the installation date.

- Elevator Inspection Certificate, NAVFAC 9-11014/33, was posted in the car.
- 4. The next scheduled inspection is November 1986.

20 Kulne



INSPECTOR'S REPORT MAVFAC 11014/38 (REV. 9-72)


S/N 0105-003-700	2	contained in NAVA	CAC MO-322, Vol.	are	
1. FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE		1	DEIS CONTROL INSPECTION
900	9	J. CATEGORY CODE	5. FUNCT. ACCT. NO.	6. L.M.C. 7. DATE SCHED:	8. MGR. INSPECTION BR.
9. DESCRIPTION AND LO	OCATION			ACT4:/28/86	5 DATE
10. INSPECTOR	ejeune, N.C.				1/6/86
Kucharski,	Navy Public Wo:	rks Center, Norfol	k A/V 564-79	11. INSPECTION TIME USED	SILET NO.
		13. DESCRIPTION OF	TEM AND DEFICIENCY		1 OF 1
	1. General The ser	Subject elevaterice being provide ating satisfactors	or is maintai		ery Elev. Co. he equipment
	0	ion. Inspection of problems. Discrep	TO BE	corrected are:	
	a.	Replace missing d	oor pull chai	in covers at al	1 floors.

sheet steel at least 0.0164 in. to protect against fire. c. Adjust the car gate, to open the same height as the

b. The underside of the car platform shall be covered with

- 3. Elevator Inspection Certificate, NAVFAC 9-11014/33, was posted
- The next scheduled inspection is November 1986.

Ook unhous



INSPECTOR'S REPORT MAVFAC 11014/38 (REV. 9-72)

3/N 0105-003-7002		contained in NA	VFAC MO-322, Vol.	are I	
670 9. DESCRIPTION AND LOCATION OF CAMP LETERS		3. F.A.C. 4. CATEGORY CODE	5. FUNCT. ACCT. NO.		DEIS CONTROL INSPECTION 8. MGR. INSPECTION BR. DATE DATE
Kucharski, N		13. DESCRIPTION OF	TIEM AND DEFICIENCY		12. SHEET NO.
	1. General The serv	Subject elevativice being providating satisfactor	tor is maintain		ery Elev. Co. he equipment
	2. Inspects	ion. Inspection problems. Discre	of the elevato	or did not unco	over any major

a. Machine room is being used as a storage space. Only machinery and equipment required for the operation of the elevator shall be permitted in the machine room.

- b. Repair/Replace car emergency bell.

Replace burnt out bulb to the car emergency light.

safety problems. Discrepancies to be corrected are:

d. Secure top of car emergency exit.


- e. Replace frayed pump belts.

M ___ f. The underside of the car platform shall be covered with sheet steel at least 0/0164 in. to protect against fire.

M __ g. Install a gauge port to ensure proper pressure.


- Elevator Inspection Certificate, NAVFAC 9-11014/33, was posted
- 4. The next scheduled inspection is November 1986.

Wichoel-



Instructions for completing form are contained in NAVFAC MO-322, Vol. I


1. FACILITY NO.		16 Table 1 Section 1 18 18 18	TAC MO-322, Vol.	I	DEIS CONTROL
NH-100	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE	5. FUNCT. ACCT. NO.	6. L.M.C. 7. DATE SCHED:	MGR. INSPECTION BR.
Naval Hosp	oital, Camp Lejeu	ine, N.C.		ACT 4/30-	-5/1 88 6 46
		ks Center, Norfo		11. INSPECTION TIME	JSED 12. SHEET NO.
	y rubile wol	13. DESCRIPTION OF	IK A/V 564-79 ITEM AND DEFICIENCY	21	1 OF 4
		ION & CERTIFICAT: LEVATORS	ION OF #1,2,4,	5,7,8,9,10,11	
	equipmen	nt is operating s	atisfactorily.	very good	
	2. Inspect:	ion. Inspection afety problems.	of the elevato Discrepancies	ors did not un	ncover any
	3. Elevator	#1.			
	С — a.	Repair/Replace de	oor elect eyes		
	c - b.	Repair floor indi			
	C — c.	Adjust rope tensi	lon.		
	C - d.	Commutator is gro	oved and threa	ading.	
	m e.]	Install guard ove	r top of car s	sheave.	
	run.	Repair Phase II E	mergency In-Ca	r Operation.	Car will not
	4. Elevator	#2.			
	C — a. R	eplace missing sp	oring to the co	ompensating c	hain and car.
	at the 3rd	ign of rouge on # d. floor. Lubric of ropes during	2 hoisting rop	e located wi	
		ommutator is groo			
	C — d. In	stall missing fa	n to the hoist	ing machine.	
	e. Ca	r will not opera	te in Phase II	Emergency In	-Car OPeration.
	5. Elevator #	4			
				CONT:	



Instructions for completing form are

	2. COST ACCOUNT NO.	3. F.A.C	4. CATEGORY CODE	TS. FUNCT. ACCT. NO.	7. L.M.C. 7. DATE	8. MGR. INSPECTION BR.
FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C	4. 04.100.11 0.000		SCHED: ACT.:	MIN SOLO
DESCRIPTION AND	LOCATION					
. INSPECTOR					11 INSPECTION TIM	
		13.	DESCRIPTION OF	ITEM AND DEFICIENCY		2 OF 4
		13.		TICH AND DETTOTENCE		a primar than the last the last
			CONT:			
	C-	a. Repa	ir/Replace	door elect ey	res.	
	m 1	. Inst	all guard o	ver top of ca	ar sheave.	
	c	. Repl	lace missing	2nd. & 3rd.	floor dust	covers.
	0	e. Adju	ıst brakes t	o the hoisting	ng machine.	
						pump discharge.
	<u> </u>	g. Car	will not op	erate on Phas	se II Emerge	ency In-Car Operation
	6. Eleva	tor #5.				
	c	a. Wip	e oil from c	ar guide rai	ls.	
	C - 1	b. Rep	air/Replace	door elect e	yes.	
	m	c. Ins	tall guard o	ver top of c	ar sheave.	
	c -	d. Doo	rs will not	stay open on	Phase II E	mergency In-Car
	Opera	tion.				
	7. Eleva	tor #7.				
	c _	a. Rep	air/Replace	door elect e	yes.	
	m -	b. Ins	tall guard o	over top of	car sheave.	
	C — Mech	c. Wir anic to	e brake on g observe con	governor rope	located at pe during r	the 2nd. floor. egular maintenance.
	2-	d. Rep	lace missing	g lst. dust c	iver.	
		e. Wat	er leakage	in the pit.	Buffer supp	ort show signs
	8. Eleva	tor #8.				

CONT:




Instructions for completing form are contained in NAVFAC MO-322, Vol. I

7N 0105-003-700	02	contained in NAVF	AC MO-322, Vol.		DEIS CONTROL INSPECTION
. FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE	5. FUNCT. ACCT. NO.	6. L.M.C. 7. DATE SCHED: ACT.:	8. MGR. INSPECTION BR.
. DESCRIPTION AND	LOCATION	er Grand Marriage B. A			10/10/10/10
O. INSPECTOR			i de la companya de l	11. INSPECTION TIME USED	12. SHEET NO. 4
		13. DESCRIPTION OF	ITEM AND DEFICIENCY		
	C _ a.	CONT. Repair/Replace do	oor elect eyes		
	M - b.	Install guard over	er top of car	sheave.	
	C — c. operati	Rear door will no	ot close on Ph	nase II Emergenc	y In-Car
	9. Elevat	or #9.			
		Extend door safet door.	y edge at lea	ast 1½ in. beyon	d leading
	10. Eleva	tor #13.			
	c — a.	Repair car emerge	ency light and	emergency bell	
	C — b.	Remove oil dry fr	om the pit.		
	11. Eleva	tor #15.			
	C — a.	Emergency recall	does not oper	ate.	
	C — b.	Remove oil dry fr	om the pit.		
	C — c. elect	Secure flexible cobox cover.	onduit to the	e car exhaust fa	n and install
	12. Eleva	tor #16.			
	C — a.	Repair eratic doo	r operator.		
	С- b.	lst. floor call b	utton is not	working-	
	C — c.	Remove oil dry fr	om the pit.		

- d. Repair door elect eyes.

CONT:




Instructions for completing form are contained in NAVFAC MO-322 Vol. I

		13.	DESCRIPTION OF	ITEM AND DEFICIENCY	Web Land		
O. INSPECTOR					11. INSP	ECTION TIME USED	12. SHEET NO.
. DESCRIPTION AND LOC	ATION						10000110
		- PA				ACT.:	Jole Lill
. FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C.	4. CATEGORY CODE	5. FUNCT. ACCT. NO.	6. L.M.C.		8. MGR INSPECTION BR

cont;

- 13. Elevator #12.
- ____ a...Repair door elect eyes.
 - 14. Elevator #11.
- a. Adjust door operator. Door is slaming.
- b. Repair/Replace car emergency bell.
 - 15. Elevator #14.
- C a. Repair door elect eyes.
 - 16. Elevator #10.
- ___ a. Repair door elect eyes.
 - 17. Elevators are scheduled for a five year load and safety test November 1987.
 - 18. Elevator Inspection Certificates, NAVFAC 9-11014/33, were issued to LT. Richards, P.W.D Officer.
 - 19 The next scheduled inspection is November 1986.

apkrenase



Instructions for completing form are contained in NAVFAC MO-322, Vol. I

CONTROL DEIS INSPECTION 3. F.A.C. 4. CATEGORY CODE 5. FUNCT. ACCT. NO. ACT 4/28/86 11. INSPECTION TIME USED 12. SHEET NO.

Marine Corps Base, Camp Lejeune, N.C.

2. COST ACCOUNT NO.

H-1

. FACILITY NO.


INSPECTION & CERTIFICATION OF # 1,2,3,4,5,&6 ELEVATORS

Kucharski, Navy Public Works Center, Norfolk A/V 564-7921 13. DESCRIPTION OF ITEM AND DEFICIENCY

- General. Subject elevators are maintained by Montgomery Elev. Co. The service being provided is considered good and the equipment is operating satisfactorily.
- Inspection. Inspection of the elevators did not uncover any major safety problems. Discrepancies to be correcter are:
- Elevator #1.
- C a. Replace over sized fuses in the control panel with proper size.
- C _ b. Replace missing door gibs located at the 3rd. floor.
- C c. Dust down entire hoistway.
- M ___ d. Machine room lighting should be altered to provide suitable lighting in all working areas.
- M ___ e. Install emergency ligting in the car.
- M __ f. Install a pit stop switch.
- M g. Secure from inside the pit the pit access door.
- 4. Elevator #2.
- M ___ a. Retile damaged car floor.
- C b. Replace missing and loose door gibs located at the 1st. and 3rd. floor.

CAM — c. See items a. c. d. e. f. and g. of Elevator #1.

- 5. Elevator #3.
- C __ a. Repair noisy door operator.
- b. Replace missing door gib located at the 2nd. floor



INSPECTOR'S REPORT NAVFAC 11014/38 (REV. 9-72)

S/N 0105-003-7002		contained in NAVE	FAC MO-322, Vol.	I	DEIS CONTROL	
. FACILITY NO.	2. COST ACCOUNT NO.	3. F.A.C. 4. CATEGORY CODE	5. FUNCT. ACCT. NO.	6. L.M.C. 7. DATE SCHED: ACT.:	B. MGR. INSPECTION BR.	
O INSPECTOR				11. INSPECTION TIME USED	12. SIVEET NO.	
		13. DESCRIPTION OF	ITEM AND DEFICIENCY		2 OF 2	
CA	6. <u>Elevato</u> C a. C b.	Cont. See items a. d. or #4. Repair/Replace car Car lighting is r See items d. e. i	ar emergency	bell.		
	7. Elevator #5.					
	С а.	a. Replace missing "J" box covers in the hoistway.				
	C b. Replace missing door gib located at the 2nd. floor.					
	m c. See items d. e. f. and g. of Elevator #1.					
	8. Elevato	r #6.				
	C - a. Clean oil from the pit.					
	0.					

Replace missing gibs located at the 1st. and 2nd. floor

c. See items d. e. f. and g. of Elevator #1

9. Elevator Inspection Certificates, NAVFAC 9-11014/33, were posted in the cars.

The next scheduled inspection is November 1986

a.P. Kuchende

