

"MASTER FILES MARINE CORPS BASE

CAMP LEJEUNE, NORTH CAROLINA 28542

BO 11090.3 MAIN/DDS/th 18 May 1982

BASE ORDER 11090.3

From: Commanding General Distribution List To:

Subj: Operation and Maintenance of Oil Pollution Abatement Facilities

(a) NPDES Permit No. NC0003239, Marine Corps Base, Camp Lejeune (NOTAL)
(b) CLean Water Act (NOTAL)
(c) BO 11090.1B Ref:

1. Purpose. To publish responsibilities for the operation and maintenance of pollution abatement facilities required to be in compliance with federal and state water quality standards established under references (a) and

2. Background

- a. Reference (c) established policy and procedures regarding the prevention and abatement of pollution resulting from accidental spills or unauthorized discharge of petroleum oil and lubricants (POLs) (e.g., diesel fuel, kerosene, lube oil, etc.) and other hazardous material or waste (e.g., mogas, paint, solvents, acid, etc.). Addressees should be aware that a major part of the oil related pollutants being discharged into storm drains and streams comes from washrack runoff and from maintenance shops where leaks and spills of POLs during routine maintenance operations are not adequately controlled and cleaned up.
- b. Facilities are being constructed at Camp Lejeune and Marine Corps Air Station (Helicopter), New River to provide compliance with references (a) and (b). These facilities connect oil contaminated wastewater drainage lines to the sanitary sewer. Oil/water separators, grit chambers, storm-water storage tanks and related devices are provided to reduce the amount of POLs in the wastewater and to prevent relatively small oil spills from entering and damaging the sanitary sewer and sewage treatment plants. Maintenance shops and other facilities constructed in the future must be equipped with pollution abatement devices in order to comply with reference (a).
- c. Explosions, gases, fumes, etc. resulting from discharge of gasoline and other flammable or hazardous material into the sanitary sewer present a serious threat to personnel safety and may result in severe damage to facilities and equipment. Further, excessive quantity of POLs entering the sanitary sewer will have a significant impact on effective sewage treatment thus causing a violation of environmental standards. Such discharges (spills) are regulated by reference (c) and must be reported to the Base Fire Department (451-3333), immediately.
- d. Washracks and related pollution abatement structures for tactical and tracked vehicles present ongoing maintenance problems due to the amount of soil washed from vehicles. Drainlines on all devices are relatively small in order to control rate of storm-water entering sewer. Keeping these drains open and flowing will require proper operation and routine maintenance.
- 3. Responsibilities. Operation, maintenance and repair of pollution abatement facilities:
 - a. Using organization will:
 - (1) Train personnel to operate pollution abatement facilities located at the work site.
- (2) Ensure that cans, oil filters, rags, brushes, litter or other foreign objects are not discarded on washracks or into oil/water separators, grit chambers, storm-water bypass chambers, storm-water storage tanks, etc.
- (3) Ensure that used oil is disposed of into properly marked waste oil containers and not on the ground or into oil/water separators, grit chambers, storm-water bypass chambers, etc.
- (4) Ensure that neither gasoline nor hazardous waste (e.g., solvents, degreasers, paint, etc.) are disposed of into waste oil tanks/collection systems.
- (5) Clean up oil contaminated soil at the work site (contact Base Maintenance Division 451-2083/1690 for disposal instructions).
- (6) Notify Base Maintenance Division (451-3001) of required maintenance and repair. Marine Corps Air Station (Helicopter), New River commands will notify the Station S-4 Officer of any required maintenance and repair.

(7) Notify Base Maintenance Division (451-5909) of waste oil containers that require emptying.

MAY 2 1 1992 INFO ACT IN LIC/TRING MAINT MT CHIEF FILE BMT FILE COPY

Promile Capy to maint, mant, spece to promile copy to fice & promile copy to fice & promile copy to fice &



- b. Base Maintenance Officer will:
- (1) Provide periodic inspection of maintenance and operation of pollution abatement facilities and initiate action to correct maintenance discrepancies. Report operational deficiencies to the using organizational commanding officer. Close the facility when it is apparent that continued operation will immediately jeopardize the capability of the sewage treatment facility.

3 117 9-12 11

- (2) Service used (waste) oil collection facilities to include pumping out oil storage tanks at regular intervals and initiating action required to maintain and repair tanks and related signs, funnels, gauges and drainlines.
- (3) Service oil/water separators, grit chambers, storm-water bypass chambers and storm-water storage tanks to include removing oily waste and solids, unclogging drainlines and initiating action to make needed repairs.
 - (4) Operate, maintain and repair wastewater lift stations and related mechanical equipment.
- (5) Operate, maintain and repair pollution abatement facilities associated with swimming pools, heating plants and water treatment plants.
 - c. Public Works Officer will:
- (1) Incorporate appropriate pollution abatement devices and structures in facilities constructed aboard Camp Lejeune, as required to provide compliance with the requirements of references (a), (b) and (c).
- (2) Review planned pollution abatement devices and structures with appropriate representatives of the Base Maintenance Officer in order to ensure compatibility with existing sewage collection and treatment facilities and maintenance programs.
- 4. Action. Commanding Officers/area commanders will take action required to assure that organizations and personnel assigned to shops and other facilities equipped with washracks, waste oil collection systems, oil/water separators and related pollution abatement structures are aware of the requirements of this Order. Commanding officers will investigate cases of unauthorized discharge (spills) of POLs or other hazardous material/waste by individuals or organizations within their cognizance and take action required to avoid recurrence of the discharge.
- 5. Applicability. Having received the concurrence of the Commanding Generals, 2d Marine Division, FMF; 2d Force Service Support Group, (Rein), FMFLANT; and the Commanding Officers of the Marine Corps Air Station (Helicopter), New River and tenant units; Naval Regional Medical Center; and Naval Regional Dental Center, this Order is applicable to those Commands.

J. R. FRIDELL Chief of Staff

DISTRIBUTION: A BMAINO (100)

8001 | C YAM

BMT

MILE



UNITED STATES MARINE CORPS Marine Corps Pase Camp Lejeune, North Carolina 28542

BO 11300.1C FAC/JAM/joh 2 Jun 1982

BASE ORDER 11300.16 W Ch

Commanding General From: Distribution List To:

Subj: Utilities and Energy Management Plan

(a) Federal Property Management Regulations, Section 116-3 (NOTAL)(b) MCO 4100.4A (NOTAL)

(1) Facilities, Maintenance and Conservation Terms and Definitions Encl:

Early Turn-on of Air Conditioning Utility and Energy Conservation Committee

(4) List of Buildings currently controlled by the Utility Monitoring and Control System
 (5) Duties and Responsibilities of Building Monitors
 (6) Facility Temperature Standards Notice (SAMPLE)

(7) Utility and Energy Contingency Plan (8) Energy Alert Procedures

(9) Utilities and Energy Command Inspection Form (SAMPLE) (10) Facility Energy Discrepancy Report (SAMPLE)

1. Purpose. To establish the utilities and energy conservation policy, goals, program and contingency plan for Marine Corps Base, Camp Lejeune, Marine Corps Air Station (Helicopter), New River, and their tenants, in order to achieve a continuing reduction in energy consumption, eliminate wasteful energy usage while enabling all commands to continue their operations and training missions without compromise to military readiness, safety, or effectiveness.

2. Cancellation. BO 11300.1F

Background. Utility and energy costs continue to escalate annually requiring more Operations and Maintenance, 3. Background. Utility and energy costs continue to escalate annually requiring more uperations and maintenance, Marine Corps (0&MMC) funding. At Camp Lejeune and MCAS(H), New River, despite some progress in conservation efforts, costs have dramatically increased. The annual costs for heating and cooling during FY-1979, 1980, 1981 were \$12,000,000, \$18,000,000 and \$19,500,000, respectively. The Marine Corps requires continuing, aggressive conservation programs at the activity level which will ensure attainment of the goals established by references (a) and (b). Despite the unique differences in the mission of each of the major commands at Camp Lejeune and MCAS(H), New River, the Department of the Defense mandated goals, the commitment of the Department of the Navy and the Commandant of the Marine Corps to attain the goals and the prospects of reducing both the consumption of our country's precious natural resourses and Operations and Maintenance, Marine Corps funding, should provide the spirit of cooperation and motivation required for a successful program.

4. Policy

- a. General. It is the policy of the Marine Corps to support and implement the energy conservation goals and policy directed by higher authority. This commitment by Headquarters Marine Corps requires similar commitment by Marine Corps Base, Camp Lejeune, the Marine Corps Air Station and their tenants. Significant reductions can be made in the consumption of energy without any significant impact on operations training of commands, subordinate tenants and the supporting establishment. It is therefore the policy of commands at Marine Corps Base, Camp Lejeune and Marine Corps Air Station(H), New River, to meet all applicable energy conservation goals set by higher authority.
 - b. Specific Goals. The goals most significant and relevant to Camp Lejeune and New River are:
- (1) By FY-1985, a reduction of energy consumed per square foot to 20% below that of FY-1975, the baseline year.
- (2) Forty-five percent more energy efficient buildings to be achieved in all new construction measured against buildings constructed during or prior to FY-1975.
- (3) Substitution of more abundant or renewable energy forms for petroleum or natural gas used, culminating in a total substitution of 10% Marine Corps-wide.
- (4) Obtain 1% of Department of Defense (DOD) installation energy by solar and geothermal means by the end of FY-1985 (DOD-wide).
 - (5) Obtain a 15% reduction in commercial motor transport (fuel/mileage).

Ch 1 (25 Oct 1983)

- c. Facilities, Maintenance and Conservation Terms and Definitions. Enclosure (1) contains a list of facilities, maintenance, and conservation terms to provide assistance to those not familiar with the technical terms.
- d. <u>Conservation Initiatives</u>. While no energy conservation initiative is too small to be considered, in keeping with sound management principles, those initiatives which offer the greatest return for the effort and dollars involved will be aggressively sought out and pursued.

e. Minimum Utilization Standards

(1) Air Conditioning

- (a) Air conditioning season will begin on or around 1 June and extend to on or around 15 September.
- (b) The minimum cooling temperature setting authorized is 78° F. The exceptions to this setting are rooms or buildings where electronic equipment is operated and patient care areas in the medical center. The minimum temperature setting for the latter cases is 75° F.
- (c) Air conditioning may only be activated when space temperature exceeds 85°F and when possible ventilation and air circulation is inadequate to relieve discomfort.
- (d) Buildings authorized "early" turn-on of air conditioning are listed in enclosure (2). These are buildings within which is performed a medical mission, no natural ventilation exists, electronic equipment operates, or where occupancy levels are so high as to generate sustained temperatures in excess of 85°F.
- (e) All blowers on fan systems must be shut off when occupants leave enlisted or officer personnel housing.
- (f) All window air conditioners must operate at levels which will not produce temperatures below 78°F and must be shut off when not in use.
- (g) Air handling systems will be utilized without compressors during the four to six weeks preceding the normal air conditioning season. This will be the case in enlisted personnel housing and dining facilities.
 - (h) Air conditioning hours are established as follows:
- $\underline{\underline{\hspace{0.5cm} 1}}$. Administrative spaces: 1000 to 1615, Mondays through Fridays. Air conditioners may not be turned on outside of cooling hours unless temperatures exceed 85°F and all possible ventilation and air circulation cannot relieve severe discomfort of personnel. Administrative spaces operating on a 24 hour basis are exempt from air conditioning hours.
 - 2. Dining Facilities: 0800 to 1900, seven days a week.
- 3. Enlisted Personnel Housing: 0500 to 0800 and 1500 to 2300, Mondays through Fridays; 0500 to 2300 on Saturdays, Sundays and holidays. Billeting for aircarft maintenance night crews will be excluded from these hours.

4. All other nonmedical facilities

- $\underline{\underline{a}}$. Exchange Facilities: 0700 to 1800, during days the PX is in use. Curtain walls should be installed to reduce energy use.
- \underline{b} . Commissary Facilities: From one hour prior to opening until one hour before closing during days of normal operations and from 0800 until one hour prior to cessation of work during nonoperational work days. Because of refrigeration requirements for frozen foods, the temperature in the commissary should not be allowed to exceed 82°F during nonworking hours.
 - c. Club Facilities: 1000 to 2300 on the days clubs are in use.
- $\underline{5}$. Spaces occupied by Watch Standers: During air conditioning season, spaces occupied by watch standers can be air conditioned, if temperatures would otherwise rise above 85°F.
 - $\underline{6}$. School Classrooms, when in use.
- (i) Air conditioning for lounges, meeting rooms, dining areas, and other areas of sporadic use will be authorized only during the period of use. Where possible, curtains should be use to reduce the radiation heating of interior floors and walls.
 - (j) Filters on window air conditioners should be cleaned monthly.
 - (k) Filters on central units should be cleaned at least quarterly.
 - (1) Water chillers must have optimum pressure adjustments.
- (m) When water chiller air conditioning units cannot be shut off, chilled water temperatures will be raised to within $5^{\circ}F$ of design air temperature.

Ch 1 (25 Oct 1983)

- (n) Notify Base Maintenance Emergency Service Desk at extensions 3001/3002 when assistance is needed to make temperature adjustments on thermostats. During work hours MCAS(H), NR activities should call 6816/6817.
- (o) Air Conditioning surveys will be requested via submission of a standard work request form NAVFAC 9-11014/20 (Rev, 2-68) to the Assistant Chief of Staff, Facilities, Marine Corps Base.

(2) Heating

- (a) The heat will be turned on from on or about the third week in October to on or about the first week in April.
- (b) The maximum heating temperature authorized is 65°F in working and administrative spaces and 68°F in unaccompanied personnel housing.
- (c) Requests for use of space heaters in nonheated spaces will be submitted to the Assistant Chief of Staff, Facilities, Marine Corps Base. Second Marine Air Wing tenants at Marine Corps Air Station(H), New River and Marine Corps Air Station(H), New River organizations will submit their requests for space heaters to the Assistant Chief of Staff, Facilities, Marine Corps Base via the I&L Office, Marine Corps Air Station(H), New River.
 - (d) Windows must be kept sealed shut while these facilities are heated.
- (e) Where possible, window curtains will be utilized to reduce drafts and provide additional insulation from the exterior cold.
- (f) Temperature Set Back. Where proper equipment exists, automatic temperature set back will occur as follows:
- <u>1</u>. <u>Unaccompanied Personnel Housing</u>. Temperatures will be set back to 58°F from 2300 to 0400, seven days a week.
- $\underline{2}$. Administrative Spaces. Temperatures will be set back to 55°F from 1800 to 0500, Mondays through Fridays, and from 1800 Friday evening through 0500 on Monday mornings.
 - 3. Dining Facilities. Temperatures will be set back to 55°F from 1800 to 0400, seven days a week.
- $\frac{4}{55}$ Medical Facilities. Exclusive of the main hospital, all medical facilities will be set back to $\frac{5}{5}$ from 1800 to $\frac{5}{50}$ Mondays through Thursdays and from 1800 Friday to 0500 Monday.
- $\underline{5}$. $\underline{\text{Commissary}}$. From one hour prior to closing to one hour prior to opening during days of normal operations, the temperature in commissaries will be set back to 55° F.
 - 6. Exchange. Closing time to 0800, seven days a week, temperatures will be set back to 55°F.
- 7. Chapels. Temperatures should be set back to 50° F, during periods when chapels are not in use and 68° F for two hours prior to and during periods of usage.
- $\underline{8}$. All non-medical facilities with thermostats that can be manually adjusted will be set back to 50°F from 1800 \overline{to} 0600, seven days a week.
- $\underline{9}$. Leaking steam lines should be reported to the Emergency Service Desk, Base Maintenance at extensions $3001/\overline{3}002$. During work hours MCAS(H), NR activities should call 6816/6817.
- 10. Notify Emergency Service Desk, extensions 3001/3002, Base Maintenance if assistance is needed to make temperature adjustments on thermostats. During work hours MCAS(H), NR activities should call 6816/6817.
 - (3) Hot Water. The maximum hot water temperatures for facilities will be as follows:
- (a) Family Housing hot water heaters without dishwashers and other facilities requiring hot water for showers and washing hands should be set at 105°F.
 - (b) Family Housing hot water heaters with dishwashers should be set at 120°F.

(4) Lighting Requirements

(a) Interior Lighting

- 1. Lighting is to be tailored or retrofitted where possible to actual requirements, in accordance with lighting standards set forth below:
 - 100 Foot-candles in Classrooms
 - 50 Foot-candles in Administrative Spaces
 - 30 Foot-candles in Maintenance Areas
 - 10 Foot-candles in General Areas

10 Foot-candles in Hallways

- $\underline{2}$. Where possible, task lighting is to be used in lieu of the overuse of general lighting. Full use is to be made of natural light and light-colored interior walls.
- $\underline{3}$. Lights are to be secured in unused spaces, including storage rooms, laundry rooms, closets, heads, lounges, etc., during all periods of nonuse. Incandescent lights are to be secured upon leaving a space for any period. Fluorescent lights are to be secured when leaving a space for a period over 10 minutes.
- $\underline{4}$. Lights are to be wired (or rewired where possible) to permit selective use of lighting at occupied work stations without turning on entire banks of lights. Individual pull-chains at each work station are recommended.
- 5. Decorative lighting is clubs and messes is to be minimized. All other decorative lighting for display or other purposes is to be specifically authorized by the Assistant Chief of Staff, Facilities, Marine Corps Base, in accordance with waiver procedures prescribed by paragraph 4e(5)(h).
- $\underline{6}$. Interior security lighting is to be minimized consistent with security requirements. Consideration must be given to the cost-to-benefit ratio of security lighting. Interior security lighting is to be controlled by separate security switches.
 - 7. Exit signs are to be lighted by one 15W bulb.
 - 8. Fluorescent fixtures are to be the reflective type to make best use of available light.
- $\underline{9}$. 40W fluorescent tubes are to be converted to 35W tubes. All light bulbs are to be replaced with lower watt \overline{b} ulbs consistent with illumination standards.
- 10. Overhead lights shall be secured in warehouses and industrial areas except on very overcast days or as required for safety reasons, at the discretion of the shop supervisor, owing to the limited usefulness of such lights for most purposes. Task lighting shall be provided work stations wherever possible to replace oversized overhead lights.

(b) Exterior Lighting

- 1. Exterior lighting is to be held to a minimum.
- $\underline{2}$. Exterior security lights are to be mercury or sodium-vapor type of the smallest possible size. Each installation must be justified in terms of cost-to-benefit ratio, most efficient placement of lights and the type of lights installed.
- $\underline{3}$. Exterior lighting is not permitted during the day. Security lights are to be used only during time of greatest threat to security and are to be turned off when that threat is diminished. Lighting at the Commissary for example, may be secured after about 0600 daily. Timers are to be installed on systems which may be turned off before sunrise and photocells for all-night systems.
 - 4. Fifty percent of all street lighting is to remain secured except in housing areas.
 - Fire alarm boxes are to be lighted by 15W bulbs.
- (c) <u>Lighting Survey</u>. Interior or exterior lighting surveys can be requested via submission of a standard Work Request Form NAVFAC 9-11014/20 (Rev. 2-68) to the Assistant Chief of Staff, Facilities, Marine Corps Base. MCAS(H), NR organizations and their tenants will submit such requests in accordance with BO P11014.1G.
- (5) <u>Water</u>. Water production is currently at near capacity at Marine Corps Base, Camp Lejeune and Marine Corps Air Station(H), New River. Thus, with more new facilities constructed each year, it is imperative to conserve water.
- (a) During annual periods of water shortage, watering of grass shall be terminated; plants and shrubs may be watered once a week, and vehicle washing, unless specifically terminated, will only be permitted providing a hose with a positive shutoff nozzle is used.
- (b) Temperatures for hot water shall not exceed the standards outlined in paragraph 4e(3) above, except where waivers have been granted by the Assistant Chief of Staff, Facilities, Marine Corps Base or his designated representative.
- (c) <u>Water-Saving Devices</u>. The following water-saving devices are mandatory for all facilities at Camp Lejeune and New River, including quarters, and will be provided and installed by Marine Corps Base, Camp Lejeune:
 - 1. All hoses shall be equipped with self-closing nozzles.
 - 2. All flushometer toilets and urinals shall be equipped with a flow-reducer flushometer insert.
- 3. All tank-type commodes shall be equipped with dike inserts to reduce flush volume by one to two gallons. Commodes may alternatively be equipped with a dial-flush system.

- 4. All showers shall be equipped with an approved flow-reducer showerhead to reduce shower water volume by 50%.
- $\underline{5}$. All government-owned washing machines without water level selectors shall be set to reduce rinse volume by \overline{no} more than 4 gallons.
- $\underline{6}$. Hot water faucet valves in all nonfamily quarters sinks will be replaced with automatic shutoff valve mechanisms.

(d) Cooling Water

- 1. One-pass water cooled equipment, including ice machines and air conditioning units, is prohibited. Such equipment is to be replaced or cooling towers and a water recirculation system installed.
 - 2. Cooling systems will be disconnected October through March.

(e) Miscellaneous Electricity Utilization Requirements

- 1. Hot water heaters, except in quarters, shall be secured outside of working hours. Hot water heaters in quarters shall be secured upon vacating quarters and when going on leave by turning off the appropriate circuit breaker.
- $\underline{2}$. Exhaust and circulation fans shall be reduced in motor size to provide the minimum acceptable air flow as determined by Base Maintenance.
- (f) $\underline{\text{Facility Requirements}}$. The following basic facility requirements are necessary to provide for the efficient utilization of all energy forms.
- 1. All air conditioned spaces are to be insulated above the ceiling and, as potential savings warrant, in the walls.
- 2. Windows in air conditioned spaces are to be shielded from the sun's direct rays by reflective sheeting, roof overhang or sun shield. Tinted windows, such as in quarters, are exempt from this requirement. Venetian blinds and/or curtains shall be used wherever possible to further reduce heat gain in air conditioned spaces.
- $\underline{\underline{3}}$. Doors into air conditioned spaces are to have springs or other door closers installed. Where possible, air conditioned spaces should be buffered by anterooms.
- $\underline{4}$. Hot water heaters and boilers are to be fully insulated and all hot water lines lagged. Condensate return lines and cold water lines should also be insulated.
- $\underline{5}$. Facilities are to be zoned to permit easy securing of air conditioning to unused spaces. Ducts should be secured to unused areas. Cross-connects between air conditioned spaces and other spaces should be blocked off.
 - 6. Restricted-range thermostats are to be installed in all air conditioned facilities.
- $\underline{\underline{\mathsf{7}}}$. Timers are to be installed to provide for automatic setback or securing of air conditioning units and other equipment.

(g) Government Vehicles

- $\underline{\text{l. Commercial motor transport assets will be consolidated through scheduling in order to reduce mileage and fuel consumption.}$
- 2. Maximum utilization will be made of the Class B/C pool, thus minimizing dedicated vehicle assignments with \bar{l} n the Class A pool.
- 3. In principle, the smallest, most efficient vehicles shall be assigned to fulfill a transportation requirement.
 - 4. Driver education classes will include instruction on fuel conservation driving techniques.
 - 5. Motor pools must assign mileage reduction goals and monitor results.
 - 6. Fuel accountability shall be strictly monitored and enforced.
- (h) <u>Waivers to Conservation Standards</u>. Temperature standards and utilization requirements established by this Order and higher authority are not intended to supplant bona fide energy requirements established by appropriate authority or dictated by prudent safety and hygienic practices. Requests for waivers to energy standards should be submitted to the Assistant Chief of Staff, Facilities, Marine Corps Base with full justification.

5. Program Management

a. General. In order to achieve the conservation goals directed by higher authority, there will have to be a

solid program and visible and active commitment by all hands. Commitment to conservation goals requires that all participants in the program's progress are aware of the goals, the methods by which they can actively make contributions, and aware that a command program is aggressively supported by the commander. Additionally, the results of significant efforts by units or individuals should be rewarded or otherwise recognized for their own contribution(s). Program accountability goes hand-in-hand with conservation efforts.

- b. <u>Energy Management Officer</u>. The Energy Management Officer, Office of the Assistant Chief of Staff, Facilities, Marine Corps Base serves as the overall program coordinator. As such, he will provide technical assistance or information to tenant commands at Camp Lejeune and the Commanding Officer, Marine Corps Air Station(H), New River, as required. Other responsibilities include, but are not limited to:
 - (1) Monitoring all utilities and energy conservation matters.
 - (2) Continued and aggressive prosecution of the program.
 - (3) Monitor effectiveness of the program.
- (4) Investigate areas in which assigned goals are not accomplished and initiate or recommend corrective action.
- (5) Monitor the progress of all major utility repair or construction projects and any energy conservation projects.
 - (6) Ensure timely submission of reports and project information required by higher authority.
- (7) Conduct command inspections with Marine Corps Base, Camp Lejeune and, upon request, courtesy inspections to tenant commands at Camp Lejeune and Marine Corps Air Station(H), New River.
- c. Command and Organization Energy Conservation Officers. Reference (b) directs that all Marine Corps installations and operating forces (divisions, wings, force service support groups, etc.) shall establish an energy conservation task group at the headquarters level to act in an advisory capacity with direct access to the commander. In order to facilitate the efforts of the task group, an energy conservation officer should be assigned at command, organizational and unit levels. These personnel will manage the dissemination of conservation awareness information, as well as ensure the accountability of subordinate units in complying with a command's program.
- d. <u>Utility and Energy Conservation Committee</u>. The Utility and Energy Conservation Committee is the means by which conservation information will be promulgated and overall energy conservation progress and policies will be reviewed. The Chairman of the committee will be the Assistant Chief of Staff, Facilities, Marine Corps Base. The duties, functions and responsibilities of the Utility and Energy Conservation Committee are discussed in enclosure (3).
- e. Activity Energy Conservation Plan. In conjunction with the Atlantic Division, Naval Facilities Engineering Command, an Activity Energy Conservation Plan has been formulated for Camp Lejeune. The plan was based on surveys conducted in 1975 and 1980. Repair and construction projects were identified which should enable Camp Lejeune and New River to achieve much of the facilities energy reduction goals. Briefly, the plan has provided the technical information necessary for the development of major projects. A few of the significant projects include:
 - (1) Utility Monitoring and Control System (UMACS)
 - (2) Precipitators for the main steam plant at Camp Lejeune (to enable burning of coal).
 - (3) Equipment to optimize the combustion process in the 35 boilers at Camp Lejeune and New River.
 - (4) Enhancement of interior and exterior lighting systems.
 - (5) Blocking windows and adding insulation in 217 major facilities.
 - (6) Repairing and re-insulating 69 miles of steam lines.
 - (7) Architectual and Engineering studies of potential energy conservation projects.
 - (8) Various energy saving projects within Family Housing.
 - f. Utility Monitoring and Control System (UMACS)
 - (1) The UMACS is a computer system which can:
 - (a) Instantaneously display the temperatures of controlled buildings.
- (b) Turn on and shut off heating and air conditioning systems in order to maintain or change building temperatures to reduce electricity or steam load.
 - (c) Control the temperature and chlorine level in swimming pools.
- (2) Ultimately, approximately 300 buildings will be controlled by UMACS. Also planned for inclusion on the system are generators which will control sewage lift stations and water pumps. Two of the most important functions of the system are it's ability to "shed" loads and set back temperatures.

- (a) <u>Load Shedding</u>. Load shedding is the planned and timed shut-off and turn-on of air conditioning systems and other electrical loads during peak electrical demand periods usually in August. This is crucial for several reasons:
- $\underline{\mathbf{1}}$. By spreading the load reduction, shut-down of air conditioning systems is only necessary for a relatively short period of time.
 - 2. Demand charges are reduced to Camp Lejeune.
- $\underline{3}$. The possibility of a shortage of electricity within the electrical grid of Camp Lejeune and New River is reduced.
- (b) <u>Temperature Setback</u>. Temperature setback is the planned and timed reduction of heating temperatures in winter and air conditioner usage during the summer for buildings controlled by UMACS. These reductions or increases are usually accomplished between 2300 and 0400, seven days a week, and 0800 to 1500, Monday through Friday.
 - (c) Enclosure (4) is a list of buildings currently controlled by the UMACS system.
- g. <u>Building Monitors</u>. With over 1930 buildings at Camp Lejeune (exclusive of Family Housing) it will be difficult for commands to manage the measurement of progress of subordinate units. The key to attaining program information and ensuring compliance with applicable directives is building monitors. Charged with the responsibility of monitoring a building's energy consumption and identifying and reporting facility maintenance and repair problems, these individuals are vital to a successful program. The personnel should be assigned in writing. The duties, functions, and responsibilities of building monitors are outlined in enclosure (5).
- h. Facility Temperature Standards Notice. Facility temperature standard notices will be posted prominently in each building. The notice will indicate the maximum heat and minimum cooling temperatures permitted in the building, as well as the name and telephone number of the building monitor and the Command having cognizance over the building. Enclosure (6) is a sample of the standards notice.
- i. Barracks Shutdown. When deployed units vacate billeting, administrative, and maintenance spaces, utility services must be curtailed. Use of billeting spaces by residual unit or other personnel must be consolidated so that large spaces or entire buildings are not heated or cooled for a few people. This should be monitored by command and organization facility Energy Conservation Officers. As a guide, buildings with less than 60% occupancy are considered to be inefficiently used in terms of utility and energy consumption, in particular, heating and cooling. The average barracks cost approximately \$100.00 per day to heat and \$70.00 per day to cool. Where possible, in the above situation, occupants should be moved to other barracks to enable the shut-down of the partially occupied building. This is despite the fact that it will be difficult, if not impossible to retain "unit integrity" until the deployed unit(s) return. The Energy Management Officer, Marine Corps Base (Extensions 3034/2544) should be notified in order to request barracks shutdown.
- j. <u>Utility and Energy Contingencies</u>. Utility and energy supplies can be interrupted due to natural disasters and storms as well as the inability of commercial sources to make fuel deliveries or meet electrical demands. A utility and energy contingency plan will enable available resources to be utilized effectively and efficiently. Enclosure (7) describes how the contingency plan is implemented.
- k. Energy Alert. During periods of peak electrical demands, energy alerts will be declared. The purpose of the Alert is to significantly reduce the electrical demand on the Camp Lejeune/Marine Corps Air Station(H), New River grid during the hours of 1200 to 1700. This will reduce the consumption charges being paid to the electric company, as well as the "demand" charges. Enclosure (8) outlines the procedures for promulgating and actions to be taken on Energy Alert days.
- 1. <u>Command Inspections</u>. Command inspection of an organization's conservation program provides valuable feedback to both the unit commander and higher headquarters. Frequently, through such efforts, formerly reported, but as yet uncorrected discrepancies, can be identified and assistance can be provided by Base Maintenance. Enclosure (9) is a sample of the Command inspection form that will be utilized for conducting command inspections.
- m. Energy Conservation Monitor Teams. To assist the Base Energy Management Officer and the Installation and Logistics Officer, Marine Corps Air Station(H), New River in identifying buildings not in compliance with facility temperature restrictions, energy conservation monitor teams from each command will make periodic visits to key air conditioned and heated buildings. The team will be made up of Base Maintenance personnel. On the first occasion a building is discovered not in compliance with temperature restrictions, a "WARNING" facility discrepancy report will be issued to the unit occupying the building. After the first report, discrepancy reports will be sent to the Command Energy Management Office. Enclosure (10) is a sample of the Facilities Energy Discrepancies Report.
- n. Energy Hotline. Anyone discovering cases of utility or energy waste through defect or negligence should report the information by telephone to the Energy Hotline at 451-2544 during normal working hours. Case of energy waste that pose immediate harm to personnel or damage to facilities or equipment, such as a ruptured steam or water line or fallen electrical wires, should be reported immediately, day or night, to the Emergency Service Desk, Base Maintenance at extensions 3001/3002.
- o. Government Buses. Camp Lejeune and New River areas are served by commercial military buses. The schedules should be prominently displayed on unit bulletin boards and use of the buses should be encouraged for dependents and, where possible, by unit personnel. The schedule is printed as an enclosure to the Globe and Rotorvue on at least a quarterly basis. BO 4650.2 is also a schedule of the Base bus schedule and routes.

- p. <u>Carpool Program</u>. A command carpool program is one of the largest potentials for fuel conservation. In cities and states where carpooling is actively encouraged, dramatic reductions in fuel consumptions are being experienced. Though the nature of military training and operations may not appear to lend themselves well to a carpool program, ingenuity and flexibility on the part of the organization and unit commanders can result in significant fuel savings with a minimum, if any, impact on the organization. In this regard, the most successful programs at Camp Lejeune and New River are those where a commitment to the program is clearly established and where a single office coordinates the program. A complex or sophisticated plan is not necessary. Rather, a simple logbook is easily maintained at the battalion or squadron level.
- 6. <u>Technical Assistance</u>. Technical assistance is available to Commands desiring help in their energy conservation program. For example, an energy survey may be requested for a building(s) in order to determine its' energy conservation efficiency. Such a request should be submitted, in writing, to the Assistant Chief of Staff, Facilities, Marine Corps Base (Attn: Energy Management Officer). For other matters regarding energy conservation, contact the Energy Management Officer at phone extensions 3034/2544.
- 7. Action. Fleet Marine Force commanders, Commanding Officer, Marine Corps Air Station(H), New River, Base organizational commanders and tenants will ensure that the contents of this Order are given wide dissemination within their commands and organizations, upon receipt and at appropriate intervals thereafter.
- 8. Applicability. Having received the concurrence of the Commanding Generals, 2d Marine Division, FMF, 2d Marine Aircraft Wing, FMF and 2d Force Service Support Group (REIN), FMFLant, and the Commanding Officers, Marine Corps Air Station (Helicopter), New River, Naval Regional Medical Center, and Naval Regional Dental Center, this Order is applicable to those Commands.

J. R. FRIDELL Chief of Staff

DISTRIBUTION: A



UNITED STATES MARINE CORPS Marine Corps Base Camp Lejeune, North Carolina 28542

M70

BO 11300.1G Ch 1 FAC/LWB/rfh 25 Oct 1983

PASE ORDER 11300.1G Ch 1

From: Commanding General To: Pistribution List

Subj: Utilities and Energy Management Plan

Encl: (1) New page inserts to the basic Order

1. Purpose. To transmit new page inserts to the basic Order.

2. Action. Remove present letterhead page, page 2, and enclosures 1 thru 10 of the basic Order and replace with corresponding pages contained in the enclosure hereto.

T. M. STOKES, JR. Chief of Staff


PISTRIBUTION: A

		THE RESIDENCE PROPERTY OF THE PARTY OF THE P
INFO	ACT	INIT
gampo alprimana	-	
-		
A . W	vg.cogsprendig	-
	, brisis selected	
A	pacerdo as	
M. 404		
	-	
	ganga tipatanin ganatanin shirin ganatanin shirin ganatanin shirin ganatanin shirin ganatanin shirin	dentity with approximate and the second seco

BMTO INFO ACTINIT

FACILITIES, MAINTENANCE AND CONSERVATION TERMS AND DEFINITIONS

- 1. Area Maintenance Officer. An officer designated by the Area Commander, who is responsible for all area facilities. All routine repair/maintenance requests will be submitted to the Base Maintenance Officer, via the Area Maintenance Officer, except requests for Dining Facilities.
- 2. <u>Building Monitor</u>. An individual assigned the authority to monitor and control building temperatures. Ideally, this individual should be the unit or organization police sergeant so that he has access to facility maintenance and repair work request information.
- 3. <u>Demand Charge</u>. The amount charged by the power company for the maximum kilowatts of energy used by the customer during an interval (15 minutes). The current rate at Camp Lejeune is \$6.37 per KW.
- 4. Enhanced Lighting. The lighting of an area to the required level with the least amount of energy consumed,
- 5. Foot Candle. A measure of illumnance on a surface everywhere one foot from a source of light of one candle and equal to one lumen per square foot.
- 6. Kilowatt (KW). A unit of power equal to 1000 watts. (Example: Turning ten 100 watt light bulbs on.)
- 7. Kilowatt Hour (KWH). A measure of energy consumption that is equal to using 1000 watts of energy for one hour.
- 8. Load Shedding. The turning off of electical loads to limit peak electrical demand,
- 9. $\underline{\text{MBTU}}$. One million British Thermal Units. One BTU is the amount of energy required to increase the temperature of one pound of water, $1^{\circ}F$.
- 10. Peak Demand. The maximum electrical load reached during a billing period. Peak Demand is usually reached during the month of August.
- 11. Peak Shaving. Turning off electrical loads during peak demand periods. This is usually done by intermittently shutting off air conditioner systems aboard base so that no one area of buildings are turned off at one time.
- 12. <u>Temperature Setback</u>. Adjusting the controlled temperature setting to a lower setting usually during unoccupied periods.
- 13. User Charge. The charge applied to a customer for the amount of energy that the customer has consumed.
- 14. $\underline{\mathsf{UMACS}}$. A computerized Utility Monitoring and Control System that is utilized to monitor and control energy consuming equipment, utility plants, and equipment.
- 15. Mobile Electric Power (MEP). Mobile Electric Power is a term describing portable generators usually tactical. These units can be connected to "throw switches" which will enable a building's electrical power needs to be fulfilled by the generator.
- 16. Steam Condensate Lines. These are pipes that return the steam that is "spent" in the heating process to the steam plants. This "spent" steam or steam condensate is actually water of a temperature of 140 to 180 degrees F.
- 17. Steam Traps. These are valve-type devices that prevent live steam from entering condensate lines.
- 18. Emergency Maintenance. Work requiring immediate action to correct or prevent loss or damage to government property, restore disrupted essential services, or eliminate hazards to personnel or property.
- 19. Facility. A separate, individual building, structure or other item of real property improvement, which is subject to separate reporting under the Department of Defense Real Property Inventory.
- 20. Work Request. A form used to request the Maintenance Department to perform work or to prepare a cost estimate of specific work. Customers should use standard Work Request Form NAVFAC 9-11014/20 (Rev. 2-68). Organizations should reconcile their outstanding work requests with the Work Reception Branch of Base Maintenance on a monthly basis.



EARLY TURN-ON OF AIR CONDITIONING

- 1. Centrally or window air conditioned buildings that meet the below criteria will be authorized early turn-on of air conditioning.
 - a. Air conditioning essential to the operation of sensitive equipment.
 - b. Medical and dental facilities.
- c. Facilities which cannot be ventilated by natural or artificial air circulation, including troop housing, especially where no window screens exist.
 - d. Welfare and recreation facilities.
- 2. The below listing of buildings are authorized early turn-on prolonged use of air conditioning:
- a. Communications or Data Processing Facilities (Only those spaces containing communications/data processing equipment will authorized early turn-on)

B1dg M-407B

Bldg 1	Bldg 1005	Bldg 1771	Bldg HP-55
Bldg 24	Bldg 1011	Bldg 4000	Bldg HP-60
Bldg 59	Bldg 1101	Bldg TC-706	Bldg M-130
Bldg 408	Bldg 1108	B1dg BA-102	Bldg M-401
Bldg 518	Bldg 1116	B1dg BB-5	Bldg PT-5
B1dg 751	Bldg 1202	Bldg BB-8	Bldg RR-12
Bldg 780	Bldg 1211	B1dg BB-250	Bldg SH-07
Bldg 817	Bldg 1301	B1dg FC-364	Bldg M-102
Bldg 900	B1dg 1502	Bldg H-17	Bldg M-126
Bldg 1002	B1dg 1606	Bldg HP-53	Bldg M-323

b. Medical and Dental Facilities

B1dg 15	B1dg 900	B1dg FC-460	Bldg H-1
B1dq 36	B1dg AS-302	Bldg FC-313	B1dq M-128
B1dg 65	Bldg BB-10	B1dg G-770	Bldg RR-11
B1dg 421			

c. Exchange Facilities

Bldg	4	B1dg	1207	B1dg	BA-101	B1dg	RR-10
B1dg	84	Bldg	4014	Bldg	BB-245	Bldg	TC-910
Bldg	225	B1dg	AS-232	B1dg	FC-320	B1dg	TT-2461
B1dg	403	B1dg	H-1	B1dg	M-19	B1dg	TT-2477
B1dg	1220	DV .				90	

d. Commissary Stores

B1dg	1200	B1da	2455	B1da	AS-414

e. Printing Plant

Bldg 80 Bldg M-131

f. Hostess House

B1dg 896

g. Bonneyman Bowling Center

B1dg 89

h. Base Theaters

Bldg 19 Bldg 4014

i. Command Club Management System Facilities

Bldg	62	B1dg	2615	B1dg	BB-54	B1dg	M-134
B1dg			BA-115	Bldg	BB-27	B1dg	M-231
Bldg		Bldg	BA-114	B1dg	FC-318	B1dg	M-240
Bldg		Bldg	BA-113	B1dg	G-560	B1dg	RR-49
	524	Bldg	BA-101	B1dg	H-39	B1dg	TC-614
	1006	Bldg	BB-45	Bldg	M-100	B1dg	FC-910
	AS-208	Bldg	AS710	B1dg	AS-901		

ENCLOSURE (2) Ch 1 (25 Oct 1983)

BO 11300.1G 2 JUN 1982

j. MCAS (H), New River Facilities

Bldg AS-130	B1dg AS-320	B1dg AS-570	B1dg AS-3000
B1dg AS-205	B1dg AS-425	B1dg AS-705	Bldg AS-4012
B1dg AS-222	Bldg AS-504	B1dg AS-805	Bldg AS-4106
B1dg AS-226	Bldg AS-518	B1dg AS-822	B1dg AS-4110
B1dg AS-240	B1dg AS-4141	B1dg AS-843	B1dg AS-4120
B1dg AS-312	Bldg AS-4122		

k. Dining Facilities

Bldg	9	Bldg	521	B1dg	BB-7	Bldg	G-640
Bldg	122	Bldg	AS-4012	B1dg	FC-303	Bldg	M-324
B1dg	325	Bldg	BA-103	B1dq	FC-420	Bldg	FC-540
B1dg		,					
-							

1. Buildings with inadequate natural ventilation


Bldg 3	B1dg 63	Bldg 1770	Bldg AS-4158
B1dg 16	B1dg 89	B1dg 2475	B1dg M-4025
Bldg 17	Bldg FC-300		

UTILITY AND ENERGY CONSERVATION COMMITTEE

1. In order to coordinate an effective conservation program at Camp Lejeune and the Marine Corps Air Station (H), New River, the Utility and Enegy Conservation Committee has been established. The Assistant Chief of Staff, Facilities, Marine Corps Base, is designated as Chairman, Energy Conservation Committee. In addition to the Chairman, the Utility Enegy Conservation Committee will be composed of the following representatives:

Assistant Chief of Staff, G-4, 2d Marine Division, FMF
Assistant Chief of Staff, Ops, 2d Force Service Support Group, (REIN), FMFLant
Chairman, Energy Conservation Council, MCAS (H), New River
Commanding Officer, Naval Regional Medical Center
Commanding Officer, Marine Corps Service Support Schools
Commanding Officer, Marine Corps Engineer School
Area Commander, Camp Geiger
Commanding Officer, Support Battalion
Commanding Officer, Headquarters Battalion
Commanding Officer, Rifle Range Detachment
Commanding Officer, Field Medical Service School
Commanding Officer, Infantry Training School
Base Maintenance Officer
Base Motor Transport Officer
Base Special Services Officer
Joint Public Affairs Officer
Director, Family Housing
Superintendent, Camp Lejeune Dependents' Schools

- 2. The Energy Conservation Committee will convene at the call of the Chairman, with administrative support provided by Marine Corps Base.
- 3. The Utility & Energy Conservation Committee will perform the following:
- a. Develop procedures which will assure the optimum utilization of energy resources and maximum savings through energy conservation programs while enabling all commands to continue their operations and training missions without compromise to military readiness, safety or effectiveness.
 - b. Provide implementation guidance directed toward reaching the goals established by references (a) and (b).
- c. Receive utilities and energy conservation comments and suggestions from command and activity representatives and make recommendations to the Assistant Chief of Staff, Facilities.
 - d. Disseminate utility and energy conservation information.
- e. Ensure maximum publicity of energy conservation programs and emphasize individual awareness and participation in the conservation of energy.
- 4. Commanding officers/area commanders will:
 - a. Assign an Energy Conservation Officer in writing.
 - b. Establish and maintain procedures to eliminate waste and abuse of utility and energy systems.
 - c. Establish energy patrols to frequently spot check facilities for execution of the energy conservation measures shown in enclosure (9). It is recommended that patrols be composed of a representative of the area or organization S-4 and one or more unit police sergeants.
 - d. Utilizing the Utilities and Energy Command Inspection Form shown in enclosure (9), take appropriate and corrective action towards individuals who fail to respond to energy conservation guidance.
 - e. Submit suggestions or report problem areas to the Utility and Energy Conservation Committee.
- 5. Director, Family Housing will:
 - a. Establish and maintain procedures to emphasize energy conservation in all family housing units.
- b. Cite occupants who fail to comply with energy conservation guidelines, i.e., outside lights on during the day; tampering with "pre-set" thermostats, etc,.



LIST OF BUILDINGS CURRENTLY CONTROLLED BY THE UTILITY MONITORING AND CONTROL SYSTEM

1. Hadnot Point Buildings


Bldg	10	Bldg	212	B1dg	404	B1dg	506
Bldg		Bldg		Bldg	406	Bldg	507
Bldg		Bldg		B1dg		B1dq	
Bldg		Bldg		Bldg		Bldg	
Bldg		Bldg		Bldg		Bldg	
Bldg		Bldg		Bldg		B1dq	
Bldg		Bldg		B1dq		Bldg	517
Bldg		Bldg		B1dq		Bldg	
Bldg		Bldg		Bldg	420	Bldg	523
Bldg		Bldg		B1dg		Bldg	527
Bldg		Bldg		Bldg			1140
Bldg		B1dg		Bldg		Bldg	1220
Bldg		Bldg		B1dg			1340
Bldg		B1dq		B1dg			

2. French Creek Area Buildings

B1dg FC-304	Bldg FC-310	Bldg FC-413
B1dg FC-305	B1dg FC-311	B1dg FC-414
B1dg FC-306	Bldg FC-411	B1dg FC-415
B1dg FC-309	Bldg FC-412	B1dg FC-416


3. Courthouse Bay Buildings

B1dg BB-250 B1dg BB-255



DUTIES AND RESPONSIBILITIES OF BUILDING MONITORS


- 1. The building monitor is a command, organization, unit or department member who is responsible for monitoring the energy efficient operation of a building(s). The monitor should be assigned in writing. His or her duties should include, but not be limited to, the following:
 - a. Checking the temperature of the building(s) at least twice daily ideally at 0800 and 1300.
 - b. Initiating necessary corrective action to rectify deviations from temperature guidelines.
- c. <u>Identification and reporting</u> of all energy conservation related maintenance and repair work to the police sergeant or S-4. In the case of a building under the cognizance of a civilian organization, this information should be forwarded to the individual who can submit a standard Work Request Form (NAVFAC 9-11014/20 Rev. 2-68) to Base Maintenance.
 - d. Maintain status on all outstanding energy conservation related work requests.
- e. Keep the individual who has cognizance over the building advised of all matters pertaining to the building and its occupants, compliance with temperature guidelines and other energy conservation matters. The most significant areas to monitor are the building's temperature and occupants utility and energy consumption habits. These include, but are not limited to:
 - (1) Length of time it takes for showers (3-5 minutes is advised).
 - (2) Keeping windows and doors closed in winter and summer during heating and air conditioning season.
 - (3) Faucets and lights turned off when not in use.
- f. Ensure that current energy conservation information is prominently displayed within the building. Minimally, this information should include the Facility Temperature Standards Notice, carpool information and a spot where a few weekly home, vehicle or on-base energy conservation tips can be posted.
 - g. Attend organization or department level meetings on energy conservation.



FACILITY TEMPERATURE STANI	DARDS NOTICE (SAMPLE)
MAXIMUM HEATING	TEMPERATURE
MINIMUM COOLING	TEMPERATURE
COMMAND HAVING COGNIZANCE OVER THIS BUILDING:	BUILDING MONITOR:
	TELEPHONE #:

EMERGENCY MAINTENANCE (BASE MAINTENANCE)
TELEPHONE NUMBER 3001 OR 3002

ENCLOSURE (6) Ch 1 (25 Oct 1983)



UTILITY AND ENERGY CONTINGENCY PLAN

1. Electricity

Condition I - 5% reduction goal in electricity. The majority of the reduction will be accomplished by the Utility Monitoring and Control System. It will stagger the shedding of air conditioning loads for brief periods of time, as required. Energy alert procedures will probably be placed in effect.

Condition II - 10% reduction in electricity

- a. Shut down all nonessential loads. Nonessential electrical loads are those not directly affecting the command or organization mission.
- b. Use of comfort air conditioning will terminate except in direct patient care and medical/dental laboratories.
- c. Shut off all lighting near windows and in hallways, except in areas of direct patient care and medical/dental laboratories.
 - d. Shut off coffee pots and reproduction machines.
 - e. Switch to mobile electric/auxiliary power for peak demand periods (1300 1630 week-days).

Condition III - 50% reduction or greater in electricity

- a. Shut down all nonessential loads.
- b. Use of comfort air conditioning will terminate.
- c. Commence shutdown and secure all functions not directly related to communication, security, safety, messing and health.
- d. Secure all building lighting during daylight hours except in direct patient and medical/dental laboratory areas. Absolute minimum mission-essential lighting during the hours of darkness.
 - e. Declaration of energy emergency. This may warrant sending civilian personnel home.
 - f. Switch to mobile electric or auxiliary power.

2. Heat

Condition I - 25% reduction in steam generating capacity

- Priority of steam distribution to messing and medical and dental facilities.
- Heating temperatures in billeting facilities may drop considerably.

Condition II - 50% or greater reduction in steam generating capacity

- Priority of steam distribution to messing and medical and dental facilities.
- Heat may have to be turned off completely.

3. Water

Condition I - Normal water supply

- a. Report and repair all water leaks, including leaking faucets and flush valves to Base Maintenance,
- b. Use water hoses only when equipped with control nozzles.
- c. Use clothers washers and dishwashers with full loads only.
- d. Eliminate continuous flush fixtures.
- e. Convert faucets frequently left open to spring loaded type.
- f. Convert shower heads to low flow rate type.
- g. Wash cars only with buckets.
- h. Restaurants serve water only when requested by customer.

Condition II - Minimal or potential water shortage

a. Stop watering grass.

BO 11300.1G 2 JUN 1982

- b. Water shrubs once a week.
- c. Wash cars only with buckets or hoses with pistol-grip nozzles.
- d. Secure showers without low flow rate shower heads.
- e. Avoid cleaning walks, carports and streets with water.
- f. Publicize shortage.
- g. Wash cars only with buckets.
- h. Restaurants serve water only when requested by customer.
- i. Water outages in quarters will be controlled by amount of water in storage tanks. When water reaches low level point to maintain fire protection pressure, it will be shut off until tank returns to a safe level at which time water will be restored. The fire department will be notified of areas with a water outage. Housing occupants should maintain, a 2-3 gallon water supply during this condition.

Condition III - Moderate water shortage

All of Condition II, plus:

- a. Secure all swimming pools relying heavily on fresh water rather than filtration and chlorination pools.
- b. Set air conditioners with cooling towers to 80°F or higher.

Condition IV - Severe water shortage

All of Conditions II and III, plus:

- a. Notify fire department to conserve water to include minimizing burning-off of weeded areas and use of water for training purposes.
 - b. Stop all washing of vehicles on base, including buses, taxis, motor transport and personal-owned vehicles.
- c. The use of washing machines in Base quarters will be in accordance with the following once-a-week schedule:

Odd numbered days - Quarters with odd numbers

Even numbered days - Quarters with even numbers

- d. Housing and UEPH/OPH occupants maintain strict water conservation practices, such as minimum flushing of toilets and use of showers.
- e. Curtail use of water in industrial areas/process to maximum extent possible. Coordinate mission required high water usable operations with Base Maintenance.
 - f. Set utility conservation patrols for all commands to ensure against water waste.

4. Vehicles

Condition I - 5-20% deficiency in diesel/mogas supplies of moderate duration (less than a month)

a. Immediate reduction in all vehicle utilization (except emergency vehicles) by 20%.

Condition II - 20-50% deficiency in diesel/mogas supplies of moderate duration (more than a month)

- a. Immediate 50% rduction for all administrative vehicles not directly in support of FMF operations,
- b. Immediate 20% reduction of all other vehicles except emergency vehicles.

Condition III - Significant deficiency of diesel/mogas of significant duration

- a. Elimination of all administrative vehicle operations not in direct support of FMF operations,
- b. Immediate 30% reduction for all other vehicles except emergency vehicles.

ENCLOSURE (7) Ch 1 (25 Oct 1983)

ENERGY ALERT PROCEDURES

- 1. An energy alert will be declared by the Base Maintenance Officer when one or more of the below conditions exist:
- a. Temperature conditons are expected to cause the Base's demand and consumption for electricity to exceed its projected consumption peak.
- b. Loss or reduction in commercial electricity due to generation problems, storm conditions or natural disaster.
- 2. Upon declaration of an energy alert, the below procedures or actions will be implemented:
- a. Commands should reduce or eleminate all nonessential electrical loads such as air conditioning, lights and coffee pots.
- b. Mobile Electric Power (Fleet Marine Force generators) or stationary auxiliary power will be activated and brought "on line" at the below locations upon the request of a representative of the Utilities Branch, Base Maintenance.
- c. Air conditioning units controlled by the UMACS will probably be run intermittently in order to reduce the electrical load.
- 3. Below are listed the buildings with auxiliary/mobile electric power systems, the command or unit responsible for equipment operation and a point of contact:

Building	Responsible for Operation	POC/Telephone Number
1	Comm/Elect Officer, MCB	Telephone Officer 2531
2	CG, 2d Marine Division	FacO, 2d MarDiv 2516
3	PMO, MCB	OPS Officer 2555
20	Base Maintenance Officer (BMO)	UtilBrnch, BM 5642
22	вмо	UtilBrnch, BM 5642
59	CG, 2d Force Service Support Group	EngSpt0, 3648
1101	OIC, Consolidated ASC	AsstOIC, 2721
1202	BMO	UtilBrnch, BM 5642
AS-122	CO, MCAS	I & L Office, 455-6506
AS-203	ВМО	UtilBrnch, BM 5642
AS-206	BMO	UtilBrnch, BM 5642
AS-230	BMO	UtilBrnch, BM 5642
AS-302	CO, MCAS	I & L Office, 455-6506
AS-504	CO, MCAS	I & L Office, 455-6506
AS-571	CO, MCAS	I & L Office, 455-6506
AS-606	вмо	UtilBrnch, BM 5642
AS-629	BMO	UtilBrnch, BM 5642
AS-804	CO, MCAS	I & L Office, 455-6506
AS-843	CO, MCAS	I & L Office, 455-6506
AS-849	CO, MCAS	I & L Office, 455-6506
AS-850	BMO	UtilBrnch, BM 5642
AS-1001	BMO	UtilBrnch, BM 5642
AS-2001	BMO	UtilBrnch, BM 5642
AS-3000	CO, MCAS	I & L Office, 455-6506

ENCLOSURE (8) Ch 1 (25 Oct 1983)

BO 11300,1G 2 JUN 1982

Building	Responsible for Operation	POC/Telephone Number
AS-3620	CO, MCAS	I & L Office, 455-6506
AS-4125	ВМО	UtilBrnch, BM 5642
AS-4151	вмо	UtilBrnch, BM 5642
BB-5	CG, 2d MarDiv	Fac0, 2516
BB-7	CO, MCES	S-4 Officer 7410
BB-10	CO, MCES	S-4 Officer 7410
BB-28	CO, MCES	S-4 Officer 7410
G-480	CG, 2d MarDiv	Fac0, 2516
G-640	CG, 2d MarDiv	Fac0, 2516
G-647	CG, 2d MarDiv	Fac0, 2516
G-770	CG, 2d MarDiv	Fac0, 2516
PT-5	Comm/Elect Officer, MCB	OPS Officer 2555
S-47A	BMO	UtilBrnch, BM 5642
TC-704	CG, 2d MarDiv	Fac0, 2516
TC-705	CG, 2d MarDiv	Fac0, 2516
TC-706	CG, 2d MarDiv	Fac0, 2516

- 4. Generator operation equipment.
- a. Start-up and shutdown times of auxiliary generators will be coordinated by a representative of the Utilities Branch, Base Maintenance.
- b. Each major command will provide points of contact for each building with mobile electric/auxiliary power in order to enable the rapid dissemination of operational information.
- c. All fuel costs associated with generator operation will be borne by the Commanding General, Marine Corps Base.
- 5. "Folding" Energy Alert signs will be "opened" (and "closed") at the below locations upon the advice of a representative of the Utilities Branch, Base Maintenance.

Responsible to Open/ Close Sign	POC/Telephone#
Base Maintenance	UtilBrnch, BM 5642
CG, 2d FSSG	EngrSptO, 3456
Director, Family Hsg	EnergyConO, 3657
Director, Family Hsg	EnergyConO, 3657
Area Commander	S-4, MCES 7410
Area Commander	S-4, RRDet 7186
Area Commander	S-4, MCSSS 6142
Area Commander	Deputy for Camp Affairs 0216
CO, MCAS (H), NR	I & L Officer, MCAS (H), NR 455-6506
	Close Sign Base Maintenance CG, 2d FSSG Director, Family Hsg Director, Family Hsg Area Commander Area Commander Area Commander Area Commander

UTILITIES AND ENERGY COMMAND INSPECTION FORM (SAMPLE)

A.	Command Program		
1.	. Is an Energy Conservation Officer assigned in writing?		
2. Mes	Does the command have all pertinent Utility and Energy Conservation Orders/Bulletins/		
	MCO 4100.4A		
	BO 11300.1G		
3.	Does the command have a Unit directive on Utility or Energy Conservation?		
4.	Has the command assigned Energy Conservation Coordinators for Divisions/Sections?		
5.	Has the command assigned Energy Conservation Monitors for each building?		
6.	Management of buildings with command's jurisdiction:		
	a. How many buildings are on the Base Plant Account for this unit?		
	b. How often is each building visited?		
cei	c. Does the command have knowledge of which buildings are heated and cooled (e.g., ntral air, radiator, space heaters)?		
Moi	d. Does the command have knowledge of which buildings are controlled by the Utility mitoring and Control System?		
7.	Carpool Program		
	a. Does the command actively sponsor a carpool program?		
	b. If so, how is it administered?		
8.	Has the command requested Energy Inspections for it's major buildings?		
9.	Are there any incentives or awards for Energy Conservation ideas?		
10	. :Is the command aware of any energy conservation projects scheduled within its area?		
11	. Motor Vehicle Mileage/Fuel Reduction		
	a. Mileage		
	(1) Commercial vehicle mileage this time last year		
	(2) Commercial vehicle mileage thus far this year		
	(3) Percent Change		
	b. Fuel Consumption		
	(1) Commercial vehicle fuel consumption this time last year		
	(2) Commercial vehicle fuel consumption thus far this year		
	(3) Percent Change		
	c. Vehicle Density (Commercial)		
	(1) Number of vehicles this time last year		
	(2) Present Number of vehicles		
	(3) Percent Change		

BO 11300.1G 2 JUN 1832

В.	3. Awareness				
1.	Is Energy Conservation information promulgated?				
	a. How?				
	b. When?				
2.	. Are energy conservation meetings held for principal energy conservation personnel?				
	a. When?				
	b. Are records (MINUTES) kept of meetings?				
3.	. Are temperature standard notices posted in buildings?				
4.	. Are temperature readings taken in buildings?				
	a. How often?				
	b. By whom?				
5.	. Are the 65%/68% and 78% temperature guidelines being adhered to:	A CONTRACT BEING STORE TO THE			
6. as	Are daily temperature records being utilized to identify and resolve such problems malfunctioning or improperly set thermostats or the need for locked thermostats?				
7. to	. Have any minor construction projects been requested/initiated to provide alterations o temperature control systems?				
c.	<u>Accountability</u>				
1.	Are units/sections formally inspected?				
	a. By whom?	4.5			
	b. How often?				
2. mai	Are records of energy conservation inspections and follow-up actions for discrepancies intained by the unit?				
	a. Are warnings/citations or discrepancy notices issued for temperature violations?	and the second second			
	b. How are outstanding work requests reconciled with Base Maintenance?				
	c. Are energy conservation work requests managed separately?				
3. bas	Are Energy Conservation reports required/submitted by subordinate units on a regular usis?				
D.	<u>Heating</u>				
1.	Are thermostats dependable?				
	Properly set?				
	Locked?				
2.	Are heat levels too high in the building?				
3.	Are spaces unnecessily heated?				
4.	Are windows or doors left open?	1.04			
5.	Are areas heated by space heaters where a central heat unit should be used?				
6.					
7.	나는 사람들이 모든 사람들이 아니라 되는 것 같아 아니라 그 그 사람들이 모르게 되었다.				
8.	그렇게 있다면 사람들 점심이 하셨다. 그는 나는 사람이 하시네요. 하는 사람이 되었다. 그리고 있다고 있다. 그 없다.				
gj.					

ENCLOSURE (9) Ch 1 (25 Oct 1983)

E.	<u>Air Conditioning</u>
1.	Are thermostats dependable?
	Properly set?
	Locked?
2.	Are spaces unnecessarily cooled?
3.	Are windows or doors left open?
4.	Is there any unauthorized use of window air conditioners?
5. air	Is this a building with window air conditioners that is a good candidate for a central conditioning system?
6.	Are unoccupied rooms air conditioned?
7.	Could operating fans operate without compressors and adequately cool the building?
F.	Electricity
1.	Lighting
	a. Are light levels correct for the task?
	b. Are unused lights turned off?
	c. Are fixtures, bulbs and tubes clean and operating?
	d. Is switching flexible to permit shutoff of unneeded lights; for example, near windows?
	e. Are show windows lights shut off?
	f. Would timer controls help cut light use?
	g. Are all outdoor lights (except security lights) off?
	h. Are walls and ceilings light-colored? Clean?
	i. Is daylight used as much as possible?
	j. Could more efficient light sources be installed?
	k. Are lamps replaced on a group basis?
2.	Heating
The	Are any electric space heaters being utilized? Use of electric space heaters is not mitted. Heating problems should be resolved through a repair or minor construction project. common condition of cold floors under office desks should be resolved by office personnel ssing more warmly (i.e., slacks, etc,.) rather than through use of electric space heaters.
G.	<u>Water</u>
1.	Is hot handwashing water necessary?
2.	Are there water leaks or drips anywhere?
3.	Can toilet-flushing water be reduced?
4.	Are shower heads fixed at least flow?
5.	Are showers needed?
6.	Are hot water pipes insulated?
7.	Can wash water flow be reduced?

BO 11300.1G 2 JUN 1982


н.	. <u>Structure</u>				
1.	Windows and Outside Doors				
	Do they fit?	* #F6001			
	Are they weatherstripped and caulked?				
	Can automatic door closers be installed?				
	Are glass panes intact and tightly installed?	300			
	Are drapes used effectively?	TO BEAUTION			
	Could vestibules be built?	2107.00			
	Could any windows be replaced by glass blocks?				
	Would double-insulating glass be justified?	A PROPERTY.			
2.	nstruction				
	Is insulation adequate and properly installed?				
	Are all possible uses made of insulation?				
	Would the addition of partitions permit reducing heated spaces?				
echnolis	Are there any cracks to be caulked and sealed?				
I.	fice Operation				
1. exp	e military personnel and government employees instructed to practice energy conservation ally custodial employees?				
2.	e personnel accustomed to dress warmly?				
3.	uld rearrnaging desks vacate space which could be closed off?	History no			
4.	there good thermostat discipline (or are they locked)?				
5.	e unused spaces shut off 100 percent?				
6. long	any rescheduling possible to permit shutdown of heating or cooling equipment for hours?				
7. mean	a study been made to determine where energy is being used, and how much by each				
8. mana	someone is charge of the local program, checking and rechecking and reporting to				
9.	there frequent and regular reminders to personnel about saving energy?	1.0			
10. avai	ve floor displays, window displays and handout pieces on energy savings been made				

ENCLOSURE (9) Ch 1 (25 Oct 1983)

Date

FACILITY ENERGY DISCREPANCY REPORT (SAMPLE)

1.	On a Ro	outine/Return I	nspection of Building	the below discrepancy(cies) was/were noted:
	a. Bui	ilding Temperat	ure		
		Too High			
	<u> </u>	Too Low			
	b. Wir	ndows Open			
	c. Doc	ors Open			
	d. Lig	ghts left on af	ter hours		
	e. Oth	her			
2.	This is	s the	notice.		
say	ed due t	to Utility and		e corrected as expeditiously as pos- in be utilized to buy such things as icks.	
				Signed	





BASE ORDER 7510.6

From: Commanding General To: Distribution List

Subj: FOLLOW-UP ON REPORTS OF AUDIT AND INTERNAL REVIEW ORGANIZATIONS

Ref:

(a) MCO 7510.4B

(b) BO 7540.1B

1. Purpose. To specify and designate the responsibilities for follow-up on recommendations from reports issued by audit and internal review organizations. This Order implements reference (a). For the purpose of this Order, audit and internal review organizations are the Naval Audit Service (NAS), Marine Corps Nonappropriated Fund Audit Service (MCNAFAS), and the Marine Corps Disbursing On-Site Examination Team (MCDOSET).

2. Background

- a. Audit follow-up (the monitoring of actions taken on concurred in recommendations to ensure they are properly implemented) has received more intense scrutiny throughout the Marine Corps as part of the increased emphasis on the elimination of fraud, waste, and abuse. Reference (a) requires a formal, standardized follow-up system to ensure local command responsiveness to audit recommendations and to focus high level attention on any significant recommendations which are either unresolved or not implemented in a timely manner.
- b. Local commands will follow-up on the implementation of all concurred in report recommendations and forward the results to Commandant of the Marine Corps (FDR). The Fiscal Director of the Marine Corps (CMC(FD)) will serve as the Marine Corps central focal point for follow-up on audit/internal review findings and recommendations and provide the Secretary of the Navy with a consolidated report of the Marine Corps activities in this area.
- 3. Policy. Increasing efficiency and improving operating procedures are goals that must be vigorously pursued in all areas of Marine Corps Base. Toward these ends, the command strives to extract the maximum benefit obtainable from audit and internal review reports. Although primary responsibility to promptly implement and follow-up concurred in recommendations rests with the command, principal staff officers shall have responsibility for implementing those recommendations falling within their functional cognizance.

4. Action

- a. Assistant Chief of Staff, Comptroller (Internal Review)
 - (1) Act as a focal point to:
- (a) Serve as the point of contact to receive reports, distribute reports or findings to cognizant staff officers for comments and action, and ensure adequacy and timeliness of responses to the reports.
 - (b) Follow-up to ensure:
- $\underline{1}$. accepted recommendations are acted on in a timely manner and physical evidence of implementation is available,
 - 2. identified savings are validated,

BO 7510.6 18 Mar 1987 THE TOA CHEET

- 3. validated savings are reflected in budget submissions,
- 4. disputed recommendations are promptly and effectively resolved within the command, if possible, and
 - 5. action on delinquent items is initiated.
- (2) Promptly apprise the Commanding General of any instances in which resolution cannot be reached with the audit organization on a disputed recommendation.
- (3) Ensure savings attributable to audit findings and recommendations are highlighted in budget requests.
- (4) Upon request by the Commandant of the Marine Corps (FDR) submit, by message, follow-up implementation status reports on specified recommendations that include, if necessary, any changes in the implementation schedule and any savings resulting from implementation.
- (5) Ensure accounts receivable are established for the recoupment of amounts due the government resulting from concurrence with an audit recommendation indicating funds are to be recovered.
 - b. General Staff Officers/Department Heads/Commanding Officers/Section Heads
 - (1) Ensure recommendations are implemented by the date promised.
- (2) Notify the Assistant Chief of Staff, Comptroller (Internal Review) if a recommendation cannot be implemented so that CMC can be notified.
- (3) Provide assistance when necessary in determining if recommendations have been implemented and providing follow-up implementation status reports to the Commandant of the Marine Corps (FDR).
- 5. Applicability. This Order applies to the follow-up on the implementation of audit and internal review organization report recommendations directed at Marine Corps Base. Processing command responses to audit reports continues to be governed by reference

M. C. HARRINGTON Chief of Staff

DISTRIBUTION: A Less Cat III and IV