Memorandum to File: P-354 81-C-1647 High Explosive Magazine-UCD Inspection


- 1. We need to initiate building no. signs for the magazines.
- 2. A weep hole will be placed at base of metal guard shack on the low side of the concrete slab base.
- 3. Bill Wicks (ROICC Inspector) ask if we would consider getting BMO personnel to install government furnished hasps that have not arrived yet? I told him that until the contract completion date (10 Sept 84) was reached, I felt it was contractors responsibility, but would make you aware of his request.
- 4. Several bolts securing steel frames for rolling doors did not show the ideal 2 to 4 threads after nuts were tightened. Lt. Krugg (ROICC) said that the contractor would tighten them if needed and they would be accepted as noted.
- 5. Gap at corner of metal fascia was noted and will be caulked accordingly.
- 6. Sealer hardener is noted in the contract spec. for "areas specified" no areas, specifically the Magazine slabs, were designated. Should I initiate something to have them sealed?
- 7. Miscellaneous screws were found unsecured in weather stripping these were being corrected as noted.
- 8. Larry Farina (ROICC Elect Inspector) was in process of checking punch items from previous walk through.
- 9. Pending satisfactory completion of ground resistance tests UCD will be dated 10 August 1984.
- 10. Silt fence to the left of entrance gate has been left in place along ditch bank. MSgt Harlan was agreeable to leaving it until vegetation is established and at a later date they will dispose of it.
- 11. Electrical hand hole is holding water. It has been established that high water table in area lends itself to that condition and ROICC feels that contractor has fulfilled his responsibilities.
- 12. Apparent conflict in drawings, regarding photo cells of ext. lights, being worked out between contractor and ROICC office.

Those in attendance:

MSgt Harlan SSgt Beopple Lt. Krugg Larry Farina Bill Wicks M. Briley

R.N. ROUSE Rep - Tim (Prime Contractor)
CAPE FEAR ELECT. PERSONNEL (SUBCONTRACTOR)

M. Brily







3.2 TURF ESTABLISHMENT PERIOD:

- 3.2.1 General: The turf establishment period will be in effect until the turf is mowed three times. A stand of turf is defined as 95 percent for the establishment and proper care of a stand of turf over the entire seeded area.
- 3.2.2 Maintenance During the Establishment Period: Mow the seeded area to an average height of 2 inches whenever the average height of the grass becomes 4 inches. Remove excess clippings, eradicate weeds, water, the growth of grass.

3.3 FINAL ACCEPTANCE:

- 3.3.1 General: Final inspection and acceptance will be at the end of the turf establishment period. Acceptance will be based upon a satisfactory stand of turf as defined in paragraph titled, "TURF
- 3.3.2 Replanting: In areas which do not have a satisfactory stand of turf, replant within planting dates as directed by the Contracting

*** END OF SECTION ***

